

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12: 11-3	*	729	9
STA.		TO STA.		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
• SANGAMON AND CHRISTIAN				

LOCATION OF WORK	CHRISTIAN COUNTY		SANGAMON COUNTY	
	80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE	
	ROADWAY	STRUCTURES	ROADWAY	
	STA. 1415+00.00 TO STA. 1665+04.46	SNO11-2514 SNO11-2515 SNO11-7052 SNO11-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,572	1,538		34
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	82	82		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	19,044.6	12,954.6		6,090.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	27,139.8	18,461.2		8,678.6
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	19,265	12,930		6,335
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	1,904	507		1,397
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	115,163	79,888		35,275
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	15	10		5
50800105	REINFORCEMENT BARS	POUND	132,780		132,780	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	230		230	
54003000	CONCRETE BOX CULVERTS	CU YD	640		640	
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	168		168	
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	450		450	
54011005	PRECAST CONCRETE BOX CULVERTS 10' X 5'	FOOT	336		336	

REVISIONS	
NAME	DATE
NH	4-1-12

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 03/06/2012

DRAWN BY: B.J.D.
CHECKED BY: J.M.M.

Default: 03066CON\proj\work\sheet\0372829-sh1-500.dgn 4/25/2012