CONTRACT NO. 72829

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 75 | 84-12; 11-3 | • | 729 | 46 |
| STA. N/A | | TO STA. N/A | | |
| FED. ROAD DIST. NO. 5 | ILLINOIS | FED. AID PROJECT | | |

• SANGAMON AND CHRISTIAN

## SEEDING SCHEDULE

| STATION / LOCATION | | SEEDING, CLASS 2 (ACRE) | INTERSEEDING, CLASS 5 (MODIFIED) (ACRE) | SEEDING, CLASS 7 (ACRE) | NITROGEN FERTILIZER NUTRIENT • (POUND) | PHOSPHORUS FERTILIZER NUTRIENT • (POUND) | POTASSIUM FERTILIZER NUTRIENT • (POUND) | AGRICULTURAL GROUND LIMESTONE •• (TON) | MULCH, METHOD 2 ••• (ACRE) | SUPPLEMENTAL WATERING (INTERSEEDING, CLASS 5) (UNIT) |
|---|---|---|---|---|---|---|---|---|---|---|
| IL RTE 29 | | | | | | | | | | |
| STA 1412+25.10 TO 1418+00.00 | LT | 0.55 | | | 49 | 49 | 49 | 1.1 | 0.5 | |
| STA 1412+25.10 TO 1418+00.00 | MED | 0.50 | | | 45 | 45 | 45 | 1.0 | 0.5 | |
| STA 1418+00.00 TO 1433+00.00 | LT | 2.8 | 0.2 | 0.2 | 254 | 254 | 254 | 5.6 | 3.0 | 13.4 |
| STA 1418+00.00 TO 1433+00.00 | MED | 1.1 | | | 102 | 102 | 102 | 2.3 | 1.1 | |
| STA 1418+00.00 TO 1433+00.00 | RT | 1.1 | | | 101 | 101 | 101 | 2.2 | 1.1 | |
| STA 1433+00.00 TO 1448+00.00 | LT | 6.9 | 0.6 | 0.6 | 619 | 619 | 619 | 13.7 | 7.5 | 48.4 |
| STA 1433+00.00 TO 1448+00.00 | MED | 1.3 | | | 117 | 117 | 117 | 2.6 | 1.3 | |
| STA 1433+00.00 TO 1448+00.00 | RT | 2.6 | | | 232 | 232 | 232 | 5.2 | 2.6 | |
| STA 1448+00.00 TO 1463+00.00 | LT | 6.7 | 0.5 | 0.6 | 601 | 601 | 601 | 13.4 | 7.2 | 47.7 |
| STA 1448+00.00 TO 1463+00.00 | MED | 1.1 | | | 98 | 98 | 98 | 2.2 | 1.1 | |
| STA 1448+00.00 TO 1463+00.00 | RT | 2.6 | | | 237 | 237 | 237 | 5.3 | 2.6 | |
| STA 1463+00.00 TO 1478+00.00 | LT | 2.3 | | | 205 | 205 | 205 | 4.5 | 2.3 | |
| STA 1463+00.00 TO 1478+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 1463+00.00 TO 1478+00.00 | RT | 2.9 | | | 260 | 260 | 260 | 5.8 | 2.9 | |
| STA 1478+00.00 TO 1493+00.00 | LT | 1.9 | | | 171 | 171 | 171 | 3.8 | 1.9 | |
| STA 1478+00.00 TO 1493+00.00 | MED | 1.1 | | | 98 | 98 | 98 | 2.2 | 1.1 | |
| STA 1478+00.00 TO 1493+00.00 | RT | 2.7 | | | 242 | 242 | 242 | 5.4 | 2.7 | |
| STA 1493+00.00 TO 1508+00.00 | LT | 2.2 | | | 202 | 202 | 202 | 4.5 | 2.2 | |
| STA 1493+00.00 TO 1508+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 1493+00.00 TO 1508+00.00 | RT | 2.3 | | | 208 | 208 | 208 | 4.6 | 2.3 | |
| STA 1508+00.00 TO 1523+00.00 | LT | 3.6 | | | 322 | 322 | 322 | 7.2 | 3.6 | |
| STA 1508+00.00 TO 1523+00.00 | MED | 1.1 | | | 99 | 99 | 99 | 2.2 | 1.1 | |
| STA 1508+00.00 TO 1523+00.00 | RT | 2.5 | | | 223 | 223 | 223 | 5.0 | 2.5 | |
| STA 1523+00.00 TO 1538+00.00 | LT | 3.4 | | | 309 | 309 | 309 | 6.9 | 3.4 | |
| STA 1523+00.00 TO 1538+00.00 | MED | 1.3 | | | 116 | 116 | 116 | 2.6 | 1.3 | |
| STA 1523+00.00 TO 1538+00.00 | RT | 5.0 | | | 454 | 454 | 454 | 10.1 | 5.0 | |
| STA 1538+00.00 TO 1553+00.00 | LT | 1.9 | | | 171 | 171 | 171 | 3.8 | 1.9 | |
| STA 1538+00.00 TO 1553+00.00 | MED | 1.1 | | | 100 | 100 | 100 | 2.2 | 1.1 | |
| STA 1538+00.00 TO 1553+00.00 | RT | 2.0 | | | 182 | 182 | 182 | 4.1 | 2.0 | |
| STA 1553+00.00 TO 1568+00.00 | LT | 1.9 | | | 172 | 172 | 172 | 3.8 | 1.9 | |
| STA 1553+00.00 TO 1568+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 1553+00.00 TO 1568+00.00 | RT | 1.8 | | | 158 | 158 | 158 | 3.5 | 1.8 | |
| STA 1568+00.00 TO 1583+00.00 | LT | 2.3 | | | 209 | 209 | 209 | 4.6 | 2.3 | |
| STA 1568+00.00 TO 1583+00.00 | MED | 1.3 | | | 115 | 115 | 115 | 2.6 | 1.3 | |
| STA 1568+00.00 TO 1583+00.00 | RT | 2.1 | | | 189 | 189 | 189 | 4.2 | 2.1 | |
| STA 1583+00.00 TO 1598+00.00 | LT | 2.2 | 1.0 | 0.4 | 196 | 196 | 196 | 4.4 | 2.6 | 90.8 |
| STA 1583+00.00 TO 1598+00.00 | MED | 1.1 | | | 98 | 98 | 98 | 2.2 | 1.1 | |
| STA 1583+00.00 TO 1598+00.00 | RT | 1.8 | | | 164 | 164 | 164 | 3.6 | 1.8 | |
| STA 1598+00.00 TO 1613+00.00 | LT | 6.4 | 1.6 | 0.6 | 575 | 575 | 575 | 12.8 | 7.0 | 135.5 |
| STA 1598+00.00 TO 1613+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 1598+00.00 TO 1613+00.00 | RT | 2.1 | | | 187 | 187 | 187 | 4.2 | 2.1 | |
| STA 1613+00.00 TO 1628+00.00 | LT | 5.5 | 1.3 | 0.6 | 495 | 495 | 495 | 11.0 | 6.1 | 110.4 |
| STA 1613+00.00 TO 1628+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 1613+00.00 TO 1628+00.00 | RT | 2.1 | | | 189 | 189 | 189 | 4.2 | 2.1 | |
| STA 1628+00.00 TO 1643+00.00 | LT | 2.8 | 1.4 | 0.6 | 250 | 250 | 250 | 5.6 | 3.3 | 125.5 |
| STA 1628+00.00 TO 1643+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 1628+00.00 TO 1643+00.00 | RT | 2.1 | | | 188 | 188 | 188 | 4.2 | 2.1 | |
| STA 1643+00.00 TO 1658+00.00 | LT | 2.6 | 1.4 | 0.6 | 235 | 235 | 235 | 5.2 | 3.2 | 123.3 |
| STA 1643+00.00 TO 1658+00.00 | MED | 1.1 | | | 98 | 98 | 98 | 2.2 | 1.1 | |
| STA 1643+00.00 TO 1658+00.00 | RT | 2.0 | | | 176 | 176 | 176 | 3.9 | 2.0 | |
| STA 1658+00.00 TO 1665+04.46 | LT | 0.9 | 1.1 | 0.3 | 82 | 82 | 82 | 1.8 | 1.2 | 98.1 |
| STA 1658+00.00 TO 1665+04.46 | MED | 0.6 | | | 55 | 55 | 55 | 1.2 | 0.6 | |
| STA 1658+00.00 TO 1665+04.46 | RT | 1.0 | | | 89 | 89 | 89 | 2.0 | 1.0 | |
| STA 0+00.00 TO 8+00.00 | LT | 1.1 | 1.1 | 0.3 | 101 | 101 | 101 | 2.2 | 1.4 | 98.5 |
| STA 0+00.00 TO 8+00.00 | MED | 0.7 | | | 63 | 63 | 63 | 1.4 | 0.7 | |
| STA 0+00.00 TO 8+00.00 | RT | 1.1 | | | 100 | 100 | 100 | 2.2 | 1.1 | |
| STA 8+00.00 TO 23+00.00 | LT | 2.2 | 2.1 | 0.6 | 195 | 195 | 195 | 4.3 | 2.7 | 185.9 |
| STA 8+00.00 TO 23+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 8+00.00 TO 23+00.00 | RT | 2.1 | | | 189 | 189 | 189 | 4.2 | 2.1 | |
| STA 23+00.00 TO 38+00.00 | LT | 1.9 | 2.3 | 0.6 | 175 | 175 | 175 | 3.9 | 2.5 | 198.9 |
| STA 23+00.00 TO 38+00.00 | MED | 1.1 | | | 98 | 98 | 98 | 2.2 | 1.1 | |
| STA 23+00.00 TO 38+00.00 | RT | 1.8 | | | 163 | 163 | 163 | 3.6 | 1.8 | |
| STA 38+00.00 TO 53+00.00 | LT | 2.2 | 2.0 | 0.6 | 195 | 195 | 195 | 4.3 | 2.7 | 178.1 |
| STA 38+00.00 TO 53+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 38+00.00 TO 53+00.00 | RT | 1.8 | | | 166 | 166 | 166 | 3.7 | 1.8 | |
| STA 53+00.00 TO 68+00.00 | LT | 2.0 | 1.0 | 0.6 | 179 | 179 | 179 | 4.0 | 2.6 | 87.5 |
| STA 53+00.00 TO 68+00.00 | MED | 1.3 | | | 117 | 117 | 117 | 2.6 | 1.3 | |
| STA 53+00.00 TO 68+00.00 | RT | 2.1 | | | 189 | 189 | 189 | 4.2 | 2.1 | |
| STA 68+00.00 TO 83+00.00 | LT | 2.0 | 0.9 | 0.6 | 179 | 179 | 179 | 4.0 | 2.6 | 76.4 |
| STA 68+00.00 TO 83+00.00 | MED | 1.1 | | | 99 | 99 | 99 | 2.2 | 1.1 | |
| STA 68+00.00 TO 83+00.00 | RT | 2.3 | | | 209 | 209 | 209 | 4.6 | 2.3 | |
| STA 83+00.00 TO 98+00.00 | LT | 1.7 | 1.1 | 0.6 | 151 | 151 | 151 | 3.4 | 2.2 | 92.5 |
| STA 83+00.00 TO 98+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 83+00.00 TO 98+00.00 | RT | 1.9 | | | 171 | 171 | 171 | 3.8 | 1.9 | |
| STA 98+00.00 TO 113+00.00 | LT | 1.4 | 0.9 | 0.5 | 123 | 123 | 123 | 2.7 | 1.9 | 74.8 |
| STA 98+00.00 TO 113+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 98+00.00 TO 113+00.00 | RT | 1.8 | | | 160 | 160 | 160 | 3.5 | 1.8 | |
| STA 113+00.00 TO 128+00.00 | RT | 2.2 | | | 194 | 194 | 194 | 4.3 | 2.2 | |
| STA 113+00.00 TO 128+00.00 | MED | 1.3 | | | 118 | 118 | 118 | 2.6 | 1.3 | |
| STA 128+00.00 TO 143+00.00 | RT | 0.3 | | | 30 | 30 | 30 | 0.7 | 0.3 | |
| STA 128+00.00 TO 143+00.00 | MED | 0.6 | | | 52 | 52 | 52 | 1.2 | 0.6 | |
| STA 143+00.00 TO 144+00.00 | MED | 0.1 | | | 6 | 6 | 6 | 0.1 | 0.1 | |
| TR 81 | | | | | | | | | | |
| STA 91+25.00 TO 97+91.48 | | 1.0 | | | 92 | 92 | 92 | 2.0 | 1.0 | |
| STA 101+29.54 TO 104+50.00 | | 0.5 | | | 43 | 43 | 43 | 1.0 | 0.5 | |
| TR 73 (INCLUDES CONNECTOR) | | | | | | | | | | |
| STA 180+00.00 TO 198+53.05 | | 3.5 | | | 311 | 311 | 311 | 6.9 | 3.5 | |
| STA 201+43.19 TO 204+50.00 | | 0.4 | | | 39 | 39 | 39 | 0.9 | 0.4 | |
| CH 21 | | | | | | | | | | |
| STA 396+50.00 TO 398+76.46 | | 0.3 | | | 26 | 26 | 26 | 0.6 | 0.3 | |
| STA 401+44.88 TO 405+25.00 | | 0.4 | | | 35 | 35 | 35 | 0.8 | 0.4 | |
| CH 23 | | | | | | | | | | |
| STA 479+36.32 TO 498+77.69 | | 4.2 | | | 374 | 374 | 374 | 8.3 | 4.2 | |
| STA 501+21.76 TO 508+92.65 | | 1.6 | | | 147 | 147 | 147 | 3.3 | 1.6 | |
| TR 88 | | | | | | | | | | |
| STA 584+74.00 TO 598+75.00 | | 5.3 | | | 473 | 473 | 473 | 10.5 | 5.3 | |
| STA 601+15.00 TO 605+25.00 | | 0.6 | | | 56 | 56 | 56 | 1.2 | 0.6 | |
| TR 74/63 N (INCLUDES CONNECTOR) | | | | | | | | | | |
| STA 94+75.00 TO 106.00.00 | | 2.2 | | | 197 | 197 | 197 | 4.4 | 2.2 | |
| TR 74/63 S (INCLUDES CONNECTOR) | | | | | | | | | | |
| STA 94+75.00 TO 108+75.00 | | 2.7 | | | 241 | 241 | 241 | 5.4 | 2.7 | |
| TR 321/486 (INCLUDES CONNECTOR) | | | | | | | | | | |
| STA 93+25.00 TO 106+25.00 | | 2.1 | | | 189 | 189 | 189 | 4.2 | 2.1 | |
| TR 299 | | | | | | | | | | |
| STA 890+39.00 TO 898+54.71 | | 0.9 | | | 77 | 77 | 77 | 1.7 | 0.9 | |
| STA 901+11.48 TO 908+00.00 | | 1.5 | | | 132 | 132 | 132 | 2.9 | 1.5 | |
| OUTLET 1 | | 1.8 | | | 163 | 163 | 163 | 3.6 | 1.8 | |
| NOMINAL (WINTER SHUTDOWN) | | | | 235 | 0 | 0 | 0 | 0.0 | 235.2 | |
| TOTALS | | 188 | 20 | 244 | 16,932 | 16,932 | 16,932 | 376.3 | 432 | 1,786 |

•NITROGEN, PHOSPHORUS, AND POTASSIUM FERTILIZER NUTRIENTS FOR SEEDING, CLASS 2 ONLY
••AGRICULTURAL GROUND LIMESTONE APPLIED TO SEEDING, CLASS 2 ONLY
•••MULCH, METHOD 2 FOR SEEDING CLASS 2 AND CLASS 7 ONLY

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SEEDING

SCALE: N/A
DRAWN BY: K.E.U.
DATE: 03/06/2012
CHECKED BY: J.M.M.

SHT03
L:\IDOT\Q30660\dr-aw\sheets\D672829-sht-Schedule.dgn
3/30/2012