

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	•	729	48
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
• SANGAMON AND CHRISTIAN				

**AGGREGATE SCHEDULE**

STATION / LOCATION				SUBBASE GRANULAR MATERIAL, TYPE C	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	AGGREGATE BASE COURSE, TYPE A 12"	AGGREGATE BASE COURSE, TYPE A 10"	AGGREGATE SHOULDERS, TYPE A	AGGREGATE SHOULDERS, TYPE A 8"
				(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)
IL RTE 29									
STA 1403+00.00	TO	1418+00.00	LT	128.4				111.4	135.1
STA 1403+00.00	TO	1418+00.00	RT					92.9	184.8
STA 1418+00.00	TO	1433+00.00	LT	579.8				344.6	250.1
STA 1418+00.00	TO	1433+00.00	RT	297.7				205.4	102.6
STA 1433+00.00	TO	1448+00.00	LT	628.3				371.0	299.0
STA 1433+00.00	TO	1448+00.00	RT	654.2				365.5	332.1
STA 1448+00.00	TO	1463+00.00	LT	563.5				345.7	221.5
STA 1448+00.00	TO	1463+00.00	RT	562.9				342.8	213.1
STA 1463+00.00	TO	1478+00.00	LT	640.5				368.2	325.7
STA 1463+00.00	TO	1478+00.00	RT	642.0				361.2	333.3
STA 1478+00.00	TO	1493+00.00	LT	557.7				336.2	215.6
STA 1478+00.00	TO	1493+00.00	RT	559.3				344.6	213.7
STA 1493+00.00	TO	1508+00.00	LT	654.2				361.2	332.1
STA 1493+00.00	TO	1508+00.00	RT	647.3				370.9	324.0
STA 1508+00.00	TO	1523+00.00	LT	646.3				353.2	223.0
STA 1508+00.00	TO	1523+00.00	RT	638.6				358.3	235.0
STA 1523+00.00	TO	1538+00.00	LT	637.2				365.7	332.1
STA 1523+00.00	TO	1538+00.00	RT	624.2				370.8	288.9
STA 1538+00.00	TO	1553+00.00	LT	562.3				345.8	213.3
STA 1538+00.00	TO	1553+00.00	RT	581.2				344.6	265.3
STA 1553+00.00	TO	1568+00.00	LT	642.0				366.4	333.3
STA 1553+00.00	TO	1568+00.00	RT	642.0				368.2	333.3
STA 1568+00.00	TO	1583+00.00	LT	642.0				366.4	333.3
STA 1568+00.00	TO	1583+00.00	RT	630.0				363.5	269.5
STA 1583+00.00	TO	1598+00.00	LT	529.6				339.3	1,379.4
STA 1583+00.00	TO	1598+00.00	RT	565.7				341.8	239.6
STA 1598+00.00	TO	1613+00.00	LT	648.8				368.2	333.3
STA 1598+00.00	TO	1613+00.00	RT	642.0				368.2	333.3
STA 1613+00.00	TO	1628+00.00	LT	656.9				368.3	333.4
STA 1613+00.00	TO	1628+00.00	RT	641.8				368.1	333.3
STA 1628+00.00	TO	1643+00.00	LT	659.2				368.9	333.7
STA 1628+00.00	TO	1643+00.00	RT	640.6				367.5	333.0
STA 1643+00.00	TO	1658+00.00	LT	565.2				345.2	216.3
STA 1643+00.00	TO	1658+00.00	RT	563.1				345.5	217.6
STA 1658+00.00	TO	1665+04.46	LT	301.5				172.9	156.5
STA 1658+00.00	TO	1665+04.46	RT	301.5				172.4	156.5
STA 0+00.00	TO	8+00.00	LT	342.4				196.4	177.8
STA 0+00.00	TO	8+00.00	RT	342.4				193.4	177.8
STA 8+00.00	TO	23+00.00	LT	428.7				368.2	333.3
STA 8+00.00	TO	23+00.00	RT	642.0				368.2	333.3
STA 23+00.00	TO	38+00.00	LT	635.7				357.4	216.3
STA 23+00.00	TO	38+00.00	RT	561.4				345.9	216.4
STA 38+00.00	TO	53+00.00	LT	641.1				367.8	333.1
STA 38+00.00	TO	53+00.00	RT	642.9				368.6	333.5
STA 53+00.00	TO	68+00.00	LT	642.3				368.3	333.4
STA 53+00.00	TO	68+00.00	RT	637.4				368.1	305.3
STA 68+00.00	TO	83+00.00	LT	562.8				345.9	216.3
STA 68+00.00	TO	83+00.00	RT	571.4				344.2	244.4
STA 83+00.00	TO	98+00.00	LT	641.9				368.2	333.3
STA 83+00.00	TO	98+00.00	RT	642.0				368.2	333.3
STA 98+00.00	TO	113+00.00	LT	299.6				216.7	236.4
STA 98+00.00	TO	113+00.00	RT	642.0				363.2	333.3
STA 113+00.00	TO	128+00.00	LT					21.4	38.8
STA 113+00.00	TO	128+00.00	RT	637.8				366.0	332.3
STA 128+00.00	TO	143+00.00	LT					96.5	104.8
STA 128+00.00	TO	143+00.00	RT	84.9				96.2	85.2
STA 143+00.00	TO	158+00.00	LT					25.4	23.7
STA 143+00.00	TO	158+00.00	RT					49.9	46.1

STATION / LOCATION				SUBBASE GRANULAR MATERIAL, TYPE C	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	AGGREGATE BASE COURSE, TYPE A 12"	AGGREGATE BASE COURSE, TYPE A 10"	AGGREGATE SHOULDERS, TYPE A	AGGREGATE SHOULDERS, TYPE A 8"
				(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)
TR 81									
STA 91+67.21	TO	99+36.87						2,885	29.8
STA 100+63.18	TO	104+04.87						1,463	39.0
TR 73									
STA 180+00.00	TO	199+38.99						6,385	169.9
STA 200+61.02	TO	203+88.47						1,386	36.6
TR 73 CONNECTOR									
STA 294+76.65	TO	299+87.58						2,112	26.6
CH 21									
STA 396+75.60	TO	399+39.00						1,285	35.1
STA 400+61.57	TO	404+50.00						1,719	42.5
CH 23									
STA 479+36.32	TO	499+39.00						7,699	253.3
STA 500+61.00	TO	508+52.37						3,143	88.8
BOX CULVERT CROSSING AT MASONIC DR.									
								144	
TR 88									
STA 584+74.00	TO	599+39.00							184.4
STA 600+61.00	TO	604+95.01							51.6
TR 74/63 CONNECTOR									
STA 696+93.00	TO	699+39.00						1,690	43.0
STA 700+61.00	TO	703+08.59						1,670	41.6
TR 74/63 N									
STA 95+47.13	TO	105+40.83						3,209	15.0
TR74/63 S									
STA 95+29.07	TO	108+44.94						4,288	16.4
TR 486 CONNECTOR									
STA 800+61.00	TO	801+80.50						1,140	25.0
TR 321/486									
STA 93+56.31	TO	106+05.38						4,128	33.0
TR 299									
STA 890+39.89	TO	899+39.00						3,716	24.1
STA 900+61.00	TO	907+67.03						7,268	43.7
ENTRANCE @ STA. 112+40.49									
								496	
MOT STAGE 1 (Subject to Change)									
TR 299 INTERSECTION						254			
MOT STAGE 2 (Subject to Change)									
TR 81 INTERSECTION						253			
TR 73 INTERSECTION						616	81		
CH 21 INTERSECTION						616			
CH 23 INTERSECTION						616			
TR 88 INTERSECTION						616			
TR 74/63 INTERSECTION						254			
TR 321/486 INTERSECTION						253			
TR 299 INTERSECTION						254			
MOT STAGE 3 (Subject to Change)									
TR 81 INTERSECTION						427			
TR 74/63 INTERSECTION						383			
TR 321/486 INTERSECTION						323			
FOR USE WITH TEMPORARY PAVEMENT									
IL. RTE. 29 (MOT STAGE 1)									
STA. 1406+23.99 TO 1413+25.53					1,149				30.3
STA. 56+16.50 TO 66+42.85					2,742				799.8
STA. 136+50.00 TO 144+00.00					3,051				
STA 152+23.24 TO 154+19.78					1,539		1,016		299.5
TOTALS				29,676.7	8,481	4,865	56,922	19,044.6	19,265

SHT05  
L:\N001\030600\Draw\Sheets\0672829-sht-Schedule.dgn  
3/30/2012

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**  
AGGREGATE

SCALE: N/A  
DATE: 03/06/2012

DRAWN BY: K.E.J.  
CHECKED BY: J.M.M.

**SCHEDULE OF QUANTITIES: IL. RTE. 29**