

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	•	729	49
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
• SANGAMON AND CHRISTIAN				

**IL. RTE. 29 PAVING SCHEDULE**

STATION / LOCATION				• HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13-3/4"	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	HOT-MIX ASPHALT SHOULDERS, 2"	HOT-MIX ASPHALT SHOULDERS, 8"	BITUMINOUS MATERIALS (PRIME COAT)	• MATERIAL TRANSFER DEVICE	
STATION	TO	STATION	SIDE	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	
<b>STAGE 1</b>										
IL RTE 29										
TEMPORARY SOUTH TRANSITION PAVEMENT					1,011			2.0		
TEMPORARY NORTH TRANSITION PAVEMENT					2,442			4.8		
TEMPORARY CROSSOVER AT TR 466					3,051			6.0		
TEMPORARY PAVEMENT AT TR 291					1,418			2.8		
66+42.85	TO	68+00.00	LT	420			245	0.9	100.0	
68+00.00	TO	83+00.00	LT	5,164			1,905	8.7	952.0	
83+00.00	TO	98+00.00	LT	4,000			2,333	8.4	952.0	
98+00.00	TO	105+00.00	LT	1,867			1,089	3.9	444.3	
<b>STAGE 1 SUB-TOTALS</b>				<b>11,450</b>	<b>7,922</b>	<b>0</b>	<b>5,572</b>	<b>37.5</b>	<b>2,448.2</b>	
<b>STAGE 2</b>										
IL RTE 29										
1424+00.00	TO	1433+00.00	RT	3,578			943	5.3	571.2	
1433+00.00	TO	1448+00.00	LT	3,088			1,804	6.5	735.0	
1433+00.00	TO	1448+00.00	RT	3,972			2,313	8.3	945.3	
1448+00.00	TO	1463+00.00	LT	5,283			1,950	8.9	952.0	
1448+00.00	TO	1463+00.00	RT	5,242			1,913	8.7	952.0	
1463+00.00	TO	1478+00.00	LT	4,025			2,315	8.4	952.0	
1463+00.00	TO	1478+00.00	RT	4,000			2,333	8.4	952.0	
1478+00.00	TO	1493+00.00	LT	5,249			1,900	8.7	952.0	
1478+00.00	TO	1493+00.00	RT	5,311			1,916	8.8	952.0	
1493+00.00	TO	1508+00.00	LT	3,972			2,313	8.3	945.3	
1493+00.00	TO	1508+00.00	RT	4,041			2,353	8.5	961.8	
1508+00.00	TO	1523+00.00	LT	4,644			2,282	8.9	952.0	
1508+00.00	TO	1523+00.00	RT	4,698			2,320	9.0	952.0	
1523+00.00	TO	1538+00.00	LT	3,974			2,315	8.3	945.7	
1523+00.00	TO	1538+00.00	RT	4,388			2,211	8.5	952.0	
1538+00.00	TO	1553+00.00	LT	5,260			1,937	8.8	952.0	
1538+00.00	TO	1553+00.00	RT	4,894			2,060	8.7	952.0	
1553+00.00	TO	1568+00.00	LT	4,000			2,333	8.4	952.0	
1553+00.00	TO	1568+00.00	RT	4,000			2,333	8.4	952.0	
1568+00.00	TO	1583+00.00	LT	4,000			2,333	8.4	952.0	
1568+00.00	TO	1583+00.00	RT	4,303			2,256	8.5	952.0	
1583+00.00	TO	1598+00.00	LT	5,563			1,766	8.8	952.0	
1583+00.00	TO	1598+00.00	RT	5,189			1,979	8.8	952.0	
1598+00.00	TO	1613+00.00	LT	4,000			2,333	8.4	952.0	
1598+00.00	TO	1613+00.00	RT	4,000			2,333	8.4	952.0	
1613+00.00	TO	1625+80.52	LT	3,415			1,992	7.2	812.7	
1613+00.00	TO	1628+00.00	RT	3,999			2,333	8.4	951.7	
1628+00.00	TO	1643+00.00	RT	3,992			2,328	8.4	950.2	
1643+00.00	TO	1658+00.00	RT	5,200			2,090	9.1	952.0	
1658+00.00	TO	1665+04.46	RT	1,879			1,191	4.1	447.1	
0+00.00	TO	8+00.00	RT	2,133			1,244	4.5	507.7	
8+00.00	TO	23+00.00	RT	4,000			2,333	8.4	952.0	
23+00.00	TO	38+00.00	RT	5,190			1,896	8.7	952.0	
38+00.00	TO	53+00.00	RT	4,005			2,337	8.4	953.1	
53+00.00	TO	68+00.00	RT	4,148			2,255	8.4	952.0	
68+00.00	TO	83+00.00	LT	97			25	0.1	0.0	
68+00.00	TO	83+00.00	RT	5,114			1,994	8.8	952.0	
83+00.00	TO	98+00.00	RT	4,000			2,333	8.4	952.0	
98+00.00	TO	113+00.00	RT	4,000			2,333	8.4	952.0	
113+00.00	TO	128+00.00	RT	3,977			2,317	8.3	946.6	
128+00.00	TO	143+00.00	RT	530			308	1.1	126.0	
<b>STAGE 2 SUB-TOTALS</b>				<b>166,351</b>	<b>0</b>	<b>0</b>	<b>82,158</b>	<b>319.9</b>	<b>35,551.5</b>	
<b>STAGE 3</b>										
IL RTE 29										
1403+00.00	TO	1418+00.00	LT	800			137	467	1.7	190.4
1403+00.00	TO	1418+00.00	RT				335		0.1	0.0
1418+00.00	TO	1433+00.00	LT	5,048				2,034	8.8	952.0
1418+00.00	TO	1433+00.00	RT	94			34	26	0.2	0.0
1433+00.00	TO	1436+50.00	LT	1,189				431	2.0	222.1
1625+80.52	TO	1628+00.00	LT	586				342	1.2	139.6
1628+00.00	TO	1643+00.00	LT	4,008				2,339	8.4	953.8
1643+00.00	TO	1658+00.00	LT	5,315				1,913	8.8	952.0
1643+00.00	TO	1658+00.00	RT	120				24	0.2	0.0

STATION / LOCATION				• HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13-3/4"	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	HOT-MIX ASPHALT SHOULDERS, 2"	HOT-MIX ASPHALT SHOULDERS, 8"	BITUMINOUS MATERIALS (PRIME COAT)	• MATERIAL TRANSFER DEVICE
STATION	TO	STATION	SIDE	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)
1658+00.00	TO	1665+04.46	LT	1,879			1,096	3.9	447.1
0+00.00	TO	8+00.00	LT	2,133			1,244	4.5	507.7
8+00.00	TO	23+00.00	LT	4,000			2,333	8.4	952.0
23+00.00	TO	38+00.00	LT	4,713			2,305	9.0	952.0
23+00.00	TO	38+00.00	RT	120			24	0.2	0.0
38+00.00	TO	53+00.00	LT	3,995			2,330	8.4	950.9
53+00.00	TO	66+42.85	LT	3,581			2,089	7.5	852.3
98+00.00	TO	113+00.00	LT				163		0.1
113+00.00	TO	128+00.00	LT				78		0.0
128+00.00	TO	143+00.00	LT				375		0.1
128+00.00	TO	143+00.00	RT				311		0.1
143+00.00	TO	158+00.00	LT				44		0.0
143+00.00	TO	158+00.00	RT				427		0.2
<b>STAGE 3 SUB-TOTALS</b>				<b>37,582</b>	<b>0</b>	<b>1,904</b>	<b>18,998</b>	<b>73.9</b>	<b>8,072.0</b>
<b>TOTALS</b>				<b>215,383</b>	<b>7,922</b>	<b>1,904</b>	<b>106,728</b>	<b>431.2</b>	<b>46,072.0</b>

• FINAL SURFACE LIFT TO BE PLACED IMMEDIATELY PRIOR TO PROJECT COMPLETION

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES IL. RTE. 29 PAVING

SCALE: N/A  
DATE: 03/06/2012

DRAWN BY: K.E.J.  
CHECKED BY: J.M.M.

**SCHEDULE OF QUANTITIES: IL. RTE. 29**