

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	•	729	52
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
• SANGAMON AND CHRISTIAN				

**DRAINAGE SCHEDULE**

STATION / LOCATION	PIPE CULVERTS, CLASS A, TYPE 1				PIPE CULVERTS CLASS A, TYPE 2				PIPE CULVERTS CLASS D, TYPE 1				PIPE CULVERTS CLASS D, TYPE 2	PRECAST REINFORCED CONCRETE FLARED END SECTIONS				METAL END SECTIONS				PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	PRECAST REINF. CONCRETE F.E.S. - ELLIPTICAL, EQ. ROUND-SIZE 24"	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	PRECAST REINF. CONCRETE F.E.S. - ELLIPTICAL, EQ. ROUND-SIZE 36"	MANHOLES, TYPE A, 5' - DIAMETER, WITH MEDIAN INLET (604106)	MEDIAN INLET (604106)	INLET, TYPE A WITH MEDIAN INLET (604101)	INLET BOX, STANDARD 542511	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	TRENCH BACKFILL	CONTROLLED LOW-STRENGTH MATERIAL	
	15" FT.	18" FT.	24" FT.	36" FT.	12" FT.	18" FT.	24" FT.	36" FT.	12" FT.	15" FT.	18" FT.	24" FT.	24" FT.	15" EACH	18" EACH	24" EACH	36" EACH	12" EACH	15" EACH	18" EACH	24" EACH	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	CU. YD.	CU. YD.	
IL RTE 29																																	
1424+50.00							80.89									1																38.93	
1437+50.00							176.29									2																142.48	
1453+50.00							174.06									2																132.64	
1470+50.00							84.20									1																57.75	
1471+25.53	RT						139.00									1																	
1472+76.49	RT															1																	
1478+37.48	LT			52.75												1																	
1479+00.27					3.99																												
1479+02.23	LT															1											1						
1489+00.00							77.09									1																	33.81
1497+00.00							81.24									1																	43.38
1498+14.31	LT															1																	
1499+23.97	LT			95.48												1																	
1507+00.00					4.35																						1						
1511+21.61	LT						126.70									1																	
1512+62.21	LT															1																	
1517+00.00							82.29									1																	50.9
1518+12.56	LT						86.88									1																	
1519+13.53	LT															1																	
1525+55.69					4.12																												
1532+90.00					1.16																												
1552+55.00							167.21									2																	
1567+60.75	LT			66.65												1																	89.84
1568+39.65	LT															1																	
1569+58.34	RT			71.54												1																	
1570+42.13	RT															1																	
1574+00.00				63.31												1																	
1582+55.00					2.93																												
1595+00.00							164.31									2																	
1597+49.74	LT						46.07									2																	
1607+00.00							186.89									2																	
1610+00.00	LT				24.36												2																
1619+70.00							80.75									1																	
1627+35.00					22.46		164.94									4																	
1634+00.00	LT				51.49											2																	
1640+00.00					20.73		181.40									4																	
1645+76.11																1																	
1647+76.11																																	
1656+34.34					3.30																												
1656+52.71	LT																																
1656+59.86	LT																																
7+15.00							252.34																										
19+00.00							258.00																										
26+00.00							83.52																										
30+92.52	LT				92.34											1																	
31+13.32	LT				49.68											1																	
31+75.24	LT															1																	
31+97.09	LT															1																	
37+15.00							260.27																										
49+85.00							83.74																										
50+00.00	LT						76.85																										
57+00.00							90.04																										
60+75.00	RT																																
60+75.00	LT						45.42																										
65+00.00							132.96																										
70+55.22	RT																																
70+83.21	LT						50.34																										
72+27.22	RT																																
76+50.00							127.89																										
80+75.00							217.36									1																	
82+33.46	LT																																

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES  
DRAINAGE**

SCALE: N/A  
DATE: 03/06/2012

DRAWN BY: K.E.J.  
CHECKED BY: J.M.M.

**SCHEDULE OF QUANTITIES: IL. RTE. 29**