

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L2SEC	L2SEC	LS3EC
				CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				0005	0014	0021
				ROADWAY 80% FEDERAL 20% STATE	BRIDGE 80% FEDERAL 20% STATE	SAFETY (I-55/IL 104) 90% FEDERAL 10% STATE
X 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	2088.0	1,770.0		318.0
X 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	79.0	79.0		
X 78009005	MODIFIED URETHANE PAVEMENT MARKING - LINE 5"	FOOT	24654.0	19,994.0		4,660.0
X 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	430.0	430.0		
X 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	585.0	483.0		102.0
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	512.0	512.0		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	512.0	512.0	
	Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	744.0	744.0	
	Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	744.0	744.0	
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5.3	5.3	
	Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	374.0		374.0
	Z0041895	POLYMER CONCRETE	CU FT	4.8	4.8	
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0	
	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	119707.0	119707.0	

X SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgw	DESIGNED - ETJ	REVISED -
c:\pwork\pwork\sparksgw\d0245433\0672E12-shr-S00.dgn		DRAWN - ETJ	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED - RTS	REVISED -
	PLOT DATE = Apr-09-2012 03:26:58PM	DATE - 01-05-12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	(140RS-6, 141RS-7)I	SANGAMON	98	7
SCALE: SHEET 5 OF 6 SHEETS STA. TO STA.			CONTRACT NO. 72E12	
ILLINOIS FED. AID PROJECT				