

HMA SURFACE REMOVAL										
LOCATION			LEFT SHOULDER	PAVEMENT	RIGHT SHOULDER	DISTANCE	PAVEMENT AREA	SHOULDER AREA	HMA SURFACE	HMA SURFACE
			WIDTH (FOOT)	WIDTH (FOOT)	WIDTH (FOOT)	OF RUN (FOOT)	(BY CADD) (SQUARE FOOT)	(BY CADD) (SQUARE FOOT)	REMOVAL, VARIABLE DEPTH (SQUARE YARD)	REMOVAL, 2" (SQUARE YARD)
BEGINNING OF PROJECT IL 104 (AUBURN)										
STA 523+55.00	TO	STA 536+00.00	3	24	3	1245.00	30133.55	7470.00	4178.17	
STA 536+00.00	TO	STA 551+00.00	3	24	3	1500.00	36343.38	9000.00	5038.15	
STA 551+00.00	TO	STA 566+00.00	3	24	3	1500.00	37617.84	9000.00	5179.76	
STA 566+00.00	TO	STA 572+51.00	3	24	3	651.00	16231.45	3906.00	2237.49	
SUGAR CREEK BRIDGE OMISSION SN: 084-0192										
STA 574+77.46	TO	STA 581+00.00	3	24	3	622.54	15285.22	3735.24	2113.38	
STA 581+00.00	TO	STA 596+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 596+00.00	TO	STA 611+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 611+00.00	TO	STA 626+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 626+00.00	TO	STA 641+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 641+00.00	TO	STA 656+00.00	3	24	3	1500.00	36297.53	9000.00	5033.06	
STA 656+00.00	TO	STA 671+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 671+00.00	TO	STA 686+00.00	3	24	3	1500.00	36299.87	9000.00	5033.32	
STA 686+00.00	TO	STA 701+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 701+00.00	TO	STA 716+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	
STA 716+00.00	TO	STA 731+00.00	3	24	3	1500.00	36299.99	9000.00	5033.33	
STA 731+00.00	TO	STA 746+00.00	3	24	3	1500.00	36299.95	9000.00	5033.33	
STA 746+00.00	TO	STA 746+90.47	3	24	3	90.47	2189.86	542.82	303.63	
STA. EQUATION: STA. 746+90.47 (BK) = STA. 71+63.54 (AHD)										
STA 71+63.54	TO	STA 72+52.02	3	24	3	88.48	2127.50	530.88	295.38	
RAILROAD OMISSION										
STA 72+64.02	TO	STA 74+62.03	3	24	3	198	4852.02	1188.06	671.12	
RAILROAD OMISSION										
I-55 INTERCHANGE @ RAILROAD TRACKS										
STA 74+82.00	TO	STA 77+00.00				218.00	4851.71	1649.68		722.38
STA 77+00.00	TO	STA 80+00.00				300.00	8303.20	5243.69		1505.21
STA 80+00.00	TO	STA 83+00.00				300.00	8598.79	5974.78		1619.29
STA 83+00.00	TO	STA 86+00.00				300.00	10601.97	4627.32		1692.14
STA 86+00.00	TO	STA 89+00.00				300.00	9882.44	6390.44		1808.10
STA 89+00.00	TO	STA 92+00.00				300.00	12175.93	5983.22		2017.68
STA 92+00.00	TO	STA 95+00.00				300.00	11368.91	3118.77		1609.74
STA 95+00.00	TO	STA 98+00.00				300.00	8807.22	6169.72		1664.10
STA 98+00.00	TO	STA 101+00.00				300.00	8831.27	6137.30		1663.17
STA 101+00.00	TO	STA 104+00.00				300.00	10645.97	6074.43		1857.82
STA 104+00.00	TO	STA 107+00.00				300.00	12704.44	4935.85		1960.03
STA 107+00.00	TO	STA 110+00.00				300.00	11801.56	3926.68		1747.58
STA 110+00.00	TO	STA 113+00.00				300.00	11715.53	6065.48		1975.67
STA 113+00.00	TO	STA 116+00.00				300.00	8994.92	6041.22		1670.68
STA 116+00.00	TO	STA 119+00.00				300.00	8750.83	5980.49		1636.81
STA 119+00.00	TO	STA 122+00.00				300.00	8278.76	6025.21		1589.33
STA 122+00.00	TO	STA 123+62.50				162.50	3963.77	2972.16		770.66
SB I-55 EXIT RAMP										
STA 21+41.00	TO	STA 23+00.00				159.00	2503.11	1183.86		409.66
STA 23+00.00	TO	STA 25+00.00				200.00	3207.73	840.18		449.77
STA 25+00.00	TO	STA 26+24.00				124.00	4947.70	185.34		570.34
SB I-55 ENTRANCE RAMP										
NB I-55 EXIT RAMP										
NB I-55 ENTRANCE RAMP										
I-55 INTERCHANGE TO PAWNEE										
STA 123+62.50	TO	STA 124+73.26	3	24	3	110.76	2627.60	664.56	365.80	
STA. EQUATION: STA. 124+73.26 (BK) = STA. 802+78.33 (AHD)										
STA 802+78.33	TO	STA 808+00.00	3	24	3	521.67	12124.11	3130.02	1694.90	
STA 808+00.00	TO	STA 823+00.00	3	24	3	1500.00	34800.00	9000.00	4866.67	
STA 823+00.00	TO	STA 825+28.50	3	24	3	228.50	4875.09	1371.00	694.01	
BRUSH CREEK BRIDGE OMISSION (0065)										
STA 826+71.50	TO	STA 838+00.00	3	24	3	1128.50	25725.94	6771.00	3610.77	
STA 838+00.00	TO	STA 853+00.00	3	24	3	1500.00	34769.41	9000.00	4863.27	
STA 853+00.00	TO	STA 868+00.00	3	24	3	1500.00	34821.25	9000.00	4869.03	
STA 868+00.00	TO	STA 883+00.00	3	24	3	1500.00	34822.61	9000.00	4869.18	
STA 883+00.00	TO	STA 898+00.00	3	24	3	1500.00	42472.61	9000.00	5719.18	
STA 898+00.00	TO	STA 913+00.00	3	24	3	1500.00	34826.39	9000.00	4869.60	
STA 913+00.00	TO	STA 928+00.00	3	24	3	1500.00	34830.35	9000.00	4870.04	
STA 928+00.00	TO	STA 935+94.00	3	24	3	794.00	22518.34	4764.00	3031.37	
END OF PROJECT IL 104 (PAWNEE)										
TOTALS						41447.43	1049520.02	307171.09	119707.3	31036.2

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
c:\pwork\pwork\sparksgw\10245433\0672E12-sht-schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET 1	OF 8	SHEETS	STA.	TO STA.	753	(140RS-6, 14IRS-7)I	SANGAMON	98	20
		CHECKED -	REVISED -						CONTRACT NO. 72E12						
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT										