

HOT - MIX ASPHALT SURFACE COURSE, MAINLINE PAVEMENT															
LOCATION		LEFT SHOULDER	PAVEMENT	RIGHT SHOULDER	DISTANCE	PAVEMENT AREA	SHOULDER AREA	SURFACE AREA	1.5" HMA SURFACE	1.5" HMA SURFACE	AGGREGATE	BITUMINOUS	0.75" HMA LEVELING	1.0" HMA LEVELING	
		WIDTH	WIDTH	WIDTH	OF RUN	(BY CADD)		(PVMT & SHLDRS)	COURSE, MIX D, N70	COURSE, MIX D, N90	PRIME COAT	PRIME COAT	BINDER, (MM) N70	BINDER, (MM) N90	
		(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQUARE FOOT)	(SQUARE FOOT)	(SQUARE YARD)	(TON)	(TON)	(TON)	(TON)	(TON)	(TON)	
BEGINNING OF PROJECT IL 104 (AUBURN)															
STA 523+55.00	TO	STA 536+00.00	3	24	3	1245.00	30133.55	7470.00	4178.17	350.97	16.71	3.18	175.48		
STA 536+00.00	TO	STA 551+00.00	3	24	3	1500.00	36343.38	9000.00	5038.15	423.20	20.15	3.83	211.60		
STA 551+00.00	TO	STA 566+00.00	3	24	3	1500.00	37617.84	9000.00	5179.76	435.10	20.72	3.94	217.55		
STA 566+00.00	TO	STA 572+51.00	3	24	3	651.00	16231.45	3906.00	2237.49	187.95	8.95	1.70	93.97		
SUGAR CREEK BRIDGE OMISSION SN: 084-0192															
STA 574+77.00	TO	STA 581+00.00	3	24	3	623.00	15285.22	3738.00	2113.69	177.55	8.45	1.61	88.78		
STA 581+00.00	TO	STA 596+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 596+00.00	TO	STA 611+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 611+00.00	TO	STA 626+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 626+00.00	TO	STA 641+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 641+00.00	TO	STA 656+00.00	3	24	3	1500.00	36297.53	9000.00	5033.06	422.78	20.13	3.83	211.39		
STA 656+00.00	TO	STA 671+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 671+00.00	TO	STA 686+00.00	3	24	3	1500.00	36299.87	9000.00	5033.32	422.80	20.13	3.83	211.40		
STA 686+00.00	TO	STA 701+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 701+00.00	TO	STA 716+00.00	3	24	3	1500.00	36300.00	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 716+00.00	TO	STA 731+00.00	3	24	3	1500.00	36299.99	9000.00	5033.33	422.80	20.13	3.83	211.40		
STA 731+00.00	TO	STA 740+00.00	3	24	3	900.00	36299.95	5400.00	4633.33	389.20	18.53	3.52	194.60		
STA 740+00.00	TO	STA 746+90.47	3	24	3	690.47	2189.86	4142.82	703.63		59.11	2.81	0.53	29.55	
STA. EQUATION: STA. 746+90.47 (BK) = STA. 71+63.54 (AHD)															
STA 71+63.54	TO	STA 72+52.02	3	24	3	88.48	2127.50	530.88	295.38		24.81	1.18	0.22	12.41	
RAILROAD OMISSION															
STA 72+64.02	TO	STA 74+64.02	3	24	3	200	4852.02	1200.00	672.45		56.37	2.69	0.51	28.19	
RAILROAD OMISSION															
I-55 INTERCHANGE @ RAILROAD TRACKS															
STA 74+82.00	TO	STA 77+00.00		VARIABLES		218.00	5211.30	1769.15	775.61		65.15	3.10	0.59	43.43	
STA 77+00.00	TO	STA 80+00.00		VARIABLES		300.00	9114.90	5248.50	1595.93		134.06	6.38	1.21	89.37	
STA 80+00.00	TO	STA 83+00.00		VARIABLES		300.00	12516.60	6017.67	2059.36		172.99	8.24	1.57	115.32	
STA 83+00.00	TO	STA 86+00.00		VARIABLES		300.00	11880.50	4722.36	1844.76		154.96	7.38	1.40	103.31	
STA 86+00.00	TO	STA 89+00.00		VARIABLES		300.00	9410.50	6395.48	1756.22		147.52	7.02	1.33	98.35	
STA 89+00.00	TO	STA 92+00.00		VARIABLES		300.00	11685.50	6077.89	1973.71		165.79	7.89	1.50	110.53	
STA 92+00.00	TO	STA 95+00.00		VARIABLES		300.00	10931.80	3226.53	1573.15		132.14	6.29	1.20	88.10	
STA 95+00.00	TO	STA 98+00.00		VARIABLES		300.00	8379.10	6236.12	1623.91		136.41	6.50	1.23	90.94	
STA 98+00.00	TO	STA 101+00.00		VARIABLES		300.00	8333.50	6212.12	1616.18		135.76	6.46	1.23	90.51	
STA 101+00.00	TO	STA 104+00.00		VARIABLES		300.00	10954.20	6023.14	1886.37		158.46	7.55	1.43	105.64	
STA 104+00.00	TO	STA 107+00.00		VARIABLES		300.00	12086.20	4920.23	1889.60		158.73	7.56	1.44	105.82	
STA 107+00.00	TO	STA 110+00.00		VARIABLES		300.00	11374.50	3957.14	1703.52		143.10	6.81	1.29	95.40	
STA 110+00.00	TO	STA 113+00.00		VARIABLES		300.00	11729.10	6046.38	1975.05		165.90	7.90	1.50	110.60	
STA 113+00.00	TO	STA 116+00.00		VARIABLES		300.00	9005.50	6049.48	1672.78		140.51	6.69	1.27	93.68	
STA 116+00.00	TO	STA 119+00.00		VARIABLES		300.00	7688.30	6050.52	1526.54		128.23	6.11	1.16	85.49	
STA 119+00.00	TO	STA 122+00.00		VARIABLES		300.00	8215.60	6051.61	1585.25		133.16	6.34	1.20	88.77	
STA 122+00.00	TO	STA 123+62.50		VARIABLES		162.50	3963.80	2969.81	770.40		64.71	3.08	0.59	43.14	
SB I-55 EXIT RAMP															
STA 21+26.00	TO	STA 23+00.00		VARIABLES		174.00	3388.10	1414.88	533.66		44.83	2.13	0.41	29.89	
STA 23+00.00	TO	STA 25+00.00		VARIABLES		200.00	4785.70	1599.77	709.50		59.60	2.84	0.54	39.73	
STA 25+00.00	TO	STA 26+24.00		VARIABLES		124.00	6040.40	1015.26	783.96		65.85	3.14	0.60	43.90	
SB I-55 ENTRANCE RAMP															
NB I-55 EXIT RAMP															
NB I-55 ENTRANCE RAMP															
I-55 INTERCHANGE TO PAWNEE															
STA 123+62.50	TO	STA 124+73.26	3	24	3	110.76	2627.60	664.56	365.80		30.73	0.73	0.28	20.48	
STA. EQUATION: STA. 124+73.26 (BK) = STA. 802+78.33 (AHD)															
STA 802+78.33	TO	STA 808+00.00	3	24	3	521.67	12124.11	3130.02	1694.90	142.37	3.39	1.29	71.19		
STA 808+00.00	TO	STA 823+00.00	3	24	3	1500.00	34800.00	9000.00	4866.67	408.80	9.73	3.70	204.40		
STA 823+00.00	TO	STA 824+97.30	3	24	3	197.30	4875.09	1183.80	673.21	56.55	1.35	0.51	28.27		
BRUSH CREEK BRIDGE OMISSION (0065)															
STA 827+01.70	TO	STA 838+00.00	3	24	3	1098.30	25725.94	6589.80	3590.64	301.61	7.18	2.73	150.81		
STA 838+00.00	TO	STA 853+00.00	3	24	3	1500.00	34769.41	9000.00	4863.27	408.51	9.73	3.70	204.26		
STA 853+00.00	TO	STA 868+00.00	3	24	3	1500.00	34821.25	9000.00	4869.03	409.00	9.74	3.70	204.50		
STA 868+00.00	TO	STA 883+00.00	3	24	3	1500.00	34822.61	9000.00	4869.18	409.01	9.74	3.70	204.51		
STA 883+00.00	TO	STA 898+00.00	3	24	3	1500.00	42472.61	9000.00	5719.18	480.41	11.44	4.35	240.21		
STA 898+00.00	TO	STA 913+00.00	3	24	3	1500.00	34826.39	9000.00	4869.60	409.05	9.74	3.70	204.52		
STA 913+00.00	TO	STA 928+00.00	3	24	3	1500.00	34830.35	9000.00	4870.04	409.08	9.74	3.70	204.54		
STA 928+00.00	TO	STA 935+94.00	3	24	3	794.00	22518.34	4764.00	3031.37	254.64	6.06	2.30	127.32		
END OF PROJECT IL 104 (PAWNEE)															
TOTALS						41403.48	1056141.46	309288.51	151714.44	9881.0	2862.9	513.9	115.3	4940.5	1885.2

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\sparksgw\0245433\0672E12-sht-schedule.dgn	DRAWN -	REVISED -	753						(140RS-6, 141RS-7)I	SANGAMON	98	21	
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -	CONTRACT NO. 72E12										
PLOT DATE = Apr-09-2012 03:33:16PM	DATE -	REVISED -	SCALE:		SHEET 2 OF 8 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT					