

PAINT PAVEMENT MARKING - LINE 5"		
LOCATION	COLOR / DESCRIPTION	LENGTH (FOOT)
AUBURN TO I-55 INTERCHANGE		
LEFT SIDE E. O. P.		
STA 523+55.00 TO STA 533+29.00	WHITE / LEFT EDGE, SOLID	974.00
SOUTH IRIS DRIVE		
STA 534+11.00 TO STA 563+46.00	WHITE / LEFT EDGE, SOLID	2935.00
DIXON ROAD		
STA 564+11.00 TO STA 589+40.00	WHITE / LEFT EDGE, SOLID	2529.00
BAB ROAD		
STA 590+38.00 TO STA 667+79.00	WHITE / LEFT EDGE, SOLID	7741.00
NORTH DAWSON ROAD		
STA 668+71.00 TO STA 707+79.00	WHITE / LEFT EDGE, SOLID	3908.00
PURDON ROAD		
STA 708+46.00 TO STA 746+90.47	WHITE / LEFT EDGE, SOLID	3844.47
STA EQUATION: 746+90.47(BK.) = 71+63.54(AHD)		
STA 71+63.54 TO STA 72+52.02	WHITE / LEFT EDGE, SOLID	88.48
RAILROAD OMISSION		
STA 72+64.02 TO STA 74+62.03	WHITE / LEFT EDGE, SOLID	198.01
RAILROAD OMISSION		
I-55 INTERCHANGE TO PAWNEE		
STA 123+62.50 TO STA 124+73.26	WHITE / LEFT EDGE, SOLID	110.76
STA EQUATION: 124+73.26(BK.) = 802+78.33(AHD)		
STA 802+78.33 TO STA 857+73.00	WHITE / LEFT EDGE, SOLID	5494.67
SOUTH COMANCHE ROAD		
STA 858+35.00 TO STA 935+94.00	WHITE / LEFT EDGE, SOLID	7759.00
END OF PROJECT (PAWNEE)		
RIGHT SIDE E. O. P.		
AUBURN TO I-55 INTERCHANGE		
STA 523+55.00 TO STA 525+62.00	WHITE / RIGHT EDGE, SOLID	207.00
SOUTH CLOVER LANE		
STA 526+28.00 TO STA 563+25.00	WHITE / RIGHT EDGE, SOLID	3697.00
DIXON ROAD		
STA 564+05.00 TO STA 589+52.00	WHITE / RIGHT EDGE, SOLID	2547.00
BAB ROAD		
STA 590+24.00 TO STA 654+68.00	WHITE / RIGHT EDGE, SOLID	6444.00
KESSLER ROAD		
STA 655+43.00 TO STA 707+66.00	WHITE / RIGHT EDGE, SOLID	5223.00
PURDON ROAD		
STA 708+52.00 TO STA 746+90.47	WHITE / RIGHT EDGE, SOLID	3838.47
STA EQUATION: 746+90.47(BK.) = 71+63.54(AHD)		
STA 71+63.54 TO STA 72+52.02	WHITE / RIGHT EDGE, SOLID	88.48
RAILROAD OMISSION		
STA 72+64.02 TO STA 74+62.03	WHITE / RIGHT EDGE, SOLID	198.01
RAILROAD OMISSION		
I-55 INTERCHANGE TO PAWNEE		
STA 123+62.50 TO STA 124+73.26	WHITE / RIGHT EDGE, SOLID	110.76
STA EQUATION: 124+73.26(BK.) = 802+78.33(AHD)		
STA 802+78.33 TO STA 857+72.00	WHITE / RIGHT EDGE, SOLID	5493.67
SOUTH COMANCHE ROAD		
STA 858+43.00 TO STA 883+78.00	WHITE / RIGHT EDGE, SOLID	2535.00
SHEEDY ROAD		
STA 885+18.00 TO STA 935+94.00	WHITE / RIGHT EDGE, SOLID	5076.00
END OF PROJECT (PAWNEE)		
CENTERLINE (10' DASH - 30' SKIP)		
AUBURN TO I-55 INTERCHANGE		
STA 523+55.00 TO STA 557+57.00	YELLOW / SKIP-DASH	860.00
STA 575+00.00 TO STA 579+02.00	YELLOW / SKIP-DASH	110.00
STA 596+10.00 TO STA 738+32.00	YELLOW / SKIP-DASH	3560.00
STA EQUATION: 746+90.47(BK.) = 71+63.54(AHD)		
I-55 INTERCHANGE TO PAWNEE		
STA 123+62.50 TO STA 124+73.26	YELLOW / SKIP-DASH	30.00
STA EQUATION: 124+73.26(BK.) = 802+78.33(AHD)		
STA 802+78.33 TO STA 884+64.00	YELLOW / SKIP-DASH	2050.00
STA 894+21.00 TO STA 935+94.00	YELLOW / SKIP-DASH	1050.00
END OF PROJECT (PAWNEE)		
NO PASSING ZONE, EASTBOUND TRAFFIC		
STA 557+57.00 TO STA 563+98.00	YELLOW / SOLID, SKIP-DASH	811.00
STA 579+02.00 TO STA 588+47.00	YELLOW / SOLID, SKIP-DASH	1185.00
STA 738+32.00 TO STA 746+90.47	YELLOW / SOLID, SKIP-DASH	1078.47
STA EQUATION: 746+90.47(BK.) = 71+63.54(AHD)		
STA 71+63.54 TO STA 72+54.02	YELLOW / SOLID, SKIP-DASH	120.48
NO PASSING ZONE, WESTBOUND TRAFFIC		
STA 566+92.00 TO STA 575+00.00	YELLOW / SOLID, SKIP-DASH	1018.00
STA 591+00.00 TO STA 596+10.00	YELLOW / SOLID, SKIP-DASH	640.00
DUAL NO PASSING ZONE		
STA 563+98.00 TO STA 566+92.00	YELLOW / DOUBLE SOLID	588.00
STA 588+47.00 TO STA 591+00.00	YELLOW / DOUBLE SOLID	506.00
STA EQUATION: 746+90.47(BK.) = 71+63.54(AHD)		
STA 72+64.02 TO STA 74+62.03	YELLOW / DOUBLE SOLID	396.02
TOTAL		
		85044.00

URATHENE PAVEMENT MARKING						
LOCATION	5" SOLID WHITE (FOOT)	5" SOLID YELLOW (FOOT)	8" SOLID WHITE (FOOT)	12" SOLID YELLOW (FOOT)	12" SOLID WHITE (FOOT)	
STA 74+82.00 TO STA 85+00.00	1689.0	2770.0		102.0		
STA 85+00.00 TO STA 95+00.00	1621.0	1902.0				
SB I-55 EXIT RAMP	650.0	491.0	160.0		127.0	
SB I-55 ENTRANCE RAMP	194.0	125.0				
STA 95+00.00 TO STA 110+00.00	2672.0	2887.0				
NB I-55 EXIT RAMP	277.0	132.0	103.0		62.0	
NB I-55 ENTRANCE RAMP	262.0	167.0	167.0		95.0	
STA 110+00.00 TO STA 123+62.50	2725.0	2723.0				
STA 884+50.00 TO STA 894+50.00		3373.4		198.6		
SUB TOTAL		10090.0	14570.4	430.0	300.6	284.0
TOTAL		24660.4	430.0	584.6		

PERFORMED PLASTIC PAVEMENT, TYPE B - INLAID - LETTERS & SYMBOLS		
LOCATION	MARKING TYPE	QUANTITY (SURFACE AREA) SQ FT
EAST OF AUBURN IL 104 MAINLINE		
STA 738+68.00	R. R. CROSS-BUCK ("X" & "R")	61.20
STA 73+42.00	R. R. CROSS-BUCK ("X" & "R")	61.20
STA 73+86.00	R. R. CROSS-BUCK ("X" & "R")	61.20
STA 82+25.00	LEFT LANE TURN ARROW	15.60
STA 83+75.00	LEFT LANE TURN ARROW	15.60
STA 81+00.00	R. R. CROSS-BUCK ("X" & "R")	61.20
STA 90+10.00	LEFT LANE TURN ARROW	15.60
STA 91+60.00	LEFT LANE TURN ARROW	15.60
STA 92+80.00	LEFT LANE TURN ARROW	15.60
STA 102+90.00	LEFT LANE TURN ARROW	15.60
STA 104+30.00	LEFT LANE TURN ARROW	15.60
STA 105+80.00	LEFT LANE TURN ARROW	15.60
STA 107+10.00	LEFT LANE TURN ARROW	15.60
SB I-55 EXIT RAMP		
STA 23+35.00	LEFT LANE TURN ARROW	15.60
STA 23+35.00	RIGHT LANE TURN ARROW	15.60
STA 24+15.00	LEFT LANE TURN ARROW	15.60
STA 24+15.00	RIGHT LANE TURN ARROW	15.60
STA 25+00.00	LEFT LANE TURN ARROW	15.60
STA 25+00.00	RIGHT LANE TURN ARROW	15.60
STA 25+80.00	LEFT LANE TURN ARROW	15.60
STA 25+80.00	RIGHT LANE TURN ARROW	15.60
NB I-55 EXIT RAMP		
STA 23+30.00	LEFT LANE TURN ARROW	15.60
STA 23+30.00	RIGHT LANE TURN ARROW	15.60
STA 889+35.00	LEFT LANE TURN ARROW	15.60
STA 890+25.00	LEFT LANE TURN ARROW	15.60
TOTAL		572.40

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - 6"			
LOCATION	6"X2' SKIP DASH (FOOT)	6" SOLID WHITE (FOOT)	
STA 74+75.00 TO STA 85+00.00	46.0	185.0	
STA 85+00.00 TO STA 95+00.00	117.0	308.0	
SB I-55 EXIT RAMP	67.0	236.0	
STA 101+00.00 TO STA 115+00.00	282.0	751.0	
STA 889+30.00 TO STA 890+25.00		96.0	
SUB TOTAL		512.0	1576.0
TOTAL		2088.0	

PERFORMED PLASTIC PAVEMENT, TYPE B - INLAID - 24"	
LOCATION	FOOT
SB I-55 EXIT RAMP	36.0
NB I-55 EXIT RAMP	43.0
TOTAL	79.0

FILE NAME = c:\pwork\pvidot\slgler\0245433\067

USER NAME = Slgler
 E12-ht-schedule.dgn
 PLOT SCALE = 100.0000' / in.
 PLOT DATE = Apr-25-2012 12:00:46PM

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 4 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	(140RS-6, 14[RS-7]I)	SANGAMON	98	23
				CONTRACT NO. 72E12
ILLINOIS FED. AID PROJECT				