



**LEGEND**

- PROPOSED EARTH EXCAVATION FOR IMPROVED SIGHT DISTANCE FOR NORTHBOUND TRAFFIC ON DIXON ROAD.
- $\begin{matrix} +XX \\ XX.XX' \end{matrix}$  ROADWAY CENTERLINE STATION OFFSET FROM ROADWAY CENTERLINE

BILL OF MATERIAL		
PAY CODE	ITEM	QUANTITY
20200100	EARTH EXCAVATION	116 CU YD
25000200	SEEDING, CLASS 2	0.2 ACRES
25000400	NITROGEN FERTILIZER NUTRIENT	18 POUNDS
25000500	PHOSPHORUS FERTILIZER NUTRIENT	18 POUNDS
25000600	POTASSIUM FERTILIZER NUTRIENT	18 POUNDS
25000700	AGGRICULTURAL GROUND LIMESTONE	0.4 TONS
25100115	MULCH, METHOD 2	0.2 ACRES