GENERAL NOTES:

- 1. ALL PROPOSED LIGHTING UNITS SHALL BE LABELED ACCORDING TO THE STANDARD SPECIFICATIONS, WITH POLE NUMBERS ATTACHED WITH STAINLESS STEEL BANDING. LIGHTING UNIT NUMBERING SHALL BE AS DIRECTED BY ENGINEER.
- 2. CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE ELECTRICAL WORK WITH OTHER TRADES.
- THE PROPOSED LIGHT POLES SHALL BE LOCATED AS NOTED ON THE PLANS, 15 FEET FROM EDGE OF TRAVELED LANE, OR AS DIRECTED BY THE ENGINEER. LIGHT POLE FOUNDATIONS SHALL BE INSTALLED PLUMB AND FLUSH WITH THE PROPOSED GRADE AND SHALL MEET THE HEIGHT REQUIREMENTS OF ARTICLE 836.03 OF THE STANDARD SPECIFICATIONS. AFTER UNIT DUCT IS INSTALLED FOUNDATIONS SHALL BE FILLED WITH FINE AGGREGATE ACCORDING TO ARTICLE 836.03. WASHERS USED TO INTALL THE POLE SHALL BE LARGE ENOUGH TO FULLY COVER THE SLOTTED HOLES IN THE POLE BASE PLATE.
- 4. CONTRACTOR SHALL INSTALL LIGHT POLES AT THE LOCATIONS INDICATED ON THE PLANS, MAINTAINING ADEQUATE CLEARANCE FROM UTILITY LINES. CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY CLEARANCES PER THE NATIONAL ELECTRICAL SAFETY CODE AND/OR THE REQUIREMENTS OF THE UTITLITY COMPANIES. THE LOCATION OF BURIED AND ABOVE GROUND UTILITIES SHOWN ARE APPROXIMATE AND ARE SHOWN FOR INFORMATION ONLY. REROUTING, DISCONNECTION, RELOCATION, PROTECTION ETC., OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.
- 5. THE CONTRACTOR IS RESPONSIBLE FOR UNCOVERING OR HAND DIGGING AROUND UTILITIES AS NECESARY. THE COST OF THIS WORK IS TO BE INCLUDED WITH THE "UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA." AND "UNIT DUCT, 600V, 2-1C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE" PAY ITEMS.
- 6. THE CONTRACTOR SHALL PROVIDE AND INSTALL A CONCRETE WORK PAD IN FRONT OF THE LIGHTING CONTROLLER PER SECTION 825 OF THE STANDARD SPECIFICATIONS.
- 7. INSTALL HORIZONTAL MOUNT LUMINAIRES PERPENDICULAR TO THE CENTERLINE OF THE ROADWAY AS REQUIRED BY ARTICLE 821.04 OF THE STANDARD SPECIFICATIONS.
- 8. UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA. SHALL BE SCHEDULE 80 AS NOTED IN THE PLANS.
- 9. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUB NUMBERS LISTED IN THE LIST OF STANDARDS ON THE COVER SHEET AND THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- 10. PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING TOPOGRAPHY AND FACILITIES HAVE BEEN TAKEN FROM THE LATEST FIELD SURVEYS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS.

GENERAL NOTES:

1. THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS COVERING ANY MAJOR PLAN CHANGES TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN, AND TO ALLOW IMPROVED DESIGN FOR THE FUTURE.

	DISTRICT SIX	
EXAMINED	•	20
OPERATIONS E	NGINEER	
EXAMINED Zun	12-14	20 //
PROJECT IMP	EMENTATION ENGIN	IEER
EXAMINED	December 12 PM LL	20 _//
PROGRAM DE	VELOPMENT ENGINE	ER

	FILE NAME =	USER NAME = Slaglert	DESIGNED -	RTS	REVISED -						F.A.U.	SECTION	COUNTY	TOTAL SHEET	1
	c:\pw_work\pwidot\slaglert\d0283566\D6xx	xxx-sht-gennote.dgn	DRAWN -	RTS	REVISED -	STATE OF ILLINOIS	l		OFFICE LIGHTS		8012	211	SANGAMON	10 2	1
		PLOT SCALE = 40.0000 '/ in.	CHECKED -	RTS	REVISED ~	DEPARTMENT OF TRANSPORTATION	GENERAL NOTES				CONTRACT NO. 72F06		1		
		PLOT DATE = Dec-16-2011 02:43:29PM	DATE -	11-29-11	REVISED ~		SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.		TO STA.	1	ILLINOIS FED. AID PROJECT			1	
•			LUATE		11211020		I JOHLL.	1 311001 1	or 1 Sheets Star	10 314	<u> </u>	ILLINOIS FED.	, ALD PROJECT		