



INSTALL PROPOSED SIGN PANEL-TYPE 1, W4-4P, 30"x24" TO EXISTING STOP SIGN

REMOVE EXISTING SIGN SUPPORT & STOP SIGN PANEL (INCLUDED IN THE COSTS FOR INSTALLATION OF PROPOSED SIGN SUPPORT AND PANEL)
 PROPOSED TELESCOPING STEEL SIGN SUPPORT, 16'-0"
 PROPOSED SIGN PANEL-TYPE 2, R1-1, OVERSIZED, 48"x48"
 PROPOSED SIGN PANEL-TYPE 1, SIGN W4-4P, 30"x24" (MUTCD, 2009; TABLE 2C-3)

PROPOSED LEGEND

- LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. MAST ARM WITH LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT & TRANSFORMER BASE
- ELECTRIC SERVICE INSTALLATION 120/240 V, 1 PHASE 4 WIRE
- LIGHTING CONTROLLER, POLE MOUNTED, 240 V, 30 AMP
- UNIT DUCT, 600 V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE
- UNDERGROUND CONDUIT, COILABLE NON-METALLIC CONDUIT, 2 1/2" DIA. (SCH.80)

BILL OF MATERIALS (THIS SHEET ONLY)

PAY CODE	ITEM DESCRIPTION	UNIT	QUANTITY
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	72
81603000	UNIT DUCT, 600V, 2-1C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	401
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	3
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 30 AMP	EACH	1
83009600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. MAST ARM	EACH	3
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	20
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	3
72000100	SIGN PANEL - TYPE 1	SQ FT	10
72000200	SIGN PANEL - TYPE 2	SQ FT	16
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	16