

HOT-MIX ASPHALT SURFACE REMOVAL

LOCATION	PAVEMENT WIDTH (FOOT)	SHLD WIDTH (FOOT)	HMA SURF REM 3/4" (SQ YD)
US 51/IL 16 STA 56+40.23 TO STA 65+68.84	VARIES	4	4,979.54
US 51 STA 63+44.78 TO STA 69+00.00	VARIES	4	2,204.64
IL 16 STA 65+68.84 TO STA 71+49.19	VARIES	4	3,691.65
STA 71+41.19 BK = STA 700+20.29 AH			
STA 700+20.29 TO STA 698+06.58	VARIES	4	855.52
STA 698+06.58 TO STA 672+04.70	23	3	8,383.84
STA 672+04.70 BK = STA 671+93.70 AH			
STA 671+93.70 TO STA 651+50.00	22	3	6,358.18
<b>TOTAL</b>			<b>26,473.4</b>

HMA SURFACE REMOVAL - BUTT JOINT

LOCATION	LENGTH (FOOT)	AREA (SQ YD)
US 51/IL 16 STA 56+40.23	30	106.67
US 51 STA 69+00.00	30	100.00
IL 16 STA 651+50.00	30	96.67
CH 2600 E STA 61+57.49	30	83.33
<b>TOTAL</b>		<b>386.7</b>

TEMPORARY RAMP

LOCATION	LENGTH (FOOT)	AREA (SQ YD)
US 51/IL 16 STA 56+40.23	5	17.78
US 51 STA 69+00.00	5	16.67
IL 16 STA 651+50.00	5	16.11
CH 2600 E STA 61+57.49	5	13.89
<b>TOTAL</b>		<b>64.4</b>

NOTE: ALL SURFACE REMOVAL AND PAVING QUANTITIES FOR CH 2600 E ARE INCLUDED WITH IL 16

PAVING

LOCATION	PAVEMENT WIDTH (FOOT)	LEFT SHOULDER WIDTH (FOOT)	RIGHT SHOULDER WIDTH (FOOT)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	LEVELING BINDER (MM) (TON)	HMA SURF COURSE, MIX D (TON)
US 51/IL 16 STA 56+40.23 TO STA 65+68.84	VARIES	4	4	4,154.11	825.43	1.89	9.96	209.14	418.28
US 51 STA 63+44.78 TO STA 69+00.00	VARIES	4	4	1,711.11	493.53	0.84	4.41	92.59	185.19
IL 16 STA 65+68.84 TO STA 71+49.19	VARIES	4	4	3,175.78	515.87	1.40	7.38	155.05	310.10
STA 71+41.19 BK = STA 700+20.29 AH									
STA 700+20.29 TO STA 698+06.58	VARIES	4	4	665.56	189.96	0.33	1.71	35.93	71.86
STA 698+06.58 TO STA 672+04.70	28	3	3	8,094.74	1,734.59	3.74	19.66	412.83	825.66
STA 672+04.70 BK = STA 671+93.70 AH									
STA 671+93.70 TO STA 651+50.00	28	3	3	6,358.18	1,362.47	2.93	15.44	324.27	648.53
<b>TOTAL</b>						<b>11.1</b>	<b>58.6</b>	<b>1,229.8</b>	<b>2,459.6</b>