

PAVING SCHEDULE

LOCATION		LENGTH	AVERAGE PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (COVER AND SEAL COATS)		SEAL COAT AGGREGATE
STATION	TO STATION	FOOT	FOOT	SO YD	GALLON	TON	
1+29.00	TO 7+67.62	638.6	VAR	2866.7	1003.3	35.8	
7+67.62	TO 27+71.62	2004.0	24.0	5566.7	1948.3	69.6	
27+71.62	TO 43+51.04	1579.4	26.0	4738.3	1658.4	59.2	
43+51.04	TO 44+60.18	109.1	24.0	303.2	106.1	3.8	
44+60.18	TO 45+77.72	117.5	BRIDGE OMISSION				
45+77.72	TO 66+46.45	2068.7	24.0	5746.5	2011.3	71.8	
66+46.45	TO 67+56.21	109.8	BRIDGE OMISSION				
67+56.21	TO 154+16.12	8659.9	24.0	24055.3	8419.4	300.7	
154+16.12	TO 155+33.66	117.5	BRIDGE OMISSION				
155+33.66	TO 172+71.41	1737.8	24.0	4827.1	1689.5	60.3	
172+71.41	TO 174+51.72	180.3	BRIDGE OMISSION				
174+51.72	TO 227+31.10	5279.4	24.0	14664.9	5132.7	183.3	
227+31.10	TO 228+36.74	105.6	BRIDGE OMISSION				
228+36.74	TO 302+42.96	7406.2	24.0	20572.8	7200.5	257.2	
302+42.96	TO 302+56.05	13.1	RR OMISSION				
302+56.05	TO 430+85.00	12829.0	24.0	35636.0	12472.6	445.4	
TOTALS		42956		118977	41642	1487	

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	PAINT PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	SO FT
1+29.00 TO 5+33.00	404	875	1974	271	45		40	3.3
5+33.00 TO 11+57.00	624	2416					64	5.3
11+57.00 TO 20+06.00	849	1780					84	7.0
20+06.00 TO 31+93.00	1187	3858					120	10.0
31+93.00 TO 37+95.00	602	2408					60	5.0
37+95.00 TO 49+26.00	1131	3623					112	9.3
49+26.00 TO 51+31.00	205	461					20	1.7
51+31.00 TO 61+41.00	1010	3183					100	8.3
61+41.00 TO 62+57.00	116	205					12	1.0
62+57.00 TO 70+30.00	773	2392					76	6.3
70+30.00 TO 226+23.00	15593	35029					1560	130.0
226+23.00 TO 233+55.00	732	2239					72	6.0
233+55.00 TO 235+61.00	206	464					20	1.7
235+61.00 TO 242+68.00	707	2148					72	6.0
242+68.00 TO 297+80.00	5512	12402					552	46.0
297+80.00 TO 302+43.00	463	1505			48	57	48	4.0
302+43.00 TO 302+56.00	13	0					0	0.0
302+56.00 TO 306+40.00	384	1248			48	57	0	0.0
306+40.00 TO 430+85.00	12445	27881					1244	103.7
TOTALS		104116	1974	271	141	114	4256	354.6