

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

TOTAL
 QUANTITIES

L23EL	L23EU		L23EL	L23EL	L23EU
ACF	ACM	ACM	ACF	ACF	ACM
80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY
ROADWAY 0001	ROADWAY 0001	ROADWAY 0001	BOX CULVERT SN 082-0400	HIGHWAY LIGHTING	BICYCLE/PEDS 0028
URBAN F.A.P. 809	URBAN F.A.U. 9251	URBAN F.A.U. 9269	FAP 809 URBAN	0021 URBAN	URBAN FAU

CODE NO	ITEM	UNIT							
20100500	TREE REMOVAL, ACRES	ACRE	0.5	0.5					
20200100	EARTH EXCAVATION	CU YD	6230	5201	473	556			
20400800	FURNISHED EXCAVATION	CU YD	4695	4545		150			
20800150	TRENCH BACKFILL	CU YD	2094	1856	74	164			
X 25000210	SEEDING, CLASS 2A	ACRE	2	1.75	0.1	0.15			
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	174	159	3	12			
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	174	159	3	12			
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	174	159	3	12			
X 25000700	AGRICULTURAL GROUND LIMESTONE	TON	4	3.6	0.1	0.3			
X 25100115	MULCH, METHOD 2	ACRE	2	1.75	0.1	0.15			
25100630	EROSION CONTROL BLANKET	SQ YD	1804	1804					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	782	764	12	6			
28000305	TEMPORARY DITCH CHECKS	FOOT	6	6					
28000400	PERIMETER EROSION BARRIER	FOOT	4460	3670	330	460			

X SPECIALTY ITEM

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -
ci:\pv_work\pwidot\owenbj\d0133899\p110825a.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -
PLOT DATE = 3/23/2012		DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 15 SHEETS STA. TO STA.

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	135-N	ST. CLAIR	206	3
CONTRACT NO. 76D06			ILLINOIS FED. AID PROJECT	