

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	L23EL	L23EU		L23EL	L23E	L23EU		
				ACF	ACM	ACM	ACF	ACF	ACM		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE FAP 809	80% FEDERAL 20% STATE FAP	80% FEDERAL 10% STATE 10% CITY		
				ROADWAY 0001	ROADWAY 0001	ROADWAY 0001	BOX CULVERT SN 082-0400	HIGHWAY LIGHTING	BICYCLE/PEDS 0028		
	URBAN F.A.P. 809	URBAN F.A.U. 9251	URBAN F.A.U. 9269	0040 URBAN	0021 URBAN	URBAN FAU					
54003000	CONCRETE BOX CULVERTS	CU YD	314.6				314.6				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2							
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	4							
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3							
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1							
54248510	CONCRETE COLLAR	CU YD	1.8	1.8							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	841	561	141	139					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	193	50	143						
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	178	178							
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	18	18							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	470	430		40					
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	395	395							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	32	32							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	200	200							

FILE NAME =	USER NAME = owerbj	DESIGNED -	REVISED -
es:\pwwork\pwwork\overbj\d0133099\p1n10005e.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -
PLOT DATE = 3/23/2012		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>			
SCALE:	SHEET 5	OF 15 SHEETS	STA. TO STA.

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	135-N	ST. CLAIR	206	7
CONTRACT NO. 76D06				
ILLINOIS FED. AID PROJECT				