

ILLINOIS DEPARTMENT OF TRANSPORTATION				L23EL	L23EU	L23EL	L23E	L23EU		
SUMMARY OF QUANTITIES				ACF	ACM	ACM	ACF	ACF	ACM	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY	ROADWAY	ROADWAY	BOX CULVERT SN 082-0400	HIGHWAY LIGHTING	BICYCLE/PEDS	
				0001	0001	0001	FAP 809	0021	0028	
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	
				F.A.P. 809	F.A.U. 9251	F.A.U. 9269	URBAN	URBAN	FAU	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	396				396			
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1						
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1						
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	907	907						
Z0054400	ROCK FILL	CU YD	160				160			
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	362	313	49					
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	51	51						
Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	54	54						
Z0056626	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	10	10						
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1	1						
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	669				669			
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	1				1			
41000680	PORTLAND CEMENT CONCRETE PAVEMENT 19"	SQ YD	619						619	

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -
ci:\pw_work\pwwork\owenbj\d0133118\0876008-S00 sheets.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 14 OF 15 SHEETS STA. TO STA.

F.A.P. RTE. ①	SECTION 135-N	COUNTY ST. CLAIR	TOTAL SHEETS 206	SHEET NO. 16
CONTRACT NO. 76006			ILLINOIS FED. AID PROJECT	

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269