

PAVING

LOCATION	STATION	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	SUBBASE GRANULAR MATERIAL, TYPE B, 8"	SUBBASE GRANULAR MATERIAL, TYPE B, 12"	PORTLAND CEMENT CONCRETE BASE COURSE, 9"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	PORTLAND CEMENT CONCRETE PAVEMENT, 9" (SPECIAL)	PORTLAND CEMENT CONCRETE PAVEMENT, 9"	PORTLAND CEMENT CONCRETE PAVEMENT, 19"	PAVEMENT FABRIC	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	
		SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	
IL 158	0+00.00 TO 5+37.78			3760									2153	619	2772	2772	
	0+50.42 TO 50+50.44												409		409	409	
	4+69.86 TO 30+67.92												456		456	456	
	50+00.00 TO 51+75.00 RT			1310									1468		1468	1468	
	51+75.00							30									
	51+75.00 TO 52+50.66			37		0.3	2		21	42							
	51+75.00 TO 53+00.00 LT			59													
	52+24.94 RT			69												91	91
	52+49.66 RT			151												143	143
	52+77.14 TO 53+40.60 RT			2												78	78
52+97.78 LT			58														
53+00.00							31										
CENTREVILLE AVE	30+00.00 TO 34+71.81			1515	118								864		864	864	
	31+71.70							26									
	31+66.98 TO 34+71.81					0.4	4		55	110							
	31+71.69 TO 33+60.02 RT			64													
	32+30.05 RT			87												89	89
	33+36.18 RT			108												107	107
	33+60.12 TO 33+77.65 RT			10													
	34+71.81							26									
	10+81.83 TO 12+60.00			500									293		293	293	
	11+77.80 TO 21+18.53											129			129	129	
IL 13 / IL 158	20+72.00 TO 22+87.50			1081								1078		1078	1078		
	22+00.00 LT	209													196	196	
	22+87.50 TO 24+05.55					0.1	1		16	31							
	22+87.50 TO 24+05.58 LT	40															
22+87.50 TO 24+05.58 RT	41																
24+05.55							20										
IL 13 / 158 & CENTREVILLE IL 13	21+11.54 TO 31+17.50											48		48	48		
	40+62.46 TO 42+86.84			948								717		717	717		
	41+61.10 TO 43+66.07 RT	105				0.3	3		40	80							
	42+04.13 RT	68													70	70	
	42+86.84 TO 44+08.08 LT	50															
	43+09.69 RT	50													51	51	
	43+86.10 RT	87													77	77	
	44+08.08							27									
TEMPORARY WHISKEY ROAD WHISKEY ROAD	60+37.99 TO 61+06.47			113		0.1	0		5	9.0							
	60+64.25 TO 61+94.51			267	132	0.2	0		9	17			104		104	104	
61+03.00							51										
IL 15 EB ENTRANCE RAMP	70+58.79 TO 71+60.00			261									189		189	189	
IL 15 EB EXIT RAMP	80+56.64 TO 81+60.00			299									226		226	226	
IL 15 WB ENTRANCE RAMP	90+30.29 TO 97+23.37			2368									1925		1925	1925	
IL 15 WB ENTRANCE BYPASS	100+50.14 TO 104+90.48			996									829		829	829	
TEMPORARY RUNAROUND	1+00.00 TO 5+14.37			1543		2.3	5.0		723	145.0							
TOTAL		1295	380	14713	118	3.7	15	211	869	434	1042	9846	619	11507	12409	902	

SEEDING

LOCATION	SEEDING, CLASS 2A	NITROGEN NUTRIENT FERTILIZER	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	ACRE	POUND	POUND	POUND	TON	ACRE
IL 158	0.49	44	44	44	1	0.49
CENTREVILLE AVENUE	0.13	12	12	12	0.3	0.13
IL 15 WB EXIT RAMP	0.11	10	10	10	0.2	0.11
IL 13 / 158	0.20	18	18	18	0.4	0.20
IL 13	0.03	3	3	3	0.1	0.03
WHISKEY ROAD	0.13	12	12	12	0.3	0.13
IL 15 EB ENTRANCE RAMP	0.04	4	4	4	0.1	0.04
IL 15 EB EXIT RAMP	0.14	13	13	13	0.3	0.14
IL 15 WB ENTRANCE RAMP	0.34	31	31	31	0.7	0.34
IL 15 WB ENTRANCE BYPASS	0.30	27	27	27	0.6	0.30
TOTAL	1.91	174	174	174	4.00	1.91
TOTAL	PAY 2.00					PAY 2.00

TREE REMOVAL

LOCATION	STATION				TREE REMOVAL, ACRES	
	ACRE	ACRE	ACRE	ACRE	ACRE	
IL 15 WB ENTRANCE RAMP	90+11.89	72.90	RT TO	92+00.00	39.02	0.40
TOTAL					PAY 0.50	

LAST SAVED = 2/29/2012
 PEN TABLE = V:\H\1414
 PLOT DRIVER = TR-18pdf-Block-Half.plt

FILE NAME =	USER NAME = bschmidt	DESIGNED -	REVISED -
1:\0906600\0906603\Cad\T\Plans\005-D876006-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 3/29/2012 10:58:31 AM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**



SCHEDULE OF QUANTITIES
PAVING, SEEDING, TREE REMOVAL

SCALE: NONE SHEET NO. 2 OF 8 SHEETS STA. TO STA.

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	135-N	ST. CLAIR	206	25
CONTRACT NO. 76D06				
ILLINOIS FED. AID PROJECT				