

PAVEMENT MARKING												
LOCATION	PREFORMED PLASTIC PAVEMENT MARKING - TYPE B TAPE											RAISED REFLECTIVE PVMT MKR TWO WAY AMBER
	LETTERS AND SYMBOLS	LINE 4" WHITE	LINE 4" YELLOW	LINE 4" YELLOW 10'-30'-10' SKIP DASH	LINE 4" WHITE 2'-6'-2' SKIP DASH	LINE 8" WHITE	LINE 8" YELLOW	LINE 12" WHITE	LINE 12" YELLOW	LINE 12" WHITE 3'-3'-3' SKIP DASH	PAINT CURB	
	A SQ FT	B FOOT	C FOOT	D FOOT	K FOOT	G FOOT	J FOOT	H FOOT	I FOOT	F FOOT	L EACH	
IL158 / CENTERVILLE AVE												
STA 50+53.16 42.92' LT TO STA 50+68.57 10.49' LT										18		
STA 50+54.35 47.10' RT TO STA 51+37.84 20.14' RT		87						11				
STA 50+68.18 21.19' RT TO STA 50+68.57 10.49' LT		33										
STA 50+68.18 21.19' RT TO STA 51+37.74 6.15' RT				71					25			
STA 50+70 TO STA 51+37 AND 6.44' LT				70							153.70	
STA 50+71.16 13.77' LT TO STA 50+76.74 26.61' LT	6.8											
STA 51+37.74 5.56' LT TO STA 53+00.00 5.56' LT					40							
STA 51+37.74 5.56' RT TO STA 53+00.00 5.56' RT					30							
STA 51+37.74 6.44' LT TO STA 53+00.00 6.44' LT				162					51			
STA 51+37.74 6.44' RT TO STA 53+00.00 6.44' RT				162								
STA 51+60.33 6.01' LT TO STA 52+66.88 6.01' LT												3
STA 51+60.33 6.01' RT TO STA 52+66.88 6.01' RT												3
STA 52+33.69 2.31' RT	15.6											
STA 52+61.93 2.49' LT	15.6											
STA 0+00 52.33' RADIUS				329								
STA 0+46.12 52.66' LT TO STA 0+68.11 16.17' LT										21		
STA 0+68.11 16.17' LT TO STA 0+69.99 1.24' RT		18										
STA 0+67.54 18.41' RT TO STA 1+29.53 5.00' RT					16							
STA 0+69.99 1.24' RT TO STA 3+33.17 9.58' LT				266								
STA 0+70 TO STA 2+99											470.40	
STA 0+70.35 19.69' LT TO STA 0+76.15 32.44' LT	6.8											
STA 0+89.93 28.36' LT TO STA 3+51.02 24.17' LT		261										
STA 1+28.78 1.34' RT	15.6											
STA 1+29.53 5.00' RT TO STA 3+33.05 5.00' RT		204										
STA 2+10.15 1.27' RT	15.6											
STA 2+95.47 2.18' RT	15.6											
STA 0+68.11 16.17' LT TO STA 3+33.17 9.58' LT				268								
STA 2+97.07 12.17' LT TO STA 3+33.17 9.58' LT									22			
STA 3+33.05 5.00' RT TO STA 3+47.65 5.00' RT						15						
STA 3+33.05 5.00' RT TO STA 3+65.43 13.00' LT						37						
STA 3+33.05 5.00' RT TO STA 3+65.43 13.00' LT								9				
STA 3+47.65 5.00' RT TO STA 4+51.69 15.67' RT				106								
STA 3+51 TO STA 4+50											231.60	
STA 3+65.43 13.00' LT TO STA 4+53.93 25.01' LT				90								
STA 3+96.14 13.00' LT TO STA 4+53.93 25.01' LT									12			
STA 4+41.51 33.46' RT TO STA 4+49.69 17.42' RT	8.5											
STA 4+51.69 15.67' RT TO STA 4+73.29 59.14' RT										24		
STA 4+51.96 15.67' RT TO STA 4+53.93 25.01' LT		41										
STA 5+37.78 69.83' RADIUS				439								
STA 30+74.54 45.83' LT TO STA 30+86.79 11.13' LT										18		
STA 30+75.79 46.55' LT TO STA 30+81.25 41.46' LT		7										
STA 30+77.14 48.37' RT TO STA 30+79.71 46.46' RT		3										
STA 30+83.96 24.64' RT TO STA 30+86.79 11.13' RT		11										
STA 30+83.96 24.64' RT TO STA 31+13.02 13.31' RT				31					15			
STA 30+88.43 13.15' LT TO STA 30+97.69 28.59' LT	8.5											
STA 30+90 TO STA 31+70											186.20	
STA 41+39 21.3' RT IL 13 TO STA 31+54 15.4' LT											256.60	
STA 31+11.98 9.70' RT TO STA 31+17.01 27.14' RT								18				
STA 31+12.03 3.13' LT TO STA 31+17.31 19.49' LT								17				

① F.A.P. RTE 809 / F.A.U. RTE 9269

FILE NAME =	USER NAME = CFC..	DESIGNED -	REVISED -
...\\033-0876006-Sht-schedule-010.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
CB PROJECT NO	PLOT DATE = 3/20/2012	DATE - / /	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES - PAVEMENT MARKING  
IL 158 / CENTERVILLE AVENUE

SCALE: SHEET NO. 10 OF 13 SHEETS STA. TO STA.

**CB** Coombe-Bloxdorf P.C.  
- CIVIL ENGINEERS -  
- STRUCTURAL ENGINEERS -  
- LAND SURVEYORS -  
Design Firm License No. 184-002703

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	135-N	ST. CLAIR	206	33
			CONTRACT NO. 76D06	
ILLINOIS FED. AID PROJECT				