

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	COVER SHEET
2	SIGNATURE SHEET
3	INDEX OF SHEETS, STANDARDS, GENERAL NOTES
4-7	SUMMARY OF QUANTITIES
8	EXISTING PERMANENT SURVEY MARKER TIES (CONTROL POINTS)
9	TYPICALS
10	EARTHWORK SCHEDULE
11-14	PLAN SHEETS / PROFILE SHEETS
15	DETAILS - AGGREGATE DITCH CHECK
16-17	DETAILS - DRAINAGE CONTROL STRUCTURES
18	DETAILS - DITCH PLUG
19	DETAILS - SWALE EXCAVATION
20-86	CROSS SECTIONS HIGHWAY STANDARDS

HIGHWAY STANDARDS

000001-06	280001-06
001001-02	542401-01
001006	666001-01
	667101-02

GENERAL NOTES

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES.

ALL AGGREGATE	2.05 TON/CU YD
RIP RAP	1.5 TON/CU YD

SEEDING SHALL BE DONE ON ALL AREAS THAT ARE DISTURBED BY CONSTRUCTION OPERATIONS AS DIRECTED BY THE ENGINEER. SEEDING SHALL BE PAID FOR ONLY WITHIN THE PROPOSED RIGHT-OF-WAY OR EASEMENT LIMITS. ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE SEEDDED AS DIRECTED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE.

WHERE SECTION OR SUB-SECTION MARKERS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE DEPARTMENT AND AUTHORIZED AGENT OR LAND SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\lavender\ba\d0277604\78278-sht-details.dgn		DRAWN -	REVISED -			853	-	FRANKLIN	86	3
	PLOT SCALE = 100.0000 / / in	CHECKED -	REVISED -							
	PLOT DATE = 3/20/2012	DATE -	REVISED -		SCALE:	SHEET NO. OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT
										CONTRACT NO. 78278