

PAVEMENT MARKING SCHEDULE

STATION TO STATION	PAINT PAVEMENT MARKING		TEMPORARY	SHORT-TERM	NOTES	
	4 INCH WHITE (EDGE LINE)	4 INCH (SKIP-DASH)	4 INCH	4 INCH		
	FOOT	FOOT	FOOT	FOOT		
MAINLINE: STA 210+08 TO STA 238+45						
210+08.0	TO	238+45.0	5,674	709	9,220	567
TOTAL			5,674	709	9,220	567

SEEDING SCHEDULE

LOCATION STATION TO STATION	LENGTH	WIDTH (EAST SIDE)	SEEDING AREA	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	AGRICULTURAL GROUND LIMESTONE	SEEDING, CLASS 2	MULCH, METHOD 2		
	(FOR INFORMATION ONLY)										
	FT	FT	ACRES	POUNDS	POUNDS	POUNDS	TONS	ACRE	ACRE		
212+22.0	TO	238+45.0	2623	10	0.60	54	54	54	1	0.60	0.60
SEEDING TOTALS			2623			54	54	54	1	0.60	0.60
			0.50	MILES							