



- | | | | |
|--|---|--|--|
| | HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT | | SIDEWALK REMOVAL |
| | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | | PAVEMENT REMOVAL & DRIVEWAY PAVEMENT REMOVAL |
| | SHOULDER REMOVAL | | COMBINATION CONCRETE CURB & GUTTER REMOVAL |

- A - MANHOLE OR INLET TO BE ADJUSTED
 R - MANHOLE, INLET OR LIGHT POLE BASE TO BE REMOVED
 RL - LIGHT POLE, LIGHTING CONTROLLER, FIRE HYDRANT, AND WATER VALVE TO BE RELOCATED (SEE LIGHTING AND WATER MAIN PLANS)
 - STORM SEWER TO BE REMOVED
 X - TREE REMOVAL

NOTE: IN ADDITION TO THE ITEMS SHOWN TO BE REMOVED, RELOCATED OR ADJUSTED HERE, UTILITIES OWNED BY OTHERS MUST ALSO BE REMOVED, RELOCATED OR ADJUSTED. THE CONTRACTOR SHALL COORDINATE HIS WORK WITH THOSE UTILITIES.

CHAMPLIN & ASSOCIATES, INC. © 2011
 DRAWING: \\nasdaq\cadd\113-Env-Survey\CAD\CADD\PLANS-EXTENDED\018-REM-98-202.dwg, Last Modified: Feb 16, 2012 - 8:29am, Plotted on: Mar 27, 2012 - 1:43pm by narcoia

DRAWN BY: NV	REVISIONS			
CHECKED BY: JKC	LEVEL	BY	DATE	DESCRIPTION
DATE: 02/12				

CHAMPLIN & ASSOCIATES
 PERU MORRIS ILLINOIS

FAS 301 / FAU 383
 SECTION 11-00007-00-WR
 VILLAGE OF DIAMOND
 GRUNDY AND WILL COUNTIES

REMOVAL PLAN - WILL ROAD
 STA. 98+00 TO STA. 202+00

CONSTRUCTION PLANS

CONTRACT NO. 87520	
CURRENT AS OF: 02/12	
SCALE: AS NOTED	SHEET 18
FILE NO.: 66022.01 Y-	OF 96