

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0011

PAY CODE	QUANTITY	UNIT	ITEM
20100500	0.17	Acre	Tree Removal, Acres
20300100	57	Cu. Yd.	Channel Excavation
20400800	40	Cu. Yd.	Furnished Excavation
25100630	956	Sq. Yd.	Erosion Control Blanket
28000400	534	Foot	Perimeter Erosion Barrier
*40200100	264	Ton	Aggregate Surface Course, Type A
50100100	1	Each	Removal of Existing Structures
*50300225	27.4	Cu. Yd.	Concrete Structures
50400505	1,420	Sq. Ft.	Precast Prestressed Concrete Deck Beams (27" Depth)
50800105	3,540	Pound	Reinforcement Bars
Δ 50900205	121	Foot	Steel Railing, Type S-1
51200957	268	Foot	Furnishing Metal Shell Piles 12" x 0.250"
51202305	268	Foot	Driving Piles
51203200	2	Each	Test Pile Metal Shells
51500100	1	Each	Name Plates
67100100	1	L. Sum	Mobilization
Z0013798	1	L. Sum	Construction Layout
*X2020410	125	Cu. Yd.	Earth Excavation (Special)
*X2070302	112	Ton	Porous Granular Embankment, Special
*X2501100	0.20	Acre	Seeding, Class 3 (Special)
*X2810208	398	Ton	Stone Riprap, Class A4 (Special)
*X7010216	1	L. Sum	Traffic Control and Protection, (Special)

*See B.L.R. 11310 in the contract documents for Special Provisions.

Δ Specialty Items

FILE = S:\PROJECTS\2010\1287012 - Bureau Co. TR106 DESIGN STRUCTURE\Drawings\1287012_Summary of Quantities.dgn

DESIGNED -	MICHAEL WAGNER	REVISED -	
CHECKED -	MEGAN CACKLEY	REVISED -	
DRAWN -	RON ALLEN	REVISED -	
CHECKED -	BRIAN CONVERSE	REVISED -	

BUREAU COUNTY
T.R. 106 (850 E. ST.) OVER HICKORY CREEK
STATION 20 + 00

SUMMARY OF QUANTITIES
STRUCTURE NO. 006-4218

TWP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
106	08-15119-00-BR	BUREAU	18	2
WHA# 1287010		CONTRACT NO. 87523		
ILLINOIS FED. AID PROJECT BROS-00110861				