

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-02-AS	WOODFORD	53	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SEEDING SCHEDULE (1 OF 2)						25000100	25000200	25100115	28000250	25000400	25000500	25000600
LOCATION	PLAN AREA	PLAN AREA	PLAN AREA X SLOPE FACTOR (1.03)	PLAN AREA X SLOPE FACTOR (1.06)	TOTAL AREA	SEEDING, CLASS 1	SEEDING, CLASS 2	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER		
										NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
STATION TO STATION	FORESLOPES (1:4)	BACKSLOPES (1:3)	FORESLOPES (1:4)	BACKSLOPES (1:3)					100 LBS/ACRE X 3 APPLICATIONS	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE
	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND
RIGHT SIDE												
STA. 280+00.00 RT TO STA. 290+00.00 RT	18625.21	10436.11	19183.97	11062.28	30246.24		0.69	0.69	208.31	62.49	62.49	62.49
STA. 290+00.00 RT TO STA. 296+25.00 RT	10772.44	6654.94	11095.61	7054.24	18149.85		0.42	0.42	125.00	37.50	37.50	37.50
STA. 296+25.00 RT TO STA. 304+00.00 RT	15015.49	8956.63	15465.95	9494.03	24959.98		0.57	0.57	171.90	51.57	51.57	51.57
STA. 304+00.00 RT TO STA. 305+00.00 RT	2774.03	1101.97	2857.25	1168.09	4025.34		0.09	0.09	27.72	8.32	8.32	8.32
STA. 305+00.00 RT TO STA. 320+00.00 RT	33111.56	14856.95	34104.91	15748.37	49853.27		1.14	1.14	343.34	103.00	103.00	103.00
STA. 320+00.00 RT TO STA. 324+00.00 RT	6900.20	3489.17	7107.21	3698.52	10805.73		0.25	0.25	74.42	22.33	22.33	22.33
STA. 324+00.00 RT TO STA. 330+69.00 RT	12441.37	6501.36	12814.61	6891.44	19706.05		0.45	0.45	135.72	40.71	40.71	40.71
STA. 330+69.00 RT TO STA. 335+00.00 RT	8196.02	6330.41	8441.90	6710.23	15152.14		0.35	0.35	104.35	31.31	31.31	31.31
STA. 335+00.00 RT TO STA. 336+94.00 RT	3638.79	1993.76	3747.95	2113.39	5861.34		0.13	0.13	40.37	12.11	12.11	12.11
STA. 336+94.00 RT TO STA. 340+16.00 RT	5272.99	2878.20	5431.18	3050.89	8482.07		0.19	0.19	58.42	17.52	17.52	17.52
STA. 340+16.00 RT TO STA. 341+63.00 RT	1510.12	0.00	1555.42	0.00	1555.42	0.04		0.04	10.71	3.21	3.21	3.21
STA. 341+63.00 RT TO STA. 342+12.00 RT	244.12	0.00	251.44	0.00	251.44	0.01		0.01	1.73	0.52	0.52	0.52
STA. 342+12.00 RT TO STA. 343+30.00 RT	1620.65	35.31	1669.27	37.43	1706.70	0.04		0.04	11.75	3.53	3.53	3.53
STA. 343+30.00 RT TO STA. 343+76.00 RT	952.20	184.76	980.77	195.85	1176.61		0.03	0.03	8.10	2.43	2.43	2.43
STA. 343+76.00 RT TO STA. 343+86.00 RT	221.81	59.49	228.46	63.06	291.52		0.01	0.01	2.01	0.60	0.60	0.60
STA. 343+86.00 RT TO STA. 350+00.00 RT	11101.19	5380.94	11434.23	5703.80	17138.02		0.39	0.39	118.03	35.41	35.41	35.41
STA. 350+00.00 RT TO STA. 357+20.00 RT	10441.85	9980.10	10755.11	10578.91	21334.01		0.49	0.49	146.93	44.08	44.08	44.08
STA. 357+20.00 RT TO STA. 365+00.00 RT	13639.37	9086.68	14048.55	9631.88	23680.43		0.54	0.54	163.09	48.93	48.93	48.93
STA. 365+00.00 RT TO STA. 367+24.00 RT	2313.96	3076.21	2383.38	3260.78	5644.16		0.13	0.13	38.87	11.66	11.66	11.66
STA. 367+24.00 RT TO STA. 380+00.00 RT	21523.50	14192.67	22169.21	15044.23	37213.44		0.85	0.85	256.29	76.89	76.89	76.89
STA. 380+00.00 RT TO STA. 381+00.00 RT	1061.42	1133.97	1093.26	1202.01	2295.27		0.05	0.05	15.81	4.74	4.74	4.74
STA. 381+00.00 RT TO STA. 384+05.00 RT	4721.32	4783.34	4862.96	5070.34	9933.30		0.23	0.23	68.41	20.52	20.52	20.52
STA. 384+05.00 RT TO STA. 390+70.00 RT	11637.80	6387.30	11986.93	6770.54	18757.47		0.43	0.43	129.18	38.76	38.76	38.76
TOTAL RIGHT SIDE ONLY						0.08	7.45	7.53	2260.47	678.14	678.14	678.14

PLOT DATE * DATE *
 FILE NAME * FILE *
 PLOT SCALE * SCALE *
 USER NAME * USER *

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
 DATE: MARCH 2012
 DRAWN BY: AMPH & KLM
 CHECKED BY: JLH