

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-02-AS	WOODFORD	53	8
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SEEDING SCHEDULE (2 OF 2)						25000100	25000200	25100115	28000250	25000400	25000500	25000600
LOCATION	PLAN AREA	PLAN AREA	PLAN AREA X SLOPE FACTOR		TOTAL AREA	SEEDING, CLASS 1	SEEDING, CLASS 2	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER		
			PLAN AREA X SLOPE FACTOR (1.03)	PLAN AREA X SLOPE FACTOR (1.06)						NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
STATION TO STATION	FORESLOPES (1:4)	BACKSLOPES (1:3)	FORESLOPES (1:4)	BACKSLOPES (1:3)					100 LBS/ACRE X 3 APPLICATIONS	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE
	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND
<b>LEFT SIDE</b>												
STA. 280+00.00 LT TO STA. 290+00.00 LT	18200.25	6797.30	18746.26	7205.14	25951.40		0.60	0.60	178.73	53.62	53.62	53.62
STA. 290+00.00 LT TO STA. 296+25.00 LT	10436.71	4014.59	10749.81	4255.47	15005.28		0.34	0.34	103.34	31.00	31.00	31.00
STA. 296+25.00 LT TO STA. 304+00.00 LT	13917.27	7744.34	14334.79	8209.00	22543.79		0.52	0.52	155.26	46.58	46.58	46.58
STA. 304+00.00 LT TO STA. 305+00.00 LT	4050.56	1679.53	4172.08	1780.30	5952.38		0.14	0.14	40.99	12.30	12.30	12.30
STA. 305+00.00 LT TO STA. 320+00.00 LT	25852.23	13056.74	26627.80	13840.14	40467.94		0.93	0.93	278.70	83.61	83.61	83.61
STA. 320+00.00 LT TO STA. 324+00.00 LT	6231.74	3041.89	6418.69	3224.40	9643.10		0.22	0.22	66.41	19.92	19.92	19.92
STA. 324+00.00 LT TO STA. 330+69.00 LT	11997.89	4189.43	12357.83	4440.80	16798.62		0.39	0.39	115.69	34.71	34.71	34.71
STA. 330+69.00 LT TO STA. 335+00.00 LT	5284.21	3700.36	5442.74	3922.38	9365.12		0.21	0.21	64.50	19.35	19.35	19.35
STA. 335+00.00 LT TO STA. 336+94.00 LT	2323.70	1485.54	2393.41	1574.67	3968.08		0.09	0.09	27.33	8.20	8.20	8.20
STA. 336+94.00 LT TO STA. 340+16.00 LT	5021.85	2027.01	5172.51	2148.63	7321.14		0.17	0.17	50.42	15.13	15.13	15.13
STA. 340+16.00 LT TO STA. 341+63.00 LT	2518.61	1140.47	2594.17	1208.90	3803.07		0.09	0.09	26.19	7.86	7.86	7.86
STA. 341+63.00 LT TO STA. 342+12.00 LT	836.44	952.80	861.53	1009.97	1871.50	0.04		0.04	12.89	3.87	3.87	3.87
STA. 342+12.00 LT TO STA. 343+30.00 LT	2249.54	2328.71	2317.03	2468.43	4785.46	0.11		0.11	32.96	9.89	9.89	9.89
STA. 343+30.00 LT TO STA. 343+76.00 LT	500.00	919.23	515.00	974.38	1489.38	0.03		0.03	10.26	3.08	3.08	3.08
STA. 343+76.00 LT TO STA. 343+86.00 LT	0.00	171.48	0.00	181.77	181.77	0.00		0.00	1.25	0.38	0.38	0.38
STA. 343+86.00 LT TO STA. 350+00.00 LT	10101.97	4600.00	10405.03	4876.00	15281.03		0.35	0.35	105.24	31.57	31.57	31.57
STA. 350+00.00 LT TO STA. 357+20.00 LT	10442.22	8006.91	10755.49	8487.32	19242.81		0.44	0.44	132.53	39.76	39.76	39.76
STA. 357+20.00 LT TO STA. 365+00.00 LT	14993.38	6835.82	15443.18	7245.97	22689.15		0.52	0.52	156.26	46.88	46.88	46.88
STA. 365+00.00 LT TO STA. 367+24.00 LT	3449.46	1628.00	3552.94	1725.68	5278.62		0.12	0.12	36.35	10.91	10.91	10.91
STA. 367+24.00 LT TO STA. 380+00.00 LT	21116.05	10154.60	21749.53	10763.88	32513.41		0.75	0.75	223.92	67.18	67.18	67.18
STA. 380+00.00 LT TO STA. 381+00.00 LT	1466.27	948.47	1510.26	1005.38	2515.64		0.06	0.06	17.33	5.20	5.20	5.20
STA. 381+00.00 LT TO STA. 384+05.00 LT	4536.73	3831.01	4672.83	4060.87	8733.70		0.20	0.20	60.15	18.04	18.04	18.04
STA. 384+05.00 LT TO STA. 390+70.00 LT	11346.60	6313.00	11687.00	6691.78	18378.78		0.42	0.42	126.58	37.97	37.97	37.97
<b>TOTAL LEFT SIDE ONLY</b>						<b>0.19</b>	<b>6.55</b>	<b>6.74</b>	<b>2023.29</b>	<b>606.99</b>	<b>606.99</b>	<b>606.99</b>
<b>TOTAL LEFT &amp; RIGHT SIDE</b>						<b>0.27</b>	<b>14.01</b>	<b>14.28</b>	<b>4283.75</b>	<b>1285.13</b>	<b>1285.13</b>	<b>1285.13</b>

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

DESIGNED BY: AMPH & KLM      DRAWN BY: AMPH & KLM  
 DATE: MARCH 2012      CHECKED BY: JLH