

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-02-AS	WOODFORD	53	9
STA. _____ TO STA. _____		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT		

TEMPORARY DITCH CHECK SCHEDULE (1 OF 4)

LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
RIGHT SIDE				
STA. 283+00.00 RT TO STA. 284+00.00 RT	100.00	0.50	200	
STA. 284+00.00 RT TO STA. 285+00.00 RT	100.00	1.60	94	
STA. 284+47.00 RT				14
STA. 285+00.00 RT TO STA. 287+81.00 RT	281.00	0.90	200	
STA. 285+90.00 RT				14
STA. 287+81.00 RT TO STA. 290+00.00 RT	219.00	1.19	136	
STA. 288+20.00 RT				14
STA. 289+50.00 RT				14
STA. 290+00.00 RT TO STA. 291+00.00 RT	100.00	1.63	94	
STA. 290+45.00 RT				14
STA. 291+00.00 RT TO STA. 294+00.00 RT	300.00	1.27	125	
STA. 291+50.00 RT				14
STA. 292+75.00 RT				14
STA. 294+00.00 RT TO STA. 296+00.00 RT	200.00	0.50	200	
STA. 294+00.00 RT				14
STA. 296+00.00 RT TO STA. 298+00.00 RT	200.00	1.28	125	
STA. 297+25.00 RT				14
STA. 298+00.00 RT TO STA. 299+00.00 RT	100.00	1.50	100	
STA. 298+40.00 RT				14
STA. 299+00.00 RT TO STA. 300+00.00 RT	100.00	1.80	83	
STA. 299+30.00 RT				14
STA. 300+00.00 RT TO STA. 302+00.00 RT	200.00	2.50	50	
STA. 300+05.00 RT				14
STA. 300+55.00 RT				14
STA. 301+05.00 RT				14
STA. 301+55.00 RT				14
STA. 302+00.00 RT TO STA. 303+00.00 RT	100.00	1.90	79	
STA. 302+05.00 RT				14
STA. 302+84.00 RT				14
STA. 303+00.00 RT TO STA. 303+50.00 RT	50.00	1.09	150	
STA. 303+50.00 RT TO STA. 303+80.00 RT	30.00	8.38	21	
STA. 303+80.00 RT TO STA. 304+60.00 RT	80.00	0.50	200	
STA. 304+60.00 RT TO STA. 317+35.50 RT	1275.5	0.30	200	
STA. 306+50.00 RT				14
STA. 308+50.00 RT				14
STA. 310+50.00 RT				14
STA. 312+50.00 RT				14
STA. 314+50.00 RT				14
STA. 316+50.00 RT				14
STA. 317+35.50 RT TO STA. 324+00.00 RT	664.50	0.46	200	
STA. 318+00.00 RT				14
STA. 320+00.00 RT				14
STA. 322+00.00 RT				14
STA. 324+00.00 RT TO STA. 326+00.00 RT	200.00	0.30	200	
STA. 326+00.00 RT				14
STA. 326+00.00 RT TO STA. 327+82.50 RT	182.50	0.60	200	
STA. 327+82.50 RT TO STA. 331+25.00 RT	342.5	0.50	200	
STA. 329+00.00 RT				14
STA. 331+25.00 RT TO STA. 332+00.00 RT	75	2.38	65	
STA. 331+70.00 RT				14
STA. 332+00.00 RT TO STA. 337+00.00 RT	500	0.30	200	
STA. 333+00.00 RT				14
STA. 335+00.00 RT				14
STA. 337+00.00 RT TO STA. 339+00.00 RT	200	1.06	150	
STA. 337+00.00 RT				14
STA. 338+50.00 RT				14
STA. 345+00.00 RT TO STA. 352+18.50 RT	718.5	0.30	200	
STA. 346+00.00 RT				14
STA. 348+00.00 RT				14
STA. 350+00.00 RT				14
SUBTOTAL 1				504

TEMPORARY DITCH CHECK SCHEDULE (2 OF 4)

LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
RIGHT SIDE				
STA. 352+18.50 RT TO STA. 359+85.25 RT	766.75	0.30	200	
STA. 354+00.00 RT				14
STA. 356+00.00 RT				14
STA. 359+85.25 RT TO STA. 367+00.00 RT	714.75	0.20	200	
STA. 361+00.00 RT				14
STA. 363+00.00 RT				14
STA. 365+00.00 RT				14
STA. 367+50.00 RT TO STA. 369+50.00 RT	200	1.19	136	
STA. 368+86.00 RT				14
STA. 369+50.00 RT TO STA. 372+14.00 RT	264	0.39	200	
STA. 370+20.00 RT				14
STA. 372+14.00 RT TO STA. 375+05.00 RT	291	0.61	200	
STA. 373+00.00 RT				14
STA. 375+05.00 RT TO STA. 378+00.00 RT	295	0.20	200	
STA. 377+00.00 RT				14
STA. 378+00.00 RT TO STA. 381+00.00 RT	300	0.54	200	
STA. 379+00.00 RT				14
STA. 381+00.00 RT TO STA. 383+00.00 RT	200	1.00	150	
STA. 382+50.00 RT				14
STA. 383+00.00 RT TO STA. 385+00.00 RT	200	2.00	75	
STA. 383+50.00 RT				14
STA. 384+75.00 RT				14
STA. 385+00.00 RT TO STA. 388+00.00 RT	300	2.62	58	
STA. 385+35.00 RT				14
STA. 385+90.00 RT				14
STA. 386+45.00 RT				14
STA. 387+00.00 RT				14
STA. 387+55.00 RT				14
STA. 388+00.00 RT TO STA. 390+70.00 RT	270	2.38	65	
STA. 388+15.00 RT				14
STA. 388+80.00 RT				14
STA. 389+45.00 RT				14
STA. 390+10.00 RT				14
STA. 390+75.00 RT				14
STA. 391+40.00 RT				14
SUBTOTAL 2				336

PLOT DATE * DATE *
FILE NAME * FILE *
PLOT SCALE * SCALE *
USER NAME * USER *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
DATE: MARCH 2012

DRAWN BY: AMPH & KLM
CHECKED BY: JLH