

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-02-AS	WOODFORD	53	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

TEMPORARY DITCH CHECK SCHEDULE (3 OF 4)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
<b>LEFT SIDE</b>				
STA. 280+00.00 LT TO STA. 282+00.00 LT	200.00	1.19	136	
STA. 282+00.00 LT				14
STA. 282+00.00 LT TO STA. 284+00.00 LT	200.00	0.30	200	
STA. 284+00.00 LT TO STA. 285+00.00 LT	100.00	1.00	150	
STA. 285+00.00 LT TO STA. 286+00.00 LT	100.00	1.90	79	
STA. 285+25.00 LT				14
STA. 286+00.00 LT TO STA. 287+00.00 LT	100.00	0.97	200	
STA. 286+00.00 LT				14
STA. 287+00.00 LT TO STA. 287+81.00 LT	81.00	2.14	71	
STA. 287+81.00 LT TO STA. 288+20.00 LT	39.00	2.80	54	
STA. 288+20.00 LT TO STA. 291+00.00 LT	280.00	1.19	136	
STA. 289+00.00 LT				14
STA. 291+00.00 LT TO STA. 294+00.00 LT	300	1.23	125	
STA. 291+85.00 LT				14
STA. 293+10.00 LT				14
STA. 294+00.00 LT TO STA. 295+00.00 LT	100	0.85	200	
STA. 294+50.00 LT				14
STA. 295+00.00 LT TO STA. 296+50.00 LT	150	0.57	200	
STA. 296+50.00 LT TO STA. 300+00.00 LT	350	1.49	107	
STA. 297+50.00 LT				14
STA. 298+50.00 LT				14
STA. 299+50.00 LT				14
STA. 300+00.00 LT TO STA. 302+00.00 LT	200	2.77	56	
STA. 300+00.00 LT				14
STA. 300+50.00 LT				14
STA. 301+00.00 LT				14
STA. 301+50.00 LT				14
STA. 302+00.00 LT				14
STA. 302+00.00 LT TO STA. 303+00.00 LT	100	1.55	100	
STA. 303+00.00 LT				14
STA. 304+50.00 LT TO STA. 316+00.00 LT	1150	0.36	200	
STA. 304+50.00 LT				14
STA. 306+50.00 LT				14
STA. 308+50.00 LT				14
STA. 310+50.00 LT				14
STA. 314+50.00 LT				14
STA. 316+00.00 LT TO STA. 317+35.50 LT	135.5	1.58	100	
STA. 316+25.00 LT				14
STA. 317+35.50 LT TO STA. 318+00.00 LT	64.5	3.03	50	
STA. 318+00.00 LT TO STA. 324+00.00 LT	600	0.35	200	
STA. 318+00.00 LT				14
STA. 322+00.00 LT				14
STA. 324+00.00 LT TO STA. 327+00.00 LT	300	0.48	200	
STA. 326+00.00 LT				14
STA. 327+00.00 LT TO STA. 327+82.50 LT	82.5	0.99	200	
STA. 327+82.50 LT TO STA. 332+00.00 LT	417.5	1.10	136	
STA. 329+20.00 LT				14
STA. 332+00.00 LT TO STA. 338+30.00 LT	630	0.40	200	
STA. 333+00.00 LT				14
STA. 335+00.00 LT				14
STA. 337+00.00 LT				14
STA. 338+30.00 LT TO STA. 340+90.00 LT	260	1.50	100	
STA. 338+50.00 LT				14
STA. 339+50.00 LT				14
STA. 340+50.00 LT				14
<b>SUBTOTAL 3</b>				<b>448</b>

TEMPORARY DITCH CHECK SCHEDULE (4 OF 4)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
<b>LEFT SIDE</b>				
STA. 340+90.00 LT TO STA. 350+00.00 LT	910	0.20	200	
STA. 342+00.00 LT				14
STA. 345+00.00 LT				14
STA. 347+00.00 LT				14
STA. 349+00.00 LT				14
STA. 350+00.00 LT TO STA. 351+00.00 LT	100	0.63	200	
STA. 351+00.00 LT TO STA. 359+85.00 LT	885	0.30	200	
STA. 353+00.00 LT				14
STA. 355+00.00 LT				14
STA. 359+00.00 LT				14
STA. 359+85.00 LT TO STA. 367+00.00 LT	715	0.14	200	
STA. 361+00.00 LT				14
STA. 363+00.00 LT				14
STA. 365+00.00 LT				14
STA. 367+50.00 LT TO STA. 369+00.00 LT	150	0.42	200	
STA. 369+00.00 LT TO STA. 370+00.00 LT	100	0.66	200	
STA. 369+50.00 LT				14
STA. 370+00.00 LT TO STA. 371+00.00 LT	100	1.05	150	
STA. 371+00.00 LT				14
STA. 371+00.00 LT TO STA. 372+14.30 LT	114.3	0.51	200	
STA. 372+14.30 LT TO STA. 375+00.00 LT	285.7	0.84	200	
STA. 373+00.00 LT				14
STA. 375+00.00 LT TO STA. 381+00.00 LT	600	0.30	200	
STA. 377+00.00 LT				14
STA. 379+00.00 LT				14
STA. 381+00.00 LT TO STA. 383+00.00 LT	200	1.02	150	
STA. 382+50.00 LT				14
STA. 383+00.00 LT TO STA. 383+61.18 LT	61.18	0.31	200	
STA. 384+54.86 LT TO STA. 385+00.00 LT	45.14	0.50	200	
STA. 385+00.00 LT TO STA. 386+00.00 LT	100	2.12	71	
STA. 385+55.00 LT				14
STA. 386+00.00 LT TO STA. 387+00.00 LT	100	2.40	63	
STA. 386+25.00 LT				14
STA. 386+85.00 LT				14
STA. 387+00.00 LT TO STA. 388+00.00 LT	100	2.69	58	
STA. 387+45.00 LT				14
STA. 388+00.00 LT				14
STA. 388+00.00 LT TO STA. 390+70.00 LT	270	2.50	60	
STA. 388+60.00 LT				14
STA. 389+20.00 LT				14
STA. 389+80.00 LT				14
STA. 390+40.00 LT				14
<b>SUBTOTAL 4</b>				<b>350</b>
<b>SUBTOTAL 1</b>				<b>504</b>
<b>SUBTOTAL 2</b>				<b>336</b>
<b>SUBTOTAL 3</b>				<b>448</b>
<b>SUBTOTAL 4</b>				<b>350</b>
<b>GRAND TOTAL</b>				<b>1638</b>

PLOT DATE \* \* \* \* \*  
 FILE NAME \* \* \* \* \*  
 PLOT SCALE \* \* \* \* \*  
 USER NAME \* \* \* \* \*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

DESIGNED BY: AMPH & KLM  
 DATE: MARCH 2012

DRAWN BY: AMPH & KLM  
 CHECKED BY: JLH