ORIGINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
NO.	PLOTTED		
	TEMPLATE		
	AREAS		
	AREAS CHECKED		

FINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
NO.	PLOTTED		
	TEMPLATE		
	AREAS		
	AREAS CHECKED		

FILE NAME = $FILE#$

USER NAME = $USER#$

PLOT SCALE = $SCALE#$

PLOT DATE = $DATE#$

	DESIGNED	-
	DRAWN	-
	CHECKED	-
	DATE	-

	REVISED
	REVISED -
	REVISED -
	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS – COUNTY HIGHWAY #1

SCALE:

SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-02-AS	WOODFORD	53	46

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

CONTRACT NO.

℄

C.H.#1

90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90

740 735 730

PR ROW | EX ROW | 35.11 | EX ROW | PR ROW

4.00% 2.00 % 2.00 % 4.00%

1:3 1:4 1:4 1:3

731.58 731.79

384 + 75.00 **384 + 75.00**

CUT = 32 SF FILL = 6 SF

PR ROW | EX ROW | 35.58 | EX ROW | PR ROW

4.00% 2.00 % 2.00 % 4.00%

1:3 1:4

731.71 732.32

384 + 50.00 **384 + 50.00**

CUT = 93 SF FILL = 3 SF

EX ROW | 35.76

4.00% 2.00 % 2.00 % 4.00%

1:3

PROPOSED PIPE CULVERT,
CLASS C, TYPE 1, 18"
INV. ELEV. = 731.82

384 + 40.00 **384 + 40.00**

CUT = 52 SF FILL = 0 SF

EX ROW | 36.03

4.00% 2.00 % 2.00 %

PROPOSED PIPE CULVERT,
CLASS C, TYPE 1, 18"
INV. ELEV. = 731.90

384 + 25.00 **384 + 25.00**

CUT = 32 SF FILL = 0 SF

36.09

4.00% 2.00 % 2.00 % TR 2100N

PROPOSED PIPE CULVERT,
CLASS C, TYPE 1, 18"
INV. ELEV. = 731.91

384 + 21.28 **384 + 21.28**

CUT = 35 SF FILL = 0 SF

TR 2100N 36.38

2.00 % 2.00 % 4.00% 1:4

PROPOSED PIPE CULVERT,
CLASS C, TYPE 1, 18"
INV. ELEV. = 732.00

384 + 04.16 **384 + 04.16**

CUT = 25 SF FILL = 0 SF

STA. 383+77.64, 38.9' LT
UTILITY POLE TO BE REMOVED
AND RELOCATED BY OTHERS

PR ROW | EX ROW | 36.85 | EX ROW | PR ROW

4.00% 2.00 % 2.00 % 4.00%

1:4 1:3

734.00

PROPOSED PIPE CULVERT,
CLASS C, TYPE 1, 18"
INV. ELEV. = 732.15

383 + 75.00 **383 + 75.00**

CUT = 67 SF FILL = 9 SF

90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90