

EARTHWORK SCHEDULE

MAIN SHARED USE PATH LINE		20201200	20200100	-	-	EARTHWORK BALANCE
PAY ITEM NUMBER	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL) (CU YD)	EARTH EXCAVATION * (CU YD)	SUITABLE EXCAVATION (ADJ FOR SHRINKAGE-25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE (EMBANKMENT - SUITABLE EXCAVATION ADJ. FOR SHRINKAGE) (CU YD)	
Location						
Station to Station						
22+07.55	23+00	36	79	59	1	58
23+00	24+00	39	82	61	2	59
24+00	25+00	39	19	15	1	13
25+00	26+00	39	69	52	0	52
26+00	26+86.60	34	24	18	0	18
26+86.60	27+38.37	0	9	7	0	6
27+38.37	28+00	24	17	13	8	5
28+00	29+00	39	0	0	27	-27
29+00	30+00	39	0	0	20	-20
30+00	31+00	39	3	2	7	-5
31+00	32+00	39	23	18	1	16
32+00	33+00	39	49	37	1	36
33+00	34+00	39	6	5	2	3
34+00	34+31.88	34	5	4	0	4
34+31.88	34+63.35	0	9	7	0	6
34+63.35	35+00	39	15	11	0	11
35+00	36+00	39	12	9	2	7
36+00	37+00	39	0	0	6	-6
37+00	38+00	39	7	5	7	-2
38+00	38+87	34	42	32	3	29
38+87	39+00	5	14	10	1	10
39+00	40+00	39	86	65	6	59
40+00	40+82.06	54	30	23	0	22
40+82.06	41+38.91	0	42	32	0	32
41+38.91	42+00	90	73	55	2	53
42+00	43+00	39	0	0	5	-5
43+00	44+00	39	3	2	3	0
44+00	45+00	39	25	19	1	18
45+00	46+00	39	63	47	0	47
46+00	47+00	39	95	71	0	71
47+00	48+00	39	146	109	0	109
48+00	49+00	39	235	176	0	176
49+00	50+00	39	343	257	0	257
50+00	50+40	16	185	139	0	139
50+40	50+60	54	129	97	0	97
50+60	50+80	8	158	119	0	119
50+80	51+00	8	87	65	1	64
51+00	52+00	39	283	212	24	189
52+00	53+00	39	181	135	52	83
53+00	54+00	39	61	45	66	-21
54+00	55+00	39	48	36	60	-24
55+00	56+00	39	0	0	33	-33
56+00	57+00	39	0	0	10	-10
57+00	58+00	39	1	1	7	-7
58+00	59+00	39	14	11	4	6
59+00	60+00	39	80	60	5	56
60+00	61+00	39	167	126	12	113
61+00	62+00	39	90	67	16	51
62+00	63+00	39	106	79	13	67
63+00	64+00	39	15	11	11	0
64+00	65+00	39	7	5	14	-9
65+00	66+00	39	61	46	11	35
66+00	67+00	39	141	106	11	95
67+00	68+00	39	10	7	17	-10
68+00	69+00	39	35	26	22	4
69+00	70+00	39	21	16	25	-9
70+00	71+00	39	16	12	31	-19
71+00	72+00	39	16	12	27	-14
72+00	73+00	39	63	47	8	39
73+00	74+00	39	163	122	0	121
74+00	75+00	39	122	91	0	91
75+00	76+00	39	106	80	0	80
76+00	77+00	39	150	113	8	104
77+00	77+15	6	2	2	2	0
77+15	78+00	33	67	50	4	46
78+00	79+00	39	30	22	3	19
79+00	80+00	39	40	30	11	19
80+00	80+60	23	0	0	7	-7
80+60	80+91.09	35	1	1	1	0
80+91.09	81+43.30	0	17	13	2	11
81+43.30	82+00	67	29	21	6	15
82+00	83+00	39	0	0	7	-7
83+00	84+00	39	10	7	3	4
84+00	85+00	39	50	37	2	36
85+00	85+30	12	1	0	6	-6
85+30	86+00	27	5	4	17	-13
86+00	87+00	39	0	0	57	-57
87+00	88+00	39	0	0	46	-46
88+00	88+50	65	0	0	48	-48
88+50	89+00	19	0	0	80	-80
89+00	90+00	39	0	0	49	-49

PAY ITEM NUMBER		20201200	20200100	-	-	EARTHWORK BALANCE
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL) (CU YD)	EARTH EXCAVATION * (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ FOR SHRINKAGE-25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE (EMBANKMENT - SUITABLE EXCAVATION ADJ. FOR SHRINKAGE) (CU YD)		
Location						
Station to Station						
90+00	90+40	39	0	0	24	-24
90+40	91+00	23	0	0	10	-10
91+00	92+00	39	10	7	3	4
92+00	93+00	39	57	43	2	41
93+00	94+00	39	42	32	6	26
94+00	95+00	39	26	20	5	14
95+00	96+00	39	9	7	1	6
96+00	97+00	39	4	3	0	3
97+00	98+00	39	31	24	1	23
98+00	99+00	39	57	43	1	42
99+00	100+00	39	67	50	0	50
100+00	100+50	17	14	10	0	10
TOTALS		3292	4708	3531	997	2535

* TO BE PAID FOR AS FURNISHED EXCAVATION

PAY ITEM NUMBER		20201200	20200100	-	-	EARTHWORK BALANCE
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL) (CU YD)	EARTH EXCAVATION * (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ FOR SHRINKAGE-25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE (EMBANKMENT - SUITABLE EXCAVATION ADJ. FOR SHRINKAGE) (CU YD)		
Location						
Station to Station						
200+00	201+00	37	5	4	45	-41
201+00	202+00	39	0	0	62	-62
202+00	203+00	39	0	0	26	-26
203+00	203+50	19	82	61	5	56
203+50	204+00	19	82	61	2	60
204+00	205+00	39	69	52	1	50
205+00	206+00	39	111	83	0	83
206+00	207+00	39	60	45	0	45
207+00	208+00	39	17	13	2	11
208+00	209+00	39	14	10	2	8
209+00	210+00	39	32	24	0	24
210+00	211+00	39	45	33	0	33
211+00	212+00	39	35	26	1	25
212+00	212+76.25	45	7	5	2	3
TOTALS		510	557	418	147	271

* TO BE PAID FOR AS FURNISHED EXCAVATION

EARTHWORK SUMMARY

PAY ITEM NUMBER	DESCRIPTION	TOTAL (CU YD)
20200100	EARTH EXCAVATION	5266
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	3802

PLAN	DESIGNED	DATE
	CHECKED	
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATION CHECKED	
	NOTE BOOK	
	NO.	

PROFILE	DESIGNED	DATE
	CHECKED	
	PLOTTED	
	GRADES CHECKED	
	STRUCTURE NOTATION CHECKED	
	NOTE BOOK	
	NO.	

FILE NAME =	USER NAME =	DESIGNED -- TMS	REVISED --
		DRAWN -- TMS	REVISED --
		CHECKED -- AJB	REVISED --
		DATE -- 01-30-2012	REVISED --

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GENERAL NOTES 2 OF 2

SCALE:

F.A.U. RTE. ###	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00105-00-BT	CHAMPAIGN	97	6
				CONTRACT NO. 91478
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				