

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 49+70 TO STA. 50+00	8	6	1	5
STA. 50+00 TO STA. 50+50	20	15	6	9
STA. 50+50 TO STA. 51+00	11	8	17	-9
STA. 51+00 TO STA. 51+50	18	13	82	-69
STA. 51+50 TO STA. 52+00	31	23	158	-135
STA. 52+00 TO STA. 52+50	31	23	209	-186
STA. 52+50 TO STA. 52+86	19	14	455	-441
BRIDGE OMISSION STA. 52+86 TO STA. 53+54				
STA. 53+54 TO STA. 54+00	30	23	240	-217
STA. 54+00 TO STA. 54+50	60	45	169	-124
STA. 54+50 TO STA. 55+00	49	37	131	-94
STA. 55+00 TO STA. 55+50	33	25	56	-31
STA. 55+50 TO STA. 56+00	19	14	20	-6
STA. 56+00 TO STA. 56+50	12	9	13	-4
<b>TOTAL</b>	<b>341</b>	<b>255</b>	<b>1557</b>	<b>-1302</b>

**SCHEDULE HOT MIX ASPHALT**

LOCATION	HMA BINDER COURSE IL-19.0 N50 (TON)	HMA SURF. COURSE MIX C N50 (TON)	BIT. MATERIALS (PRIME COAT) (GALLON)
STA. 49+70 TO STA. 52+86	100.5	60	263.5
STA. 52+86 TO STA. 53+54		26	
STA. 53+54 TO STA. 56+70	100.5	60	263.5
<b>TOTAL</b>	<b>201</b>	<b>146</b>	<b>527</b>

**SCHEDULE AGGREGATE**

LOCATION	AGG. BASE COURSE, TYPE A (TON)	AGG. SHOULDERS (TON)
STA. 49+70 TO STA. 56+70	815	
STA. 49+70 TO STA. 52+76 RT.		33
STA. 49+70 TO STA. 52+96 LT.		35
STA. 53+44 TO STA. 56+70 RT.		35
STA. 53+64 TO STA. 56+70 LT.		33
F.E. STA. 49+91 RT.		16
F.E. STA. 51+25 LT.		23
<b>TOTAL</b>	<b>815</b>	<b>175</b>

**SCHEDULE TEMPORARY EROSION CONTROL SEEDING & SEEDING, CLASS 2 (SPECIAL)**

LOCATION	SEEDING CLASS 2 QUANTITY (ACRE)	TEMPORARY EROSION CONTROL SEEDING QUANTITY (POUND)
STA. 49+70 TO STA. 56+70 R.O.W. TO R.O.W. & EASEMENT	1.0	100
<b>TOTAL</b>	<b>1.0</b>	<b>100</b>

**SCHEDULE ERECTING RIGHT OF WAY MARKERS**

LOCATION	QUANTITY (EACH)
STA. 51+00 33' RT. & 40' LT.	2
STA. 52+00 45' RT. & 55' LT.	2
STA. 55+00 45' RT. & 55' LT.	2
STA. 56+00 33' RT. & 40' LT.	2
<b>TOTAL</b>	<b>8</b>

**SCHEDULE PERIMETER EROSION BARRIER**

LOCATION	QUANTITY (FOOT)
STA. 50+00 35' RT. TO STA. 52+55 45' RT.	256
STA. 53+00 45' RT. TO STA. 56+70 33' RT.	671
STA. 49+70 40' LT. TO STA. 51+00 40' LT.	130
STA. 51+35 45' LT. TO STA. 53+00 55' LT.	166
STA. 53+00 55' LT. TO STA. 54+50 80' LT.	195
STA. 54+50 55' LT. TO STA. 56+70 40' LT.	221
<b>TOTAL</b>	<b>1639</b>

**SCHEDULE PAINT PAVEMENT MARKING-LINE 4"**

LOCATION	WHITE (FOOT)	YELLOW (FOOT)
STA. 49+70 TO STA. 56+70 (SKIP DASH)		180
STA. 49+70 TO STA. 56+70 (EDGE LINE)	1400	
<b>SUB-TOTAL</b>	<b>1400</b>	<b>180</b>
<b>TOTAL</b>	<b>1400</b>	<b>1580</b>

**SCHEDULE TREE REMOVAL (6 TO 15 UNITS)**

LOCATION	QUANTITY (UNIT)
STA. 52+59 43' RT.	12
STA. 53+52 55' LT.	6
STA. 53+55 50' LT.	12
<b>TOTAL</b>	<b>30</b>

**SCHEDULE PIPE CULVERTS, CLASS D, TYPE 1 15"**

LOCATION	QUANTITY (FOOT)
STA. 51+02 (26' LT.) TO STA. 51+48 (28.5' LT.)	46
<b>TOTAL</b>	<b>46</b>

**SCHEDULE PIPE CULVERT REMOVAL**

LOCATION	QUANTITY (FOOT)
STA. 51+07 TO STA. 51+43 (27' LT.)	36
<b>TOTAL</b>	<b>36</b>

**SCHEDULE TEMPORARY DITCH CHECKS**

LOCATION	QUANTITY (FOOT)
STA. 51+50 29' LT. & 33' RT.	16
STA. 52+50 35' LT. & 33.5' RT.	16
STA. 54+50 42' LT. & 33.5' RT.	16
<b>TOTAL</b>	<b>48</b>