STORM SEWER SCHEDULE (CONTINUED)

LOCATION					STRUCTURE						INLETS	MANHOLE		PRECAST REINFORCED CONCRETE FLARED END SECTION					STORM SEWER, TYPE 1				STORM SEWER, TYPE 2				STORM SEWER, CLASS A, TYPE 2, EQUIVALENT ROUND	PIPE CULVERTS		TRENCH BACKFILL
									CAST IRON																		R.C.E.P.			
STATION	OFFSET LT/RT	TO	STATION	OFFSET LT/RT	NO.	DESCRIPTION	RIM ELEV	INV ELEV	FRAME	GRATE/LID	TYPE B	4' DIA	5' DIA	12"	15"	18"	24"	ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	12"	15"	18"	21"	12"	15"	21"	24"	24"	15"	18"	
																											FOOT	FOOT	FOOT	CU YD
EAST CENTRAL STREET																														
118+42.55	13.00' LT	TO	117+79.32	56.85' LT																44										5
117+79.32	56.85' LT				425**	FLARED END SECITON	---	520.95							1															
SUBTOTAL EAST CENTRAL STREET															1					44										5
NORTH STREET																														
109+68.28	13.00' LT	TO	800+42.37	16.30' LT																			33							6
800+42.37	16.30' LT				216	INLET W/FLAT SLAB	524.70	520.31	TYPE 8		1																			
800+42.37	16.30' LT	TO	800+42.37	16.31' RT																			33							11
800+42.37	16.31' RT				217	INLET W/FLAT SLAB	525.50	520.48	TYPE 8		1																			
SUBTOTAL NORTH STREET											2												66							17
EAST MAIN STREET																														
200+57.93	35.09' LT				421**	FLARED END SECTION	---	521.48								1														
200+57.93	35.09' LT	TO	200+56.24																										72	22
200+56.24	36.79' RT				422**	FLARED END SECTION	---	521.84								1														
200+35.49	37.49' RT				423**	FLARED END SECTION	--	521.99						1																
200+35.49	37.49' RT	TO	200+22.28	16.87' RT															23											3
200+22.28	16.87' RT				424	INLET W/FLAT SLAB	524.81	522.11	TYPE 3V		1																			
201+10.65	32.61' RT				300	FLARED END SECTION	---	522.48							1															
201+10.65	32.61' RT	TO	201+68.89	30.47' RT																								62		14
201+68.89	30.47' RT				301	FLARED END SECTION	---	523.10							1															
SUBTOTAL EAST MAIN STREET											1			1	2	2			23									62	72	39
LONGFELLOW STREET																														
400+75.00	26.70' RT				426**	FLARED END SECTION	---	521.72							1															
400+75.00	26.70' RT	TO	400+75.00	23.12' LT																								50		11
400+75.00	23.12' LT				427**	FLARED END SECTION	---	521.97							1															
SUBTOTAL LONGFELLOW STREET															2													50		11
SHEET 9 SUBTOTAL											3			1	5	2			23	44			66					112	72	72
SHEET 7 SUBTOTAL											13	7		1	1			1	184	141			121	29	158	64	155			477
SHEET 8 SUBTOTAL											13	9	1			1	1		89	105	173	679	215	193	225	545				689
TOTAL											29	16	1	2	6	3	1	1	296	290	173	679	402	222	383	609	155	112	72	1238

PLAN — NOTE BOOK NO.____ — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RTE. PLAN PLOTTED / CADD FILE NAME — BY — DATE

PROFILE — NOTE BOOK NO.____ — SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTAT'NS CH'KD — BY — DATE