DE073

COORDINATE TABLE FOR TIE-DOWNS, AND MARKING

POINT #	STATION	OFFSET	NORTHING	EASTING	DESCRIPTION
1	151+12	587' LT	1154558.0455	831232.0000	END OF TAXIWAY MARKING
2	151+13	426' LT	1154560.3543	831392.7971	END OF RADIUS
3	151+08	369' LT	1154556.2199	831450.1535	END OF RADIUS
4	151+42	258' LT	1154590.3536	831560.7551	CENTER OF RADIUS
5	151+26	158' LT	1154575.4874	831660.9283	CENTER OF RADIUS
6	152+09	258' LT	1154658.1100	831559.8984	CENTER OF RADIUS
7	153+10	258' LT	1154758.4114	831559.0052	CENTER OF RADIUS
8	153+47	258' LT	1154796.0479	831558.7500	CENTER OF RADIUS
9	154+47	258' LT	1154896.0437	831557.8249	CENTER OF RADIUS
10	153+68	158' LT	1154817.3492	831658.5128	CENTER OF RADIUS
11	154+68	158' LT	1154917.3449	831657.5877	CENTER OF RADIUS
12	154+64	258' LT	1154912.8493	831557.6707	CENTER OF RADIUS
13	155+64	258' LT	1155012.8449	831556.7456	CENTER OF RADIUS
14	155+76	258' LT	1155024.9563	831556.4340	CENTER OF RADIUS
15	156+77	258' LT	1155125.3122	831555.5199	CENTER OF RADIUS
16	156+88	258' LT	1155136.3497	831555.5917	CENTER OF RADIUS
17	157+88	258' LT	1155236.2691	831554.6869	CENTER OF RADIUS
18	158+05	257' LT	1155253.3656	831555.0204	CENTER OF RADIUS
19	158+53	505' LT	1155299.4586	831306.7202	END OF TAXIWAY MARKING
20	159+05	257' LT	1155353.3613	831554.0953	CENTER OF RADIUS
21	158+41	157' LT	1155290.2745	831655.1833	CENTER OF RADIUS
22	151+27	161' LT	1154576.9898	831657.2820	TIE-DOWN
23	151+39	144' LT	1154589.1466	831674.1702	TIE-DOWN
24	151+51	161' LT	1154600.9888	831657.0600	TIE-DOWN
25	151+72	161' LT	1154621.9879	831656.8657	TIE-DOWN
26	151+84	144' LT	1154634.1447	831673.7540	TIE-DOWN
27	151+96	161' LT	1154645.9869	831656.6437	TIE-DOWN
28	152+17	161' LT	1154666.9783	831656.4495	TIE-DOWN
29	152+29	144' LT	1154679.1350	831673.3377	TIE-DOWN
30	152+41	161' LT	1154690.9773	831656.2275	TIE-DOWN
31	152+62	161' LT	1154711.9841	831656.0331	TIE-DOWN
32	152+74	144' LT	1154724.1408	831672.9214	TIE-DOWN
33	152+86	161' LT	1154735.9830	831655.8111	TIE-DOWN
34	153+07	161' LT	1154756.9821	831655.6168	TIE-DOWN
35	153+19	144' LT	1154769.1389	831672.5051	TIE-DOWN

COORDINATE TABLE FOR TIE-DOWNS, AND MARKING

POINT #	STATION	OFFSET	NORTHING	EASTING	DESCRIPTION
36	153+31	161' LT	1154780.9811	831655.3948	TIE-DOWN
37	153+52	161' LT	1154801.9802	831655.2005	TIE-DOWN
38	153+64	144' LT	1154814.1370	831672.0888	TIE-DOWN
39	153+76	161' LT	1154825.9792	831654.9785	TIE-DOWN
40	151+27	102' LT	1154577.5356	831716.2795	TIE-DOWN
41	151+39	85' LT	1154589.6924	831733.1677	TIE-DOWN
42	151+51	102' LT	1154601.5346	831716.0574	TIE-DOWN
43	151+72	102' LT	1154622.5337	831715.8632	TIE-DOWN
44	151+84	85' LT	1154634.6905	831732.7514	TIE-DOWN
45	151+96	102' LT	1154646.5327	831715.6411	TIE-DOWN
46	152+17	102' LT	1154667.5318	831715.4469	TIE-DOWN
47	152+29	85' LT	1154679.6885	831732.3351	TIE-DOWN
48	152+41	102' LT	1154691.5308	831715.2249	TIE-DOWN
49	152+62	102' LT	1154712.5299	831715.0306	TIE-DOWN
50	152+74	85' LT	1154724.6866	831731.9188	TIE-DOWN
51	152+86	102' LT	1154736.5288	831714.8086	TIE-DOWN
52	153+07	102' LT	1154757.5279	831714.6143	TIE-DOWN
53	153+19	85' LT	1154769.6847	831731.5026	TIE-DOWN
54	153+31	102' LT	1154781.5269	831714.3923	TIE-DOWN
55	153+52	102' LT	1154802.5260	831714.1980	TIE-DOWN
56	153+64	85' LT	1154814.6828	831731.0863	TIE-DOWN
57	153+76	102' LT	1154826.5250	831713.9760	TIE-DOWN
58	151+09	50' LT	1154559.4647	831768.8939	CENTER OF RADIUS
59	153+68	50' LT	1154818.3564	831766.4825	CENTER OF RADIUS
60	154+68	50' LT	1154918.3349	831765.5525	CENTER OF RADIUS
61	152+60	589' LT	1154705.2324	831228.7702	END OF TAXIWAY MARKING
62	153+97	589' LT	1154842.9607	831226.6295	END OF TAXIWAY MARKING
63	155+14	558' LT	1154960.1136	831255.0886	END OF TAXIWAY MARKING
64	156+26	558' LT	1155072.4003	831256.2854	END OF TAXIWAY MARKING
65	157+37	558' LT	1155183.4041	831255.0645	END OF TAXIWAY MARKING

MARKING QUANTITIES

DESCRIPTION	UNIT AREA	NO. REQUIRED	TOTAL AREA
TAXIWAY CENTERLINE	4,821	1	4,821
TIE-DOWN	39	27	1,053
TAXIWAY EDGE	15	9	135
NON-MOVEMENT AREA	304	1	304
		TOTAL YELLOW	6,313
TAXIWAY CENTERLINE	4,821	1	4,821
TAXIWAY EDGE	25	9	225
NON-MOVEMENT AREA	706	1	706
		TOTAL BLACK	5,752
		TOTAL MARKING	12,065

MAY 14, 2012 9:01 AM HARRI01115
C:\PWISE_WORK\DO_NOT_DELETE\DMS27480\R-151MRK.DWG

DATE	REVISION

DECATUR AIRPORT
DECATUR, ILLINOIS
IL. PROJ.: DEC-4102 A.I.P. PROJ.: 3-17-0033-B3

Hanson Proj. No. 10A0136D 0001
Filename R-151MRK.DWG
Scale 1"= 50'
Date 05/11/12

LAYOUT	JSL	03/21/11
DRAWN	BAK	03/21/11
REVIEWED	RAW	04/07/11

HANSON
©Copyright Hanson Professional Services Inc. 2012
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Ph: (217) 788-2450 Fax: (217) 788-2503
www.hanson-inc.com
Offices Nationwide

RECONSTRUCT NORTH GA RAMP

PROPOSED MARKING COORDINATE TABLE