

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE 0005					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	343	343					
550A0050	STORM SEWERS CLASS A, TYPE 1, 12"	FT	83	83					
60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1					
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60258100	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1					
60261540	INLETS TO BE ADJUSTED W/NEW TYPE 24 F&G	EACH	2	2					
60262700	INLETS TO BE RECONSTRUCTED	EACH	2	2					
60266600	VALVE BOXES TO BE ADJUSTED	EACH	9	9					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	27	27					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	all	all					
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10	10					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	12	12					
67100100	MOBILIZATION	LSUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE 0005					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
70102634	TRAFFIC CONTROL AND PROTECTION, STANDARD 701611	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11786	11786					
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	3929	3929					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	871	871					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	62708	62708					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	10589	10589					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	908	908					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	674	674					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5893	5893					
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4					

REV