

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

* 54+53 = 107 TOTAL SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	1
		ILLINOIS	CONTRACT NO. 62F74	

FOR INDEX OF SHEETS, SEE SHEET NO. 2


PROJECT LOCATED IN THE CITY OF BERWYN
AND TOWN OF CICERO

TRAFFIC DATA:

CERMAK RD.
ADT= 30,300 (2014)
SPEED LIMIT= 25 TO 30 MPH

PROPOSED HIGHWAY PLANS


**F.A.U. 1453 / CERMAK RD.
IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)
SECTION: (78-1&78-3)RS-2
PROJECT: STP-SK4A(039)
RESURFACING (3P) AND PEDESTRIAN RAMPS
COOK COUNTY
C-91-042-18**



PROJECT BEGINS
STA. 11 + 43

PROJECT ENDS
STA. 177 + 11.7

GROSS LENGTH = NET LENGTH = 16568.7 FT. = 3.1 MILE




FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD
ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT
CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS
ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123
OR 811

PROJECT ENGINEER: DAN WILGREEN (847) 705-4240
PROJECT MANAGER: FAWAD AQUEEL (847) 705-4247

CONTRACT NO. 62F74



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUBMITTED March 20 20 18
Anthony J. Quigley / CHS
REGIONAL ENGINEER
May 11 20 18
May 11 20 18
ENGINEER OF DESIGN AND ENVIRONMENT
May 11 20 18
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

**PRINTED BY THE AUTHORITY
OF THE STATE OF ILLINOIS**

INDEX OF SHEETS

STATE STANDARDS

GENERAL NOTES

SHEET NO.	DESCRIPTION	STANDARD NO.	DESCRIPTION	
1	COVER SHEET	000001-06	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS	1. BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC,
2	INDEX OF SHEETS	424001-10	PERPENDICULAR CURB RAMPS FOR SIDEWALKS	2. TEN (10) FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER TO EXISTING CURBS AND GUTTERS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.
3-5	SUMMARY OF QUANTITIES	424006-03	DIAGONAL CURB RAMPS FOR SIDEWALKS	3. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITY OF BERWYN, AND TOWN OF CICERO.
6-10	EXISTING AND PROPOSED TYPICAL SECTIONS	424011-03	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS	4. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION OF THE DEPARTMENT.
11-16	ROADWAY AND PAVEMENT MARKING PLAN	424016-04	MID-BLOCK CURB RAMPS FOR SIDEWALKS	5. ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS WILL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
17-22Z 23-23Z 24-24A	PEDESTRIAN RAMP (ADA) DETAILS	424021-04	DEPRESSED CORNER FOR SIDEWALKS	6. BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.
25-41	DETECTOR LOOP REPLACEMENT PLAN	424031-01	MEDIAN PEDESTRIAN CROSSINGS	7. ALL PAVEMENT PATCHING, CURB AND GUTTER REMOVAL AND REPLACEMENT, SIDEWALK REMOVAL, P.C.C. SIDEWALK 5", AND DRAINAGE ADJUSTMENT LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
42	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING (BD-8)	442201-03	CLASS C AND D PATCHES	8. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
43	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT (BD-22)	482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT	9. FRAMES AND GRATES ADJUSTMENT OF PRIVATE UTILITIES WITHIN THE LIMITS OF THE IMPROVEMENTS SHALL BE DONE BY THEIR RESPECTIVE OWNERS AND ARE NOT PART OF THIS CONTRACT.
44	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD-24)	604001-04	FRAME AND LIDS, TYPE 1	10. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING OF WORK.
45	BUTT JOINT AND HMA TAPER DETAILS (BD-32)	604091-03	FRAME AND GRATE, TYPE 24	11. THE RESIDENT ENGINEER SHALL CONTACT CORY JUCIUS, ARTERIAL TRAFFIC FIELD ENGINEER, AT CORY.JUCIUS@ILLINOIS.GOV A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
46	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)	606001-07	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER	12. THE CONTRACTOR WILL BE REQUIRED TO KEEP A RECORD OF THE LOCATIONS OF THE BURIED STRUCTURES ACCORDING TO THE STATION AND DISTANCE LEFT OR RIGHT OF THE CENTERLINE OF PAVEMENT. UPON COMPLETION OF THE WORK, THE CONTRACTOR WILL DELIVER THE RECORD TO THE ENGINEER.
47	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)	606301-04	PC CONCRETE ISLANDS FOR MEDIANS	13. EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.
48	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)	701101-05	OFF-RD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600m) FROM PAVEMENT EDGE	14. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
49	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14)	701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' (4.5 m) AWAY	15. DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN THE PLANS.
50	SHORT TERM PAVEMENT MARKING LETTERS AND SYMBOLS (TC-16)	701427-05	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS ≤ 40 MPH	16. PAVEMENT MARKING TAPE, TYPE III SHALL BE USED FOR SHORT TERM PAVEMENT MARKINGS ON ALL FINAL SURFACES.
51	ARTERIAL ROAD INFORMATION SIGN (TC-22)	701601-09	URBAN LANE CLOSURE, MULTILANE 1W OR 2W WITH NONTRANSVERSABLE MEDIAN	17. WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC, THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1½ INCHES WHERE THE SPEED LIMIT IS 40 MPH OR LESS. WITH WRITTEN APPROVAL OF THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75 mm) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM OF 1:3 (V:H).
52	DRIVEWAY ENTRANCE SIGNING (TC-26)	701606-10	URBAN SINGLE LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN	18. BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.
53	STANDARD TRAFFIC SIGNAL DESIGN DETAILS (TS-05, SHEET 2 OF 7)	701701-10	URBAN LANE CLOSURE, MULTILANE INTERSECTION	19. OVERNIGHT LANE CLOSURES SHALL NOT BE ALLOWED FOR REHABILITATION PROJECTS INVOLVING DAYTIME MILLING AND RESURFACING OPERATIONS AND CLASS D PATCHING UNLESS OTHER CONDITIONS WARRANT EXTENDED LANE CLOSURES AS DETERMINED AND APPROVED IN WRITING BY THE ENGINEER OR AS PROVIDED FOR IN THE CONTRACT SPECIFICATIONS
54	DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING (TS-07)	701801-06	SIDEWALK, CORNER, OR CROSSWALK CLOSURE	20. PROPOSED SIDEWALK RAMPS SHALL CONFORM TO CURRENT ADA REQUIREMENTS AND APPLICABLE STATE HIGHWAY STANDARDS OR AS DETERMINED BY THE ENGINEER.
		701901-07	TRAFFIC CONTROL DEVICES	21. THE CONTRACTOR SHALL MAINTAIN PEDESTRIAN ACCESS AT ALL TIMES DURING CONSTRUCTION.
		780001-05	TYPICAL PAVEMENT MARKINGS	
		814001-03	HANDHOLES	
		886001-01	DETECTOR LOOP INSTALLATIONS	

FILE NAME	USER NAME = locymr	DESIGNED -	REVISED ML 4/27/18	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES F.A.U. 1453 CERMAK ROAD (IL 43/HARLEM AVE. - IL 50/CICERO AVE.)	F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\1\1084EBID\INTEG\illinois.gov\PI\DOT\Documents\IDOT Offices\District 1\Projects\DI03218\BROWN\Note\Design\DI03218-sht-genote.dgn		CHECKED -	REVISED -			1453	(78-1&78-3IRS-2	COOK	54	2
	PLOT SCALE = 100.0000' / in.					CONTRACT NO. 62F74				
	PLOT DATE = 4/27/2018	DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
						SHEET NO. 2 OF		SHEETS	STA.	TO STA.

URBAN

SUMMARY OF QUANTITIES

CODE NO

ITEM

UNIT

TOTAL QUANTITIES

80% FED
20% STATE
0005

20200100

EARTH EXCAVATION

CU YD

258

258

21101615

TOPSOIL FURNISH AND PLACE, 4"

SQ YD

267

267

25000400

NITROGEN FERTILIZER NUTRIENT

POUND

4

4

25000500

PHOSPHORUS FERTILIZER NUTRIENT

POUND

4

4

25000600

POTASSIUM FERTILIZER NUTRIENT

POUND

4

4

25200110

SODDING, SALT TOLERANT

SQ YD

267

267

25200200

SUPPLEMENTAL WATERING

UNIT

2.7

2.7

40600290

BITUMINOUS MATERIALS (TACK COAT)

POUND

78263

78263

40600400

MIXTURE FOR CRACKS, JOINTS, AND
FLANGEWAYS

TON

174

174

40600827

POLYMERIZED LEVELING BINDER (MACHINE
METHOD), IL-4.75, N50

TON

4783

4783

40600982

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT
JOINT

SQ YD

2414

2414

42001300

PROTECTIVE COAT

SQ YD

6547

6547

42400200

PORTLAND CEMENT CONCRETE SIDEWALK 5
INCH

SQ FT

47200

47200

42400800

DETECTABLE WARNINGS

SQ FT

2137

2137

URBAN

SUMMARY OF QUANTITIES

CODE NO

ITEM

UNIT

TOTAL QUANTITIES

80% FED
20% STATE
0005

44000159

HOT-MIX ASPHALT SURFACE REMOVAL, 2
1/2"

SQ YD

115945

115945

44000600

SIDEWALK REMOVAL

SQ FT

47200

47200

44201789

CLASS D PATCHES, TYPE II, 12 INCH

SQ YD

396

396

44201794

CLASS D PATCHES, TYPE III, 12 INCH

SQ YD

161

161

44201796

CLASS D PATCHES, TYPE IV, 12 INCH

SQ YD

721

721

60255410

CATCH BASINS TO BE CLEANED

EACH

6

6

60266600

VALVE BOXES TO BE ADJUSTED

EACH

8

8

60300105

FRAMES AND GRATES TO BE ADJUSTED

EACH

14

14

66900200

NON-SPECIAL WASTE DISPOSAL

CU YD

258

258

66900450

SPECIAL WASTE PLANS AND REPORTS

L SUM

1

1

66900530

SOIL DISPOSAL ANALYSIS

EACH

5

5

67000400

ENGINEER'S FIELD OFFICE, TYPE A

CAL MO

6

6

67100100

MOBILIZATION

L SUM

1

1

70102625

TRAFFIC CONTROL AND PROTECTION,
STANDARD 701606

L SUM

1

1

14

☐ 100 % STATE
* SPECIALTY ITEM

FILE NAME =

USER NAME = Bltgramso

DESIGNED -

REVISED -

OFFICIALS/Client: NProjctns\00328\CA0000\Design\00328\DRAWING

PLOT SCALE = 1000000' / 1in

CHECKED -

REVISED -

PLOT DATE = 3/23/2018

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE:

SHEET NO. OF SHEETS STA. TO STA.

F.A.U.
RTE.
1453

SECTION
(78-1&78-3)RS-2

COUNTY
COOK

TOTAL
SHEETS
54

SHEET
NO.
3

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

CONTRACT NO. 62F74

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE 0005						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE 0005					
70102630	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	54087	54087					
	STANDARD 701601										4"								
70102635	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	11056	11056					
	STANDARD 701701										6"								
70102640	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1						* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	805	805					
	STANDARD 701801										8"								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	47228	47228						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	177	177					
											12"								
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	7879	7879						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	6836	6836					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND	SO FT	2473	2473							24"								
	SYMBOLS									* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	790	790					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54087	54087															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11056	11056						78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	790	790					
											REMOVAL								
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	805	805						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	7459	7459					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	177	177						* 89502376	REBUILD EXISTING HANDHOLE	EACH	60	60					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	6836	6836						X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	11807	11807						X0327611	REMOVE AND REINSTALL BRICK PAVER	SO FT	4482	4482					
* 78000100	THERMOPLASTIC PAVEMENT MARKING -	SO FT	2473	2473						X4060004	POLYMERIZED HOT-MIX ASPHALT SURFACE	TON	11363	11363					
	LETTERS AND SYMBOLS										COURSE, STONE MATRIX ASPHALT, 9.5, N80								
										* 12	SPECIALTY ITEMS								
FILE NAME =					DESIGNED -					SUMMARY OF QUANTITIES					F.A.I. RTE.				
USER NAME =					REVISED -					CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)					SECTION				
PLOT SCALE =					CHECKED -					SCALE:					COUNTY				
PLOT DATE =					DATE -					SHEET NO. OF SHEETS STA. TO STA.					TOTAL SHEETS				
															CONTRACT NO. 62F74				
															FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

[illegible]

MODEL Default
FILE Name: p:\u0084EID\NTEC\Illinois.gov\PI\DOT\Documents\DOT_Offices\District_1\Projects\ID103218\CADD\data\Design\ID103218-shr-typlcd.dgn

NOTES:

1. THE CONTRACTOR SHALL MILL FIRST BEFORE PATCHING BETWEEN
STA. 11+43 AND STA. 177+11.7

HOT-MIX ASPHALT MIXTURE REQUIREMENTS			
MIXTURE USES	MIXTURE TYPE	AIR VOIDS @ Ndes	QUALITY MANAGEMENT PROGRAM (QMP)
PAVEMENT RESURFACING	POLYMERIZED HMA SURFACE COURSE, SMA, N80, (IL 9.5 mm); 1 3/4"	3.5% @ 80 GYR.	PFP
	POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50; 3/4"	3.5% @ 50 GYR.	OCP
PATCHING	CLASS D PATCHES (HMA BINDER IL-19.0 mm)	4% @ 70 GYR	QC/QA
QMP DESIGNATION: QUALITY CONTROL/QUALITY ASSURANCE (QC/QA); QUALITY CONTROL FOR PERFORMANCE (QCP)			


NOTE 1: THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.

NOTE 2: THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76 -22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64 -22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS.

FOR USE OF RECYCLED MATERIALS SEE DISTRICT ONE SPECIAL PROVISIONS.

QUALITY MANAGEMENT PROGRAM (QMP) IDENTIFIES THE PARTICULAR QUALITY CONTROL SPECIFICATION THAT APPLIES TO THE HMA MIXTURE.


	USER NAME = bilgramisa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING AND PROPOSED TYPICAL SECTIONS CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -				1453	(78-1&78-3)RS-2	COOK	54	6
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -				CONTRACT NO. 62F74				
	PLOT DATE = 3/23/2018	DATE -	REVISED -		SCALE:	SHEET OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		



CERMAK ROAD
EXISTING TYPICAL SECTION
STA. 11+43 TO STA. 22+74
STA. 171+00 TO STA. 177+11.7

LEGEND:

- ① EXISTING SIDEWALK
- ② EXISTING COMB. CONC. CURB AND GUTTER, B6.12
- ③ EXISTING HMA SURFACE COURSE, ± 5.5"
- ④ EXISTING PCC BASE COURSE, ± 9"
- ⑤ EXISTING SUB-BASE
- ⑥ EXISTING CONCRETE MEDIAN
- ⑦ PROPOSED HMA SURFACE REMOVAL, 2½"
- ⑧ PROPOSED POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, ¾"
- ⑨ PROPOSED POLYMERIZED HMA SURFACE COURSE, SMA, 9.5, N80, 1 ¾"
- ⑩ PROPOSED LONGITUDINAL JOINT SEALANT




CERMAK ROAD
PROPOSED TYPICAL SECTION
STA. 11+43 TO STA. 22+74
STA. 171+00 TO STA. 177+11.7

NOTES:

- THE CONTRACTOR SHALL MILL FIRST BEFORE PATCHING BETWEEN STA. 11+43 AND STA. 177+11.7
- LONGITUDINAL JOINT SEALANT TO BE PLACED OVER POLY. LEVELING BINDER (MM) IL-4.75, N50 WHERE SURFACE MIX JOINT WILL BE LOCATED

MODEL Default
FILE Name: pavulul84E8ED1NTEC\Illinois.gov\PIVDOT\Documents\DOT Office\Bldg\1\Projects\103218\CADD\Bldg\Design\103218-shr-typcal.dgn


	USER NAME = bilgramisa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING AND PROPOSED TYPICAL SECTIONS CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -				1453	(78-1&78-3)RS-2	COOK	54	7
	PLOT DATE = 3/23/2018	CHECKED -	REVISED -		CONTRACT NO. 62F74						
		DATE -	REVISED -		SCALE:	SHEET OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		



CERMAK ROAD

EXISTING TYPICAL SECTION

STA. 22+74 TO STA. 27+00
STA. 48+00 TO STA. 61+00
STA. 64+00 TO STA. 71+00
STA. 74+00 TO STA. 77+93
STA. 81+00 TO STA. 84+62
STA. 87+70 TO STA. 111+00
STA. 114+23 TO STA. 171+00



CERMAK ROAD

PROPOSED TYPICAL SECTION

STA. 22+74 TO STA. 27+00
STA. 48+00 TO STA. 61+00
STA. 64+00 TO STA. 71+00
STA. 74+00 TO STA. 77+93
STA. 81+00 TO STA. 84+62
STA. 87+70 TO STA. 111+00
STA. 114+23 TO STA. 171+00

LEGEND:


- ① EXISTING SIDEWALK
- ② EXISTING COMB. CONC. CURB AND GUTTER, B6.12
- ③ EXISTING HMA SURFACE COURSE, ± 5.5''
- ④ EXISTING PCC BASE COURSE, ± 9''
- ⑤ EXISTING SUB-BASE
- ⑥ EXISTING CONCRETE MEDIAN
- ⑦ PROPOSED HMA SURFACE REMOVAL, 2 1/2''
- ⑧ PROPOSED POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, 3/4''
- ⑨ PROPOSED POLYMERIZED HMA SURFACE COURSE, SMA, 9.5, N80, 1 3/4''
- ⑩ PROPOSED LONGITUDINAL JOINT SEALANT

NOTES:


1. THE CONTRACTOR SHALL MILL FIRST BEFORE PATCHING BETWEEN STA. 22+74 AND STA. 171+00
2. LONGITUDINAL JOINT SEALANT TO BE PLACED OVER POLY. LEVELING BINDER (MM) IL-4.75, N50 WHERE SURFACE MIX JOINT WILL BE LOCATED

MODEL Default
FILE Name: p:\u0008a8e8d1n0te\illinois.gov\p\w\DOT\Documents\DOT_Offices\Director\Projects\ID103218\CADD\data\Design\ID103218-shr-hydcadd.dgn

	USER NAME = bilgramisa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING AND PROPOSED TYPICAL SECTIONS CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -				1453	(78-1&78-3)RS-2	COOK	54	8
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -				CONTRACT NO. 62F74				
	PLOT DATE = 3/23/2018	DATE -	REVISED -				ILLINOIS FED. AID PROJECT				
SCALE:		SHEET	OF	SHEETS	STA.	TO STA.					



CERMAK ROAD
EXISTING TYPICAL SECTION
STA. 27+00 TO STA. 48+00



CERMAK ROAD
PROPOSED TYPICAL SECTION
STA. 27+00 TO STA. 48+00


LEGEND:

- ① EXISTING SIDEWALK
- ② EXISTING COMB. CONC. CURB AND GUTTER, B6.12
- ③ EXISTING HMA SURFACE COURSE, $\pm 5.5''$
- ④ EXISTING PCC BASE COURSE, $\pm 9''$
- ⑤ EXISTING SUB-BASE
- ⑥ EXISTING CONCRETE MEDIAN
- ⑦ PROPOSED HMA SURFACE REMOVAL, $2\frac{1}{2}''$
- ⑧ PROPOSED POLYMERIZED LEVELING BINDER (MM), 1L-4.75, N50, $\frac{3}{4}''$
- ⑨ PROPOSED POLYMERIZED HMA SURFACE COURSE, SMA, 9.5, N80, $1\frac{3}{4}''$
- ⑩ PROPOSED LONGITUDINAL JOINT SEALANT


NOTES:

1. THE CONTRACTOR SHALL MILL FIRST BEFORE PATCHING BETWEEN STA. 27+00 AND STA. 48+00
2. LONGITUDINAL JOINT SEALANT TO BE PLACED OVER POLY. LEVELING BINDER (MM) IL-4.75, N50 WHERE SURFACE MIX JOINT WILL BE LOCATED

FILE NAME: D:\1453\1453.DWG	USER NAME = Bilgramisa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING AND PROPOSED TYPICAL SECTIONS CERMAK RD. – IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN -	REVISED -			1453	(78-1&78-3)RS-2	COOK	54	9		
	PLOT SCALE = 100,000' / in.	CHECKED -	REVISED -			CONTRACT NO. 62F74						
	PLOT DATE = 3/23/2018	DATE -	REVISED -			SCALE:	SHEET OF SHEETS STA.					
							TO STA.					
									ILLINOIS FED. AID PROJECT			



CERMAK ROAD
EXISTING TYPICAL SECTION
STA. 61+00 TO STA. 64+00
STA. 71+00 TO STA. 74+00
STA. 77+93 TO STA. 81+00
STA. 84+62 TO STA. 87+70
STA. 111+00 TO STA. 114+23
STA. 84+62 TO STA. 87+70
STA. 111+00 TO STA. 114+23



CERMAK ROAD
PROPOSED TYPICAL SECTION
STA. 61+00 TO STA. 64+00
STA. 71+00 TO STA. 74+00
STA. 77+93 TO STA. 81+00
STA. 84+62 TO STA. 87+70
STA. 111+00 TO STA. 114+23
STA. 84+62 TO STA. 87+70
STA. 111+00 TO STA. 114+23


- LEGEND:**
- 1 EXISTING SIDEWALK
 - 2 EXISTING COMB. CONC. CURB AND GUTTER, B6.12
 - 3 EXISTING HMA SURFACE COURSE, ± 5.5"
 - 4 EXISTING PCC BASE COURSE, ± 9"
 - 5 EXISTING SUB-BASE
 - 6 EXISTING CONCRETE MEDIAN
 - 7 PROPOSED HMA SURFACE REMOVAL, 2 1/2"
 - 8 PROPOSED POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, 3/4"
 - 9 PROPOSED POLYMERIZED HMA SURFACE COURSE, SMA, 9.5, N80, 1 3/4"
 - 10 PROPOSED LONGITUDINAL JOINT SEALANT

- NOTES:**
- THE CONTRACTOR SHALL MILL FIRST BEFORE PATCHING BETWEEN STA. 61+00 AND STA. 114+23
 - LONGITUDINAL JOINT SEALANT TO BE PLACED OVER POLY. LEVELING BINDER (MM) IL-4.75, N50 WHERE SURFACE MIX JOINT WILL BE LOCATED

MODEL Default
FILE Name: p:\u0000\B04E8ED0\NTEC\Illinois.gov\PIU\DOT\Documents\DOT_Offices\DI\drct_1\Projects\ID103218\CADD\data\Design\ID103218-shr-typcal.dgn


	USER NAME = bilgramisa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING AND PROPOSED TYPICAL SECTIONS CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -				1453	(78-1&78-3)RS-2	COOK	54	10
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -				CONTRACT NO. 62F74				
	PLOT DATE = 3/23/2018	DATE -	REVISED -				ILLINOIS FED. AID PROJECT				
SCALE:		SHEET	OF	SHEETS	STA.	TO STA.					

MODEL Default
FILE Name: p:\u0000\B&E\BID\NTEC\Illinois\gov\PI\DOT\Documents\DOT Office\Bldg\1\Projects\03218\CAD\B&E\Design\BID\03218-shr-plan.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|--|
| ① THERMOPLASTIC PAVEMENT MARKING, 4" DOUBLE SOLID YELLOW CENTERLINE, 2 @ 11" C-C (TYP.) | ⑦ THERMOPLASTIC PAVEMENT MARKING 12" DIAGONAL SOLID WHITE LINE @ 75' C-C (5 MINIMUM) (TYP.) |
| ② THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE TURN LANE (TYP.) | ⑧ THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS, SOLID WHITE (TYP.) |
| ③ THERMOPLASTIC PAVEMENT MARKING, 24" SOLID WHITE STOP BAR (TYP.) | ⑨ THERMOPLASTIC PAVEMENT MARKING, 4" SKIP DASH WHITE LANE LINE, 10' DASH - 30' SKIP (TYP.) |
| ④ THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE CROSSWALK LINE, 2 @ 6' C-C (TYP. UNLESS OTHERWISE NOTED) | ⑩ THERMOPLASTIC PAVEMENT MARKING, 12" SOLID WHITE LONGITUDINAL BAR, SPACED 2' APART (TYP.) |
| ⑤ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID YELLOW LINE (TYP.) | ⑪ THERMOPLASTIC PAVEMENT MARKING, 6" SKIP DASH WHITE TURN LANE, 2' LINE WITH 6' SPACE (TYP.) |
| ⑥ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID WHITE LINE (TYP.) | |



Ⓐ PROP. PEDESTRIAN RAMP (ADA) IMPROVEMENTS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


ROADWAY PLAN CERMAK ROAD
IL. RTE. 43 (HARLEM AVE.) TO IL. RTE. 50 (CICERO AVE.)

SCALE: 1"=50' SHEET OF SHEETS STA. 12+18.1 TO STA. 40+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	11
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

USER NAME = bilgramisa	DESIGNED -	REVISED -
PLOT SCALE = 100,0000 ' / in.	DRAWN -	REVISED -
PLOT DATE = 3/23/2018	CHECKED -	REVISED -
	DATE -	REVISED -


MODEL Default
FILE Name: p:\work\8484EID\NTEC\Illinois.gov\PHUDOT\Documents\DOT Office\Bldg\1\Projects\103218\CADD\Bldg\Design\103218-shr-plan.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|--|
| ① THERMOPLASTIC PAVEMENT MARKING, 4" DOUBLE SOLID YELLOW CENTERLINE, 2 @ 11" C-C (TYP.) | ⑦ THERMOPLASTIC PAVEMENT MARKING 12" DIAGONAL SOLID WHITE LINE @ 75' C-C (5 MINIMUM) (TYP.) |
| ② THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE TURN LANE (TYP.) | ⑧ THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS, SOLID WHITE (TYP.) |
| ③ THERMOPLASTIC PAVEMENT MARKING, 24" SOLID WHITE STOP BAR (TYP.) | ⑨ THERMOPLASTIC PAVEMENT MARKING, 4" SKIP DASH WHITE LANE LINE, 10' DASH - 30' SKIP (TYP.) |
| ④ THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE CROSSWALK LINE, 2 @ 6' C-C (TYP. UNLESS OTHERWISE NOTED) | ⑩ THERMOPLASTIC PAVEMENT MARKING, 12" SOLID WHITE LONGITUDINAL BAR, SPACED 2' APART (TYP.) |
| ⑤ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID YELLOW LINE (TYP.) | ⑪ THERMOPLASTIC PAVEMENT MARKING, 6" SKIP DASH WHITE TURN LANE, 2' LINE WITH 6' SPACE (TYP.) |
| ⑥ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID WHITE LINE (TYP.) | |

Ⓐ PROP. PEDESTRIAN RAMP (ADA) IMPROVEMENTS



Ⓐ PROP. PEDESTRIAN RAMP (ADA) IMPROVEMENTS


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY PLAN CERMAK RD.
IL. RTE. 43 (HARLEM AVE.) TO IL. RTE. 50 (CICERO AVE.)

SCALE: 1"=50' SHEET OF SHEETS STA. 70+00 TO STA. 100+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	13
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				


MODEL: Default
FILE: \\nrcs-prod\illinois\dot\Illinois\gov\PHUDOT\Documents\DOT_Offices\Bldg\1103218\CADD\Bldg\Design\1103218-shr-plan.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|--|
| ① THERMOPLASTIC PAVEMENT MARKING, 4" DOUBLE SOLID YELLOW CENTERLINE, 2 @ 11" C-C (TYP.) | ⑦ THERMOPLASTIC PAVEMENT MARKING 12" DIAGONAL SOLID WHITE LINE @ 75' C-C (5 MINIMUM) (TYP.) |
| ② THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE TURN LANE (TYP.) | ⑧ THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS, SOLID WHITE (TYP.) |
| ③ THERMOPLASTIC PAVEMENT MARKING, 24" SOLID WHITE STOP BAR (TYP.) | ⑨ THERMOPLASTIC PAVEMENT MARKING, 4" SKIP DASH WHITE LANE LINE, 10' DASH - 30' SKIP (TYP.) |
| ④ THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE CROSSWALK LINE, 2 @ 6' C-C (TYP. UNLESS OTHERWISE NOTED) | ⑩ THERMOPLASTIC PAVEMENT MARKING, 12" SOLID WHITE LONGITUDINAL BAR, SPACED 2' APART (TYP.) |
| ⑤ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID YELLOW LINE (TYP.) | ⑪ THERMOPLASTIC PAVEMENT MARKING, 6" SKIP DASH WHITE TURN LANE, 2' LINE WITH 6' SPACE (TYP.) |
| ⑥ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID WHITE LINE (TYP.) | |

Ⓐ PROP. PEDESTRIAN RAMP (ADA) IMPROVEMENTS



Ⓐ PROP. PEDESTRIAN RAMP (ADA) IMPROVEMENTS

USER NAME = bilgramisa	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100,0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 3/23/2018	DATE -	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY PLAN CERMAK RD.
IL. RTE. 43 (HARLEM AVE.) TO IL. RTE. 50 (CICERO AVE.)

SCALE: 1"=50' SHEET OF SHEETS STA. 100+00 TO STA. 130+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	14
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

MODEL Default
FILE Name: p:\u0000\B&E\BID\NTEC\Illinois.gov\PI\DOT\Documents\BID\Office\BID\rdct_1\p03cscs\03218\CADD\B&E\Design\BID\03218-shr-plan.dgn




USER NAME	= bilgramisa	DESIGNED	-	REVISED	-
		DRAWN	-	REVISED	-
PLOT SCALE	= 100.0000 ' / in.	CHECKED	-	REVISED	-
PLOT DATE	= 3/23/2018	DATE	-	REVISED	-

STATE OF ILLINOIS	
DEPARTMENT OF TRANSPORTATION	

ROADWAY PLAN CERMAK RD.			
IL. RTE. 43 (HARLEM AVE.) TO IL. RTE. 50 (CICERO AVE.)			
SCALE: 1"=50'	SHEET	OF	SHEETS
STA. 130+00		TO STA. 160+00	


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	15
CONTRACT NO. 62F74				
		ILLINOIS	FED. AID PROJECT	

MODEL: Default
FILE: \\nrcs-prod\ulb84e\BID\NTEC\Illinois\gov\PI\DOT\Documents\DOT-Office\BID\DOT-1\Projects\ID103218\CADD\BID\Design\ID103218-shr-plan.dgn



PAVEMENT MARKING LEGEND

- | | |
|---|--|
| ① THERMOPLASTIC PAVEMENT MARKING, 4" DOUBLE SOLID YELLOW CENTERLINE, 2 @ 11" C-C (TYP.) | ⑦ THERMOPLASTIC PAVEMENT MARKING 12" DIAGONAL SOLID WHITE LINE @ 75' C-C (5 MINIMUM) (TYP.) |
| ② THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE TURN LANE (TYP.) | ⑧ THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS, SOLID WHITE (TYP.) |
| ③ THERMOPLASTIC PAVEMENT MARKING, 24" SOLID WHITE STOP BAR (TYP.) | ⑨ THERMOPLASTIC PAVEMENT MARKING, 4" SKIP DASH WHITE LANE LINE, 10' DASH - 30' SKIP (TYP.) |
| ④ THERMOPLASTIC PAVEMENT MARKING, 6" SOLID WHITE CROSSWALK LINE, 2 @ 6' C-C (TYP. UNLESS OTHERWISE NOTED) | ⑩ THERMOPLASTIC PAVEMENT MARKING, 12" SOLID WHITE LONGITUDINAL BAR, SPACED 2' APART (TYP.) |
| ⑤ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID YELLOW LINE (TYP.) | ⑪ THERMOPLASTIC PAVEMENT MARKING, 6" SKIP DASH WHITE TURN LANE, 2' LINE WITH 6' SPACE (TYP.) |
| ⑥ THERMOPLASTIC PAVEMENT MARKING, 4" SINGLE SOLID WHITE LINE (TYP.) | |




USER NAME = bilgramisa	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 3/23/2018	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ROADWAY PLAN CERMAK RD.
IL. RTE. 43 (HARLEM AVE.) TO IL. RTE. 50 (CICERO AVE.)**

SCALE: 1"=50' SHEET OF SHEETS STA. 150+00 TO STA. 177+11.7

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	16
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				



-CURB ISLAND TO BE
REMOVED WITH PROPOSED
INTERSECTION IMPROVEMENTS

	STATION	OFFSET	ELEVATION
A	2346+86.88	35.91 L	(618.40)
B	2347+00.66	41.23 L	618.51
C	2347+01.15	41.52 L	618.51
D	2347+05.35	44.25 L	618.54
E	2347+06.66	45.24 L	618.55
F	2347+07.17	47.68 L	618.79
G	2347+04.41	45.53 L	618.56
H	2347+04.24	45.76 L	618.56
I	2347+00.21	42.80 L	618.53
J	2346+97.08	41.14 L	618.80
K	2346+82.93	46.63 L	(619.21)
L	2346+87.49	48.67 L	(619.19)
M	2346+89.74	44.20 L	(619.12)
N	2346+93.36	52.09 L	618.93
O	2346+96.33	48.06 L	618.86
P	2346+97.39	55.06 L	618.96
Q	2347+00.36	51.03 L	618.89
R	2347+23.77	69.96 L	618.73
S	2347+24.00	70.60 L	618.73
T	2347+25.47	75.44 L	618.76
U	2347+25.62	75.97 L	618.76
V	2347+24.94	79.59 L	619.01
W	2347+24.02	76.14 L	618.78
X	2347+22.55	71.30 L	618.75
Y	2347+21.84	71.64 L	618.76
Z	2347+21.40	67.97 L	618.98
AA	2347+18.69	87.56 L	(619.40)
BB	2347+23.45	86.03 L	619.33
CC	2347+15.84	80.10 L	619.10
DD	2347+13.66	75.60 L	619.08
EE	2347+18.16	73.42 L	619.01
FF	2347+20.34	77.92 L	619.03
GG	2347+28.70	90.37 L	(618.77)
HH	2347+20.06	92.37 L	(619.43)
II	2347+95.89	70.21 L	619.90
JJ	2347+95.87	76.21 L	619.94
KK	2347+06.66	0.00	619.52
LL	2347+00.66	0.00	619.49



(XX.XX)	EXISTING LENGTH/ELEVATION
=====	PROPOSED SIDE CURB
(%)	EXISTING SLOPE


- | | |
|---|--|
|  | PROPOSED SIDEWALK |
|  | DETECTABLE WARNINGS |
|  | SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD |

ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

FILE NAME =	USER NAME = jrobinson	DESIGNED - JIR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SMART CORRIDOR CERMAK ROAD / 22ND STREET & IL-43 (HARLEM AVENUE)				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95212.Cermak-sht-Harlem01.dgn		DRAWN - JIR	REVISED -		1453	(78-1&78-3)RS-2		COOK	54	17			
	PLOT SCALE = 10,0000 ' / in.	CHECKED - RGJ	REVISED -		CONTRACT NO. 62F74								
Default	PLOT DATE = 3/26/2018	DATE - 1/24/2018	REVISED -		SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.			
				ILLINOIS FED. AID PROJECT									

ADA DETAILS FOR PHASE 1 PROJECTS

	STATION	OFFSET	ELEVATION
A	2348+41.66	87.60 L	(618.79)
B	2348+44.11	76.57 L	619.08
C	2348+44.28	75.98 L	619.10
D	2348+45.68	71.18 L	619.12
E	2348+45.85	70.58 L	619.13
F	2348+48.28	68.29 L	619.38
G	2348+47.19	71.62 L	619.14
H	2348+45.79	76.42 L	619.12
I	2348+44.92	79.81 L	619.32
J	2348+51.09	89.29 L	(619.43)
K	2348+49.63	77.54 L	619.40
L	2348+53.47	78.66 L	(619.46)
M	2348+51.03	72.74 L	619.42
N	2348+54.87	73.86 L	(619.48)
O	2348+59.66	47.36 L	619.32
P	2348+61.33	45.83 L	619.34
Q	2348+65.25	42.73 L	619.27
R	2348+65.66	42.44 L	619.26
S	2348+90.93	32.49 L	(618.71)
T	2348+69.17	42.04 L	619.51
U	2348+66.24	43.97 L	619.29
V	2348+66.24	43.97 L	619.29
W	2348+59.76	49.49 L	619.62
X	2348+64.80	50.22 L	619.64
Y	2348+67.28	53.36 L	(619.66)
Z	2348+68.72	47.12 L	619.57
AA	2348+71.21	50.26 L	(619.59)
BB	2348+93.09	41.82 L	(619.50)
CC	2348+65.66	0.00	619.86
DD	2348+59.66	0.00	619.82
EE	2347+95.89	70.21 L	619.90
FF	2347+95.87	76.21 L	619.94



ADA DESIGN INCORPORATES PROPOSED GEOMETRY AND INTERSECTION IMPROVEMENTS FROM PROJECT P-91-357-13. PROPOSED IMPROVEMENTS INCLUDE REMOVAL AND REPLACEMENT OF ALL SIGNAL EQUIPMENT. SIGNAL EQUIPMENT TO BE PLACED OUTSIDE OF RAMP/LANDING/P.A.R.



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

===== PROPOSED SIDE CURB

(%) EXISTING SLOPE


PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2346+75.42	58.96 R	(617.96)
B	2347+00.66	64.53 R	618.00
C	2347+01.18	64.71 R	618.01
D	2347+06.08	66.50 R	618.08
E	2347+06.66	66.73 R	618.09
F	2346+85.56	62.13 R	618.55
G	2346+90.66	63.27 R	618.59
H	2347+00.67	66.21 R	618.03
I	2347+05.50	67.98 R	618.10
J	2347+14.90	72.72 R	618.69
K	2347+19.39	76.02 R	618.76
L	2347+16.20	79.88 R	618.79
M	2347+12.17	76.92 R	618.72
N	2347+03.75	72.66 R	618.13
O	2346+99.05	70.94 R	618.06
P	2346+89.46	68.12 R	618.64
Q	2346+84.58	67.03 R	618.59
R	2346+74.21	69.98 R	(618.55)
S	2347+23.87	77.97 R	618.40
T	2347+24.61	78.72 R	618.41
U	2347+28.35	83.10 R	618.48
V	2347+28.98	83.95 R	618.49
W	2347+38.76	106.28 R	(618.67)
X	2347+33.99	96.66 R	619.07
Y	2347+31.80	91.62 R	619.02
Z	2347+27.09	84.06 R	618.50
AA	2347+23.47	79.82 R	618.43
BB	2347+19.86	83.28 R	618.46
CC	2347+23.11	87.08 R	618.53
DD	2347+27.33	93.86 R	619.07
EE	2347+29.32	98.45 R	619.12
FF	2347+29.49	108.72 R	(619.22)
GG	2347+00.66	0.00	619.49
HH	2347+06.66	0.00	619.52
II	2347+96.75	83.71 R	619.72
JJ	2347+96.71	77.71 R	619.70

ADA DESIGN INCORPORATES PROPOSED
GEOMETRY AND INTERSECTION
IMPROVEMENTS FROM PROJECT P-91-357-13.
PROPOSED IMPROVEMENTS INCLUDE REMOVAL
AND REPLACEMENT OF ALL SIGNAL
EQUIPMENT. SIGNAL EQUIPMENT TO BE
PLACED OUTSIDE OF RAMP/LANDING/P.A.R.



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK

 DETECTABLE WARNINGS SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


SMART CORRIDOR
CERMAK ROAD / 22ND STREET & IL-43 (HARLEM AVENUE)

SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.
----------------	-------	----	--------	------	---------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	19
		CONTRACT NO. 62F74		
		ILLINOIS FED. AID PROJECT		

ADA DETAILS FOR PHASE 1 PROJECTS

	STATION	OFFSET	ELEVATION
A	2348+44.39	94.30 R	(618.92)
B	2348+47.75	83.34 R	619.14
C	2348+47.96	82.82 R	619.16
D	2348+50.13	78.28 R	619.09
E	2348+50.66	77.31 R	619.08
F	2348+53.23	76.09 R	619.29
G	2348+51.99	79.45 R	619.09
H	2348+51.47	79.12 R	619.09
I	2348+49.32	83.68 R	619.16
J	2348+48.08	87.03 R	619.36
K	2348+54.15	96.63 R	(619.55)
L	2348+54.15	96.63 R	(619.55)
M	2348+57.94	89.11 R	(619.58)
N	2348+56.80	82.48 R	619.49
O	2348+60.18	84.62 R	(619.51)
P	2348+59.66	65.62 R	618.99
Q	2348+61.29	64.10 R	618.96
R	2348+65.18	60.95 R	618.91
S	2348+65.66	60.60 R	618.91
T	2348+75.48	55.07 R	(618.87)
U	2348+69.08	60.21 R	619.10
V	2348+66.18	62.18 R	618.91
W	2348+62.29	65.33 R	618.96
X	2348+59.76	67.77 R	619.21
Y	2348+66.08	70.00 R	619.16
Z	2348+69.23	73.89 R	619.19
AA	2348+73.11	70.74 R	619.14
BB	2348+69.96	66.85 R	619.11
CC	2348+75.00	63.70 R	619.32
DD	2348+77.36	68.11 R	(619.35)
EE	2348+80.43	66.64 R	(619.28)
FF	2347+96.75	83.71 R	619.72
GG	2347+96.71	77.71 R	619.70
HH	2348+59.66	0.00	619.82
II	2348+65.66	0.00	619.86



ADA DESIGN INCORPORATES PROPOSED
GEOMETRY AND INTERSECTION
IMPROVEMENTS FROM PROJECT P-91-357-13.
PROPOSED IMPROVEMENTS INCLUDE REMOVAL
AND REPLACEMENT OF ALL SIGNAL
EQUIPMENT. SIGNAL EQUIPMENT TO BE
PLACED OUTSIDE OF RAMP/LANDING/P.A.R.

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

11

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD



FILE NAME =
95212_Cermak-sht-Harlem04.dgn

```
USER NAME = j1robinson
```

DESIGNED - JIR

REVISÉ

PLOT SCALE = 10.0000' / in.

CHECKED - RG

REVISÉD


**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & IL-43 (HARLEM AVENUE)

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	20
		CONTRACT NO. 62F74		
ILLINOIS		FED. AID PROJECT		

Default

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2357+85.25	28.75 L	(617.65)
B	2357+99.04	28.75 L	617.92
C	2358+00.51	28.75 L	617.94
D	2358+04.51	28.75 L	617.97
E	2358+05.05	28.75 L	617.97
F	2358+19.51	28.75 L	(617.87)
G	2358+08.01	30.33 L	618.18
H	2358+04.51	30.33 L	618.00
I	2358+00.51	30.33 L	617.97
J	2357+97.01	30.33 L	618.20
K	2357+86.04	38.33 L	(618.67)
L	2357+92.01	37.83 L	(618.68)
M	2358+00.51	37.83 L	618.28
N	2358+04.51	37.83 L	618.31
O	2358+12.01	37.83 L	(618.68)
P	2358+12.01	33.83 L	(618.62)
Q	2358+04.51	33.83 L	618.25
R	2358+00.51	33.83 L	618.22
S	2357+92.01	33.83 L	(618.62)
T	2357+97.61	0.00	618.64
U	2358+03.62	0.00	618.69
V	2358+19.51	38.33 L	(618.60)

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

PROPOSED SIDE CURB

(%) EXISTING SLOPE

PROPOSED SIDEWALK



DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



ADA DETAILS FOR PHASE 1 PROJECTS



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE


PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS




FILE NAME = 95212-Cermak-sht-Wenonah02.dgn Default	USER NAME = jirobinson	DESIGNED - JIR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SMART CORRIDOR CERMAK ROAD / 22ND STREET & WENONAH AVENUE				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JIR	REVISED -		1453	(78-1&78-3)RS-2	COOK	54	22				
	PLOT SCALE = 10.0000 ' / in.	CHECKED - RGJ	REVISED -		CONTRACT NO. 62F74								
	PLOT DATE = 3/26/2018	DATE - 1/24/2018	REVISED -		ILLINOIS FED. AID PROJECT								
					SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.			

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2361+71.11	44.40 L	(618.12)
B	2361+71.11	40.00 L	(618.09)
C	2361+76.32	39.40 L	617.89
D	2361+76.32	35.40 L	617.85
E	2361+81.32	35.40 L	617.80
F	2361+81.32	39.40 L	617.84
G	2361+89.86	44.38 L	(617.05)
H	2361+87.95	41.42 L	617.65
I	2361+89.18	39.86 L	617.50
J	2361+89.03	39.39 L	617.53
K	2361+87.35	39.40 L	617.55
L	2361+87.02	35.39 L	617.57
M	2361+85.87	33.92 L	617.59
N	2361+85.04	35.40 L	617.59
O	2361+82.88	33.25 L	617.83
P	2361+81.82	30.62 L	617.65
Q	2361+81.32	30.34 L	617.67
R	2361+81.32	32.16 L	617.69
S	2361+76.32	28.69 L	617.70
T	2361+75.83	28.62 L	617.68
U	2361+76.32	30.29 L	617.72
V	2361+76.32	32.16 L	617.74
W	2361+71.11	28.50 L	(617.58)
X	2361+73.32	30.08 L	617.86
Y	2361+75.98	0.00	618.84
Z	2361+81.98	0.00	618.83
AA	2362+04.11	39.60 L	618.16
BB	2362+04.11	33.60 L	618.23
CC	2361+85.04	39.40 L	617.56

	STATION	OFFSET	ELEVATION
A	2362+42.88	38.82 L	(618.18)
B	2362+35.88	38.82 L	(617.98)
C	2362+35.88	45.82 L	(617.96)
D	2362+35.88	33.82 L	617.93
E	2362+30.88	33.81 L	617.88
F	2362+30.88	38.82 L	617.93
G	2362+24.09	38.81 L	617.48
H	2362+18.33	45.80 L	(617.16)
I	2362+20.18	41.80 L	617.54
J	2362+19.17	39.34 L	617.40
K	2362+19.34	38.81 L	617.42
L	2362+21.03	38.81 L	617.44
M	2362+22.04	33.81 L	617.46
N	2362+22.46	33.28 L	617.48
O	2362+24.09	33.81 L	617.48
P	2362+28.18	30.50 L	617.87
Q	2362+30.38	27.76 L	617.66
R	2362+30.88	27.60 L	617.65
S	2362+30.88	29.27 L	617.66
T	2362+35.88	29.27 L	617.65
U	2362+35.88	26.76 L	617.62
V	2362+36.39	26.75 L	617.60
W	2362+38.88	28.33 L	617.83
X	2362+42.88	26.75 L	(617.58)
Y	2362+30.63	0.00	618.84
Z	2362+36.63	0.00	618.85
AA	2362+04.11	39.60 L	618.16
BB	2362+04.11	33.60 L	618.23
CC	2362+35.88	28.34 L	617.64



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE


PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



FILE NAME = 95212_Cermak-sht-Home01.dgn	USER NAME = jrobinson	DESIGNED - KBH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SMART CORRIDOR CERMAK ROAD / 22ND STREET & HOME AVENUE			F.A.J. RTE. 1453	SECTION (78-1&78-3)RS-2	COUNTY COOK	TOTAL SHEETS 54	SHEET NO. 22A
Default	PLOT SCALE = 10.0000" / 1in.	CHECKED - JIR	REVISED -		SCALE: 1" = 5'	SHEET	OF SHEETS	STA.	TO STA.	CONTRACT NO. 62F74		
	PLOT DATE = 3/26/2018	DATE - 1/24/2018	REVISED -							ILLINOIS FED. AID PROJECT		

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2361+71.64	47.35 R	(618.48)
B	2361+76.64	42.35 R	618.47
C	2361+80.64	42.35 R	618.43
D	2361+80.64	38.35 R	618.39
E	2361+76.64	38.35 R	618.43
F	2361+73.64	32.85 R	618.30
G	2361+71.56	31.34 R	(617.94)
H	2361+76.14	31.49 R	618.10
I	2361+76.65	31.59 R	618.13
J	2361+76.64	33.20 R	618.15
K	2361+76.64	34.68 R	618.17
L	2361+80.65	32.90 R	618.16
M	2361+80.64	34.68 R	618.18
N	2361+82.15	33.71 R	618.17
O	2361+82.84	36.11 R	618.35
P	2361+86.54	37.52 R	618.12
Q	2361+85.17	38.35 R	618.13
R	2361+87.17	38.35 R	618.11
S	2361+87.60	42.35 R	618.08
T	2361+89.30	42.35 R	618.06
U	2361+89.61	43.25 R	618.02
V	2361+90.33	47.25 R	(617.84)
W	2361+88.50	45.35 R	618.21
X	2361+85.17	42.35 R	618.11
Y	2362+04.11	35.82 R	618.23
Z	2362+04.11	41.85 R	618.21
AA	2361+75.98	0.00	618.84
BB	2361+81.98	0.00	618.83



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE


PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & HOME AVENUE

SCALE: 1" = 5' SHEET OF SHEETS STA. TO STA.



	STATION	OFFSET	ELEVATION
A	2362+36.49	44.36 R	(618.02)
B	2362+36.49	39.36 R	(617.99)
C	2362+42.40	39.36 R	(617.98)
D	2362+36.40	34.36 R	617.94
E	2362+36.40	38.36 R	617.98
F	2362+31.40	38.37 R	617.93
G	2362+31.40	34.37 R	617.89
H	2362+25.91	38.37 R	617.75
I	2362+19.12	44.13 R	(617.65)
J	2362+20.12	40.29 R	617.67
K	2362+21.64	40.76 R	617.89
L	2362+20.97	38.37 R	617.69
M	2362+22.77	38.37 R	617.71
N	2362+23.71	34.37 R	617.75
O	2362+24.17	33.87 R	617.76
P	2362+25.91	34.37 R	617.77
Q	2362+29.61	31.68 R	618.12
R	2362+30.90	29.34 R	617.99
S	2362+31.40	29.15 R	618.00
T	2362+31.40	30.84 R	618.02
U	2362+36.40	29.65 R	618.05
V	2362+36.40	28.06 R	618.03
W	2362+36.89	28.03 R	618.03
X	2362+36.40	30.84 R	618.07
Y	2362+40.40	29.58 R	618.27
Z	2362+42.40	28.00 R	(618.05)
AA	2362+04.11	35.82 R	618.23
BB	2362+04.11	41.85 R	618.21
CC	2362+30.63	0.00	618.84
DD	2362+36.63	0.00	618.85

FILE NAME =
95212_Cermak-sht-Home02.dgn
Default

USER NAME = jrobinson
PLOT SCALE = 10.0000 " / in.
PLOT DATE = 3/26/2018

DESIGNED - KBH
DRAWN - KBH
CHECKED - JIR
DATE - 1/24/2018


REVISED -
REVISED -
REVISED -
REVISED -

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	22B
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

CERMAK RD

KENILWORTH AVE

KENILWORTH AVE. NORTH LEG



LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE



PROPOSED SIDEWALK



PROPOSED SIDE CURB

SC

TOP OF PROPOSED
SIDE CURB



CLASS D PATCH



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 619.15

BENCHMARK : ARROW POINTS TO SOUTH WESTERNLY LOWER
FLANGE BOLT OF HYDRANT

LOCATION : ON NORTH WEST CORNER OF CERMAK RD. AND
KENILWORTH AVE.

FILE NAME =	USER NAME = Bilgramiso	DESIGNED -	ML 4/27/18
pw\11084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI03218\Design\DI03218-sh\Default.sldg		REVIS	
		REVIS	
		REVIS	
		REVIS	


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN
CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)


SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	22C
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2375+69.90	38.95 L	(616.92)
B	2375+71.92	38.95 L	(616.88)
C	2375+71.92	40.00 L	(616.91)
D	2375+78.28	38.94 L	616.75
E	2375+79.40	40.00 L	(616.78)
F	2375+79.40	45.00 L	(616.79)
G	2375+78.28	34.94 L	616.71
H	2375+82.28	34.94 L	616.67
I	2375+82.28	38.94 L	616.71
J	2375+86.82	41.94 L	616.77
K	2375+88.40	45.00 L	(616.27)
L	2375+86.52	38.94 L	616.54
M	2375+88.22	39.41 L	616.50
N	2375+88.14	38.94 L	616.52
O	2375+84.96	38.94 L	616.56
P	2375+86.77	34.94 L	616.56
Q	2375+85.90	33.45 L	616.57
R	2375+84.96	34.94 L	616.58
S	2375+83.63	33.07 L	616.81
T	2375+83.75	30.89 L	616.59
U	2375+82.28	31.69 L	616.62
V	2375+82.28	29.66 L	616.60
W	2375+78.28	27.56 L	616.62
X	2375+77.82	27.41 L	616.60
Y	2375+78.28	29.25 L	616.64
Z	2375+78.28	31.69 L	616.66
AA	2375+69.90	26.75 L	(616.51)
BB	2375+69.90	28.33 L	(616.93)
CC	2375+78.34	0.00	617.69
DD	2375+84.34	0.00	617.68
EE	2376+12.40	39.04 L	617.43
FF	2376+12.40	33.04 L	617.48



	STATION	OFFSET	ELEVATION		STATION	OFFSET	ELEVATION		STATION	OFFSET	ELEVATION
A	2376+64.15	38.15 L	(617.08)	L	2376+48.35	53.14 L	(617.01)	W	2376+43.92	27.71 L	616.54
B	2376+64.15	33.15 L	(616.93)	M	2376+36.40	53.14 L	(616.17)	X	2376+44.87	0.00	617.74
C	2376+64.14	26.50 L	(616.40)	N	2376+43.35	48.44 L	616.96	Y	2376+38.87	0.00	617.72
D	2376+59.15	33.15 L	617.06	O	2376+43.35	43.43 L	616.94	Z	2376+12.40	39.04 L	617.43
E	2376+59.15	38.15 L	(617.10)	P	2376+43.35	38.15 L	616.58	AA	2376+12.40	33.04 L	617.48
F	2376+54.15	38.15 L	(617.05)	Q	2376+38.07	38.15 L	616.50				
G	2376+54.15	33.15 L	(617.01)	R	2376+36.43	38.68 L	616.46				
H	2376+48.35	33.15 L	616.61	S	2376+36.47	38.15 L	616.48				
I	2376+48.35	38.15 L	616.65	T	2376+37.74	32.66 L	616.51				
J	2376+48.35	43.43 L	(617.01)	U	2376+43.35	29.82 L	616.58				
K	2376+48.35	48.43 L	(617.03)	V	2376+43.34	28.00 L	616.56				

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



PROPOSED SIDEWALK



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD



FILE NAME =
95212_Cermak-sht-0akPark01.dgn

USER NAME	= j1robinson
-----------	--------------

DESIGNED - KBH

REVISÉ -

REVISÉ -

PLOT SCALE = 10.0000 ' /

CHECKED	-
---------	---

REVISÉ -

REVISÉ -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & OAK PARK AVENUE

SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.
----------------	-------	----	--------	------	---------

F.A.U. RTE.	1453
----------------	------

SECTION

COUNTY


TOTAL SHEETS	SHEET NO.
-----------------	--------------

SHEET 13	NO.
54	22E


CONTRACT NO. 62F74

ILLINOIS	FED. AID PROJECT
----------	------------------

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2375+63.40	35.50 R	(616.80)
B	2375+63.40	39.50 R	(616.95)
C	2375+67.40	39.50 R	(616.99)
D	2375+67.40	35.50 R	616.95
E	2375+71.40	35.50 R	616.99
F	2375+71.40	39.50 R	(617.03)
G	2375+79.90	39.50 R	616.47
H	2375+79.40	46.00 R	(616.92)
I	2375+79.40	52.00 R	(616.93)
J	2375+79.40	57.00 R	(616.95)
K	2375+86.82	57.00 R	(616.77)
L	2375+88.40	57.00 R	(616.33)
M	2375+86.82	52.00 R	616.82
N	2375+86.82	46.00 R	616.81
O	2375+86.70	39.50 R	616.44
P	2375+87.37	35.98 R	616.36
Q	2375+87.17	35.50 R	616.38
R	2375+85.41	35.50 R	616.40
S	2375+84.91	30.00 R	616.50
T	2375+79.40	29.88 R	616.35
U	2375+79.40	28.17 R	616.33
V	2375+78.87	27.99 R	616.30
W	2375+63.40	27.25 R	(616.18)
X	2375+78.34	0.00	617.69
Y	2375+84.34	0.00	617.68
Z	2376+12.40	29.75 R	617.59
AA	2376+12.40	35.75 R	617.55



	STATION	OFFSET	ELEVATION
A	2376+54.15	35.00 R	(616.92)
B	2376+54.15	40.00 R	(617.00)
C	2376+45.40	40.00 R	(616.73)
D	2376+45.40	44.00 R	(616.76)
E	2376+38.24	44.00 R	(616.51)
F	2376+36.65	44.00 R	(616.07)
G	2376+38.24	40.00 R	616.63
H	2376+37.42	35.52 R	616.57
I	2376+37.64	35.00 R	616.59
J	2376+39.38	35.00 R	616.61
K	2376+45.40	35.00 R	616.68
L	2376+54.15	27.75 R	(616.51)
M	2376+45.84	28.08 R	616.60
N	2376+45.40	28.20 R	616.62
O	2376+45.40	29.85 R	616.64
P	2376+39.89	29.50 R	616.64
Q	2376+44.87	0.00	617.74
R	2376+38.87	0.00	617.72
S	2376+12.40	29.75 R	617.59
T	2376+12.40	35.75 R	617.55

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



PROPOSED SIDEWALK



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD



FILE NAME =
95212_Cermak-sht-OakPark02.dgn

USER NAME = j1robinsor

DESIGNED - KB

REVISÉ

REVISÉ

REVISÉ

REVISÉ

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & OAK PARK AVENUE

SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.
----------------	-------	----	--------	------	---------

F.A.U. RTE.	1453
----------------	------

SECTION

COUNTY

COOK

CONTRA


PROJECT

TOTAL SHEETS	SHEET NO.
54	225

NO 62E74


ILLINOIS	FED. AID PROJECT
----------	------------------

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2382+37.03	26.50 L	616.17
B	2382+46.53	26.60 L	616.14
C	2382+47.03	26.66 L	616.13
D	2382+52.03	27.91 L	616.08
E	2382+52.50	28.10 L	616.08
F	2382+43.53	28.08 L	616.37
G	2382+55.53	31.55 L	616.35
H	2382+47.03	28.25 L	616.13
I	2382+47.03	29.62 L	616.15
J	2382+52.03	29.62 L	616.08
K	2382+47.03	34.35 L	616.48
L	2382+52.03	34.35 L	616.41
M	2382+52.03	38.35 L	616.43
N	2382+47.03	38.35 L	616.50
O	2382+37.03	38.35 L	(616.89)
P	2382+47.03	58.00 L	(616.97)
Q	2382+65.47	58.00 L	(616.29)
R	2382+65.47	53.00 L	616.40
S	2382+65.47	51.50 L	616.41
T	2382+65.47	47.50 L	616.44
U	2382+65.46	47.00 L	616.44
V	2382+63.78	45.50 L	616.64
W	2382+63.88	47.50 L	616.46
X	2382+63.88	51.50 L	616.43
Y	2382+63.88	55.00 L	616.65
Z	2382+54.03	47.50 L	616.94
AA	2382+54.03	51.50 L	616.90
BB	2382+47.03	51.50 L	(616.96)
CC	2382+47.03	47.50 L	(617.02)
DD	2382+47.13	0.00	617.47
EE	2382+53.13	0.00	617.48
FF	2382+78.97	47.25 L	617.11
GG	2382+78.97	53.25 L	617.07

	STATION	OFFSET	ELEVATION
A	2382+92.81	53.50 L	616.90
B	2382+92.88	53.00 L	616.90
C	2382+93.57	48.00 L	616.95
D	2382+93.65	47.51 L	616.95
E	2382+94.57	56.00 L	617.08
F	2382+95.68	53.00 L	616.89
G	2382+94.98	53.00 L	616.88
H	2382+95.68	48.00 L	616.93
I	2382+97.15	45.00 L	617.21
J	2382+98.47	53.00 L	617.05
K	2382+98.47	48.00 L	617.10
L	2383+03.47	48.00 L	617.15
M	2383+03.47	53.00 L	617.10
N	2383+11.97	58.50 L	(617.09)
O	2382+92.22	58.50 L	(616.82)
P	2383+11.97	41.00 L	(616.85)
Q	2382+78.97	53.25 L	617.07
R	2382+78.97	47.25 L	617.11



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

===== PROPOSED SIDE CURB

(%) EXISTING SLOPE


** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

ADA DETAILS FOR PHASE 1 PROJECTS



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

===== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD



	STATION	OFFSET	ELEVATION
A	2382+31.37	28.00 R	(616.52)
B	2382+47.78	29.17 R	616.41
C	2382+48.28	29.32 R	616.41
D	2382+61.96	38.50 R	616.28
E	2382+62.48	39.14 R	616.26
F	2382+65.76	44.43 R	(616.00)
G	2382+31.37	39.00 R	(617.11)
H	2382+35.37	38.50 R	617.08
I	2382+40.37	38.50 R	617.01
J	2382+35.37	29.58 R	617.04
K	2382+40.37	29.59 R	616.97
L	2382+48.28	38.50 R	616.45
M	2382+59.86	38.50 R	616.28
N	2382+53.03	38.50 R	616.38
O	2382+53.03	44.25 R	616.79
P	2382+53.03	50.50 R	616.85
Q	2382+48.28	30.99 R	616.41
R	2382+53.03	59.50 R	616.97
S	2382+53.03	64.50 R	(616.89)
T	2382+48.03	64.50 R	(617.17)
U	2382+48.03	59.50 R	(617.02)
V	2382+48.03	50.50 R	616.88
W	2382+39.57	58.28 R	(617.25)
X	2382+36.23	54.65 R	(617.25)
Y	2382+45.04	47.23 R	616.90
Z	2382+48.28	44.25 R	616.86
AA	2382+47.13	0.00	617.50
BB	2382+53.13	0.00	617.51
CC	2383+17.02	46.34 R	616.93
DD	2383+11.71	51.21 R	616.94
EE	2382+53.84	31.72 R	616.36
FF	2382+53.82	30.84 R	616.37

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2383+32.40	64.02 R	(616.24)
B	2383+38.58	57.80 R	616.34
C	2383+38.99	57.39 R	616.34
D	2383+43.17	53.26 R	616.37
E	2383+43.60	52.86 R	616.37
F	2383+57.23	42.88 R	(616.40)
G	2383+41.36	57.97 R	616.32
H	2383+44.40	58.72 R	616.34
I	2383+45.60	53.86 R	616.35
J	2383+48.35	54.53 R	616.55
K	2383+53.20	55.72 R	616.62
L	2383+52.01	60.58 R	616.60
M	2383+59.84	62.50 R	(616.92)
N	2383+47.15	59.39 R	616.54
O	2383+43.91	69.16 R	(616.70)
P	2383+40.23	72.54 R	(616.72)
Q	2383+36.00	67.94 R	(616.70)
R	2383+40.53	65.48 R	616.68
S	2383+17.02	46.34 R	616.93
T	2383+11.71	51.21 R	616.94
U	2383+61.03	57.64 R	(616.83)



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

===== PROPOSED SIDE CURB


(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS


PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD




ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2389+09.09	42.75 L	(615.23)
B	2389+13.69	43.08 L	615.19
C	2389+14.09	43.16 L	615.18
D	2389+19.09	45.05 L	615.12
E	2389+19.86	45.51 L	615.10
F	2389+22.09	50.07 L	615.23
G	2389+19.09	47.49 L	615.10
H	2389+14.09	45.29 L	615.16
I	2389+14.09	47.49 L	615.17
J	2389+11.09	44.85 L	(615.41)
K	2389+14.09	52.49 L	615.29
L	2389+19.09	52.49 L	615.22
M	2389+14.09	57.49 L	615.32
N	2389+19.09	57.49 L	615.25
O	2389+09.09	56.19 L	(615.41)
P	2388+98.09	56.19 L	(615.53)
Q	2389+28.28	67.69 L	614.60
R	2389+28.28	68.19 L	614.58
S	2389+28.28	73.19 L	614.51
T	2389+28.28	73.69 L	614.49
U	2389+28.28	73.69 L	614.49
V	2389+26.20	73.19 L	614.49
W	2389+26.20	68.19 L	614.56
X	2389+26.20	64.69 L	614.84
Y	2389+18.59	73.19 L	615.03
Z	2389+14.59	73.19 L	615.09
AA	2389+18.59	68.19 L	615.05
BB	2389+14.59	68.19 L	615.11
CC	2389+18.59	78.69 L	615.28
DD	2389+14.59	78.69 L	(615.34)
EE	2389+19.09	83.69 L	(615.19)
FF	2389+14.09	83.69 L	(615.35)
GG	2389+09.09	68.19 L	615.43
HH	2389+09.09	73.19 L	(615.46)
II	2389+04.09	73.69 L	(615.52)
JJ	2389+04.09	68.19 L	615.45
KK	2388+98.09	73.69 L	(615.50)
LL	2389+11.00	0.00	615.83
MM	2389+17.01	0.00	615.78
NN	2389+46.03	67.69 L	615.05
OO	2389+46.03	73.69 L	614.98

	STATION	OFFSET	ELEVATION
A	2389+64.03	78.80 L	(614.25)
B	2389+64.03	73.69 L	614.31
C	2389+64.03	73.00 L	614.33
D	2389+64.03	68.00 L	614.40
E	2389+64.03	67.69 L	614.41
F	2389+64.03	67.69 L	614.41
G	2389+66.12	68.00 L	614.38
H	2389+66.12	73.00 L	614.31
I	2389+73.24	68.00 L	614.77
J	2389+78.24	68.00 L	614.84
K	2389+73.24	73.00 L	614.80
L	2389+73.24	73.80 L	614.81
M	2389+73.24	78.80 L	614.93
N	2389+72.74	82.80 L	(614.84)
O	2389+78.74	82.80 L	(615.01)
P	2389+78.24	78.80 L	(615.00)
Q	2389+78.24	73.80 L	614.88
R	2389+84.24	73.80 L	615.16
S	2389+89.24	74.30 L	(615.21)
T	2389+89.24	66.50 L	(615.01)
U	2389+73.53	34.24 L	615.12
V	2389+74.03	34.01 L	615.12
W	2389+79.03	32.62 L	615.06
X	2389+79.53	32.57 L	615.06
Y	2389+84.03	32.50 L	(615.04)
Z	2389+82.53	34.58 L	615.28
AA	2389+79.03	34.72 L	615.04
BB	2389+79.03	36.33 L	615.05
CC	2389+74.03	36.33 L	615.10
DD	2389+70.53	38.90 L	615.33
EE	2389+74.03	42.33 L	615.14
FF	2389+74.03	47.33 L	615.09
GG	2389+79.03	47.33 L	615.04
HH	2389+79.03	42.33 L	615.09
II	2389+46.03	73.69 L	614.98
JJ	2389+46.03	67.69 L	615.05
KK	2389+73.53	0.00	615.64
LL	2389+79.53	0.00	615.61
MM	2389+84.24	68.00 L	615.08




LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2389+03.20	44.75 R	614.88
B	2389+08.20	44.81 R	614.85
C	2389+08.70	44.86 R	614.85
D	2389+13.70	45.95 R	614.81
E	2389+14.13	46.10 R	614.81
F	2389+05.20	46.83 R	615.10
G	2389+08.70	46.95 R	614.83
H	2389+08.70	48.17 R	614.84
I	2389+13.70	48.17 R	614.79
J	2389+17.20	49.93 R	615.02
K	2389+08.70	52.17 R	614.98
L	2389+13.70	52.17 R	614.93
M	2389+08.70	57.17 R	615.00
N	2389+13.70	57.17 R	614.95
O	2389+28.53	69.07 R	614.67
P	2389+28.53	69.57 R	614.67
Q	2389+28.53	74.57 R	614.69
R	2389+28.53	75.07 R	614.69
S	2389+28.53	77.57 R	(614.70)
T	2389+26.44	66.07 R	614.91
U	2389+26.45	69.57 R	614.65
V	2389+26.45	74.57 R	614.67
W	2389+13.70	69.57 R	614.96
X	2389+08.70	69.57 R	615.02
Y	2389+13.70	74.57 R	(614.98)
Z	2389+08.70	74.57 R	(615.04)
AA	2389+03.20	74.57 R	(615.17)
BB	2389+11.00	0.00	615.83
CC	2389+17.00	0.00	615.78
DD	2389+48.03	69.07 R	614.94
EE	2389+48.03	75.07 R	614.87


	STATION	OFFSET	ELEVATION
A	2389+64.03	79.57 R	(614.18)
B	2389+64.03	75.07 R	614.36
C	2389+64.03	74.57 R	614.38
D	2389+64.03	69.57 R	614.45
E	2389+64.03	69.07 R	614.46
F	2389+66.12	64.57 R	614.84
G	2389+66.12	69.57 R	614.43
H	2389+66.12	74.57 R	614.36
I	2389+66.12	78.07 R	614.63
J	2389+76.53	74.57 R	615.10
K	2389+76.53	69.57 R	615.08
L	2389+81.03	74.57 R	(615.16)
M	2389+81.03	69.57 R	615.14
N	2389+81.03	79.57 R	(615.12)
O	2389+82.78	74.57 R	(615.18)
P	2389+73.53	36.90 R	615.05
Q	2389+74.03	36.56 R	615.06
R	2389+79.03	34.14 R	615.11
S	2389+79.53	33.98 R	615.12
T	2389+82.44	33.29 R	(615.14)
U	2389+82.45	35.41 R	(615.33)
V	2389+79.03	36.35 R	615.09
W	2389+79.03	39.10 R	615.11
X	2389+74.03	39.10 R	615.04
Y	2389+70.53	42.49 R	615.17
Z	2389+74.03	47.33 R	615.19
AA	2389+79.03	47.33 R	615.17
BB	2389+79.03	52.33 R	615.19
CC	2389+74.03	52.33 R	615.21
DD	2389+48.03	69.07 R	614.94
EE	2389+48.03	75.07 R	614.87
FF	2389+73.53	0.00	615.64
GG	2389+79.53	0.00	615.61

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



SCALE: 1" = 5'
SHEET OF SHEETS
STA. TO STA.

FILE NAME = 95212_Cermak-sht-East02.dgn
Default

USER NAME = jrobinson
PLOT SCALE = 10.0000" / 1in.
PLOT DATE = 3/26/2018

DESIGNED - JIR
DRAWN - JIR
CHECKED - JMA
DATE - 1/24/2018


REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & EAST AVENUE


F.A.U. RTE. 1453
SECTION (78-1&78-3)RS-2
COUNTY COOK
TOTAL SHEETS 54
SHEET NO. 22K
CONTRACT NO. 62F74
ILLINOIS FED. AID PROJECT

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2402+35.67	43.25 L	(611.49)
B	2402+40.22	43.25 L	611.52
C	2402+40.67	43.25 L	611.52
D	2402+45.67	43.25 L	611.54
E	2402+46.23	43.26 L	611.54
F	2402+49.17	46.08 L	611.76
G	2402+45.67	45.33 L	611.52
H	2402+40.67	45.33 L	611.50
I	2402+37.17	45.33 L	611.77
J	2402+40.67	49.33 L	611.69
K	2402+45.67	49.33 L	611.71
L	2402+45.67	54.33 L	611.74
M	2402+40.67	54.33 L	611.72
N	2402+35.67	67.34 L	(611.93)
O	2402+29.14	67.34 L	(611.97)
P	2402+55.68	68.95 L	611.03
Q	2402+55.68	69.45 L	611.02
R	2402+55.64	74.45 L	610.99
S	2402+55.63	74.95 L	610.98
T	2402+55.62	77.45 L	(610.86)
U	2402+53.56	74.43 L	611.01
V	2402+53.59	69.43 L	610.04
W	2402+53.62	65.93 L	611.33
X	2402+45.68	69.37 L	611.46
Y	2402+41.18	69.34 L	611.53
Z	2402+45.64	74.37 L	611.49
AA	2402+41.14	74.34 L	611.56
BB	2402+40.53	88.83 L	(612.21)
CC	2402+40.48	94.83 L	(612.24)
DD	2402+45.48	94.87 L	(612.07)
EE	2402+45.53	88.87 L	612.14
FF	2402+34.14	74.84 L	(611.95)
GG	2402+29.14	74.84 L	(612.00)
HH	2402+29.14	69.34 L	(612.03)
II	2402+34.14	69.34 L	(611.96)
JJ	2402+43.14	0.00	612.39
KK	2402+49.16	0.00	612.33
LL	2402+79.94	68.40 L	612.23
MM	2402+79.89	74.40 L	612.19

	STATION	OFFSET	ELEVATION
A	2403+03.53	81.37 L	(611.29)
B	2403+03.60	73.87 L	611.41
C	2403+03.60	73.37 L	611.42
D	2403+03.64	68.37 L	611.47
E	2403+03.65	67.87 L	611.48
F	2403+05.76	64.88 L	611.73
G	2403+05.73	68.38 L	611.47
H	2403+05.69	73.38 L	611.42
I	2403+05.66	76.88 L	611.66
J	2403+14.35	73.46 L	612.03
K	2403+14.39	68.46 L	612.01
L	2403+19.39	68.50 L	612.08
M	2403+19.35	73.50 L	612.10
N	2403+19.28	81.50 L	(612.27)
O	2403+19.34	74.50 L	(612.11)
P	2403+24.34	74.50 L	(612.27)
Q	2403+14.00	37.56 L	611.82
R	2403+14.34	37.29 L	611.83
S	2403+19.34	34.42 L	611.86
T	2403+19.70	34.26 L	611.86
U	2403+23.87	32.92 L	(611.88)
V	2403+22.84	35.35 L	612.08
W	2403+19.34	36.71 L	611.84
X	2403+19.34	39.94 L	611.86
Y	2403+14.34	39.94 L	611.81
Z	2403+11.34	42.96 L	612.05
AA	2403+14.34	44.94 L	612.09
BB	2403+14.34	49.94 L	612.14
CC	2403+19.34	49.94 L	612.19
DD	2403+19.34	44.94 L	612.14
EE	2402+79.89	74.40 L	612.19
FF	2402+79.94	68.40 L	612.23
GG	2403+10.30	0.00	612.23
HH	2403+16.33	0.00	612.19



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE


** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2402+40.93	42.50 R	(611.65)
B	2402+46.01	42.50 R	611.68
C	2402+46.43	42.50 R	611.68
D	2402+51.43	42.94 R	611.74
E	2402+52.07	43.13 R	611.74
F	2402+54.93	47.00 R	611.97
G	2402+51.43	45.11 R	611.72
H	2402+46.43	45.11 R	611.67
I	2402+46.43	44.58 R	611.66
J	2402+42.93	44.58 R	611.85
K	2402+46.43	49.11 R	611.89
L	2402+46.43	54.11 R	611.91
M	2402+51.43	54.11 R	611.84
N	2402+51.43	49.11 R	611.82
O	2402+61.05	68.54 R	611.40
P	2402+61.04	69.04 R	611.40
Q	2402+61.03	74.04 R	611.43
R	2402+61.03	74.54 R	611.44
S	2402+60.98	94.54 R	(611.54)
T	2402+58.94	77.53 R	611.67
U	2402+58.95	74.03 R	611.41
V	2402+58.96	69.03 R	611.38
W	2402+58.97	65.53 R	611.64
X	2402+52.04	69.01 R	611.72
Y	2402+47.04	69.00 R	611.79
Z	2402+52.03	74.01 R	611.74
AA	2402+40.93	74.00 R	(611.94)
BB	2402+47.03	74.00 R	(611.81)
CC	2402+46.98	94.50 R	(611.88)
DD	2402+43.14	0.00	612.39
EE	2402+49.16	0.00	612.33
FF	2402+79.80	68.51 R	612.33
GG	2402+79.78	74.51 R	612.37



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE


** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK


DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

	STATION	OFFSET	ELEVATION
A	2402+98.57	80.47 R	(611.73)
B	2402+98.58	74.47 R	611.76
C	2402+98.58	73.97 R	611.76
D	2402+98.59	68.97 R	611.71
E	2402+98.59	68.47 R	611.70
F	2403+00.68	65.48 R	611.86
G	2403+00.67	68.98 R	611.69
H	2403+00.66	73.98 R	611.74
I	2403+00.66	77.48 R	611.97
J	2403+07.66	73.99 R	611.77
K	2403+07.67	68.99 R	611.72
L	2403+12.67	69.00 R	611.74
M	2403+12.66	74.00 R	611.79
N	2403+12.65	80.50 R	(611.77)
O	2403+12.66	75.00 R	(611.80)
P	2403+18.66	75.00 R	(611.83)
Q	2403+06.45	39.07 R	611.82
R	2403+07.66	38.00 R	611.83
S	2403+12.66	34.78 R	611.86
T	2403+12.91	34.65 R	611.86
U	2403+18.21	32.84 R	(611.80)
V	2403+16.16	35.58 R	612.07
W	2403+12.66	37.12 R	611.84
X	2403+12.66	40.80 R	611.86
Y	2403+07.66	40.80 R	611.81
Z	2403+05.16	43.66 R	611.99
AA	2403+07.66	44.80 R	611.89
BB	2403+07.66	49.80 R	611.84
CC	2403+12.66	49.80 R	611.89
DD	2403+12.66	44.80 R	611.94
EE	2402+79.78	74.51 R	612.37
FF	2402+79.80	68.51 R	612.33
GG	2403+10.30	0.00	612.23
HH	2403+16.33	0.00	612.19



ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2415+77.25	84.95 L	(609.93)
B	2415+85.41	84.95 L	(609.49)
C	2415+85.41	79.95 L	609.73
D	2415+85.41	79.95 L	609.73
E	2415+85.41	74.95 L	609.69
F	2415+77.25	74.95 L	(609.95)
G	2415+72.25	74.95 L	(609.95)
H	2415+67.25	74.95 L	(609.85)
I	2415+67.25	66.00 L	(609.92)
J	2415+70.25	66.00 L	(609.82)
K	2415+70.25	62.00 L	(609.97)
L	2415+77.25	62.00 L	(609.71)
M	2415+72.25	69.95 L	609.90
N	2415+77.75	74.45 L	609.77
O	2415+77.75	74.95 L	609.77
P	2415+77.75	69.95 L	609.72
Q	2415+85.41	69.95 L	609.64
R	2415+96.41	69.95 L	608.87
S	2415+96.41	74.95 L	608.92
T	2416+03.00	84.75 L	(608.98)
U	2416+00.91	74.95 L	608.88
V	2416+03.00	75.38 L	608.88
W	2416+03.00	74.95 L	608.86
X	2416+03.00	69.95 L	608.81
Y	2416+03.00	69.37 L	608.79
Z	2416+00.91	69.95 L	608.83
AA	2416+00.91	66.02 L	609.00
BB	2415+85.23	47.87 L	609.60
CC	2415+90.23	47.87 L	609.55
DD	2415+85.23	42.87 L	609.55
EE	2415+90.23	42.87 L	609.50
FF	2415+92.32	39.36 L	609.60
GG	2415+90.23	37.87 L	609.45
HH	2415+90.73	35.74 L	609.41
II	2415+90.23	35.45 L	609.43
JJ	2415+85.23	33.32 L	609.46
KK	2415+84.72	33.17 L	609.48
LL	2415+85.23	35.51 L	609.48
MM	2415+85.23	37.87 L	609.50
NN	2415+80.98	34.53 L	609.82
OC	2415+77.25	32.25 L	(609.66)
PP	2415+84.57	0.00	610.29
QC	2415+90.57	0.00	610.30
RR	2416+17.25	68.84 L	609.47
SS	2416+17.25	74.85 L	609.48

	STATION	OFFSET	ELEVATION
A	2416+58.92	75.00 L	(609.66)
B	2416+57.17	75.00 L	(609.67)
C	2416+57.17	81.21 L	(609.84)
D	2416+43.58	73.70 L	609.62
E	2416+43.58	68.70 L	609.67
F	2416+39.58	68.70 L	609.62
G	2416+39.58	73.70 L	609.57
H	2416+35.79	78.81 L	609.40
I	2416+34.90	81.62 L	(608.83)
J	2416+34.58	73.70 L	609.22
K	2416+33.00	74.26 L	609.18
L	2416+33.00	73.70 L	609.20
M	2416+33.00	68.70 L	609.25
N	2416+33.00	68.26 L	609.27
O	2416+34.58	68.70 L	609.27
P	2416+34.58	64.90 L	609.57
Q	2416+47.59	53.58 L	609.90
R	2416+52.59	53.58 L	609.92
S	2416+47.59	49.58 L	609.88
T	2416+52.59	49.58 L	609.90
U	2416+43.54	44.59 L	610.06
V	2416+47.59	44.58 L	609.76
W	2416+47.03	43.00 L	609.75
X	2416+47.59	43.00 L	609.74
Y	2416+52.59	44.58 L	609.73
Z	2416+52.59	43.00 L	609.71
AA	2416+53.03	43.00 L	609.70
BB	2416+55.59	44.58 L	609.95
CC	2416+58.92	43.00 L	(609.68)
DD	2416+51.54	0.00	610.41
EE	2416+45.54	0.00	610.38
FF	2416+17.25	68.84 L	609.47
GG	2416+17.25	74.85 L	609.48

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

PROPOSED SIDE CURB


(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS


PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD



ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2415+73.41	73.89 R	(609.98)
B	2415+73.41	68.89 R	(609.95)
C	2415+78.41	68.89 R	609.98
D	2415+78.41	73.89 R	(610.00)
E	2415+85.41	73.89 R	609.50
F	2415+85.41	79.39 R	(609.87)
G	2415+85.41	84.39 R	(609.81)
H	2415+85.41	89.39 R	(609.79)
I	2415+90.41	89.39 R	(609.54)
J	2415+92.73	90.32 R	(608.76)
K	2415+90.41	84.39 R	609.74
L	2415+90.41	79.39 R	609.80
M	2415+90.41	73.89 R	609.43
N	2415+90.41	69.89 R	609.41
O	2415+85.41	64.89 R	609.45
P	2415+90.41	64.89 R	609.38
Q	2416+01.32	74.18 R	608.93
R	2416+02.12	69.89 R	608.58
S	2416+03.67	70.44 R	608.57
T	2416+03.71	69.89 R	608.56
U	2416+03.75	64.89 R	608.53
V	2416+03.75	64.44 R	608.52
W	2416+02.16	64.89 R	608.55
X	2416+02.16	61.18 R	608.83
Y	2415+84.91	47.41 R	609.82
Z	2415+89.91	47.41 R	609.77
AA	2415+84.91	42.41 R	609.80
BB	2415+89.91	42.41 R	609.75
CC	2415+92.43	39.00 R	609.82
DD	2415+89.91	37.41 R	609.72
EE	2415+90.41	35.89 R	609.68
FF	2415+89.91	35.63 R	609.70
GG	2415+84.91	37.41 R	609.77
HH	2415+84.91	33.77 R	609.74
II	2415+84.42	33.65 R	609.75
JJ	2415+84.91	35.41 R	609.76
KK	2415+81.50	34.77 R	609.02
LL	2415+72.33	38.58 R	(609.75)
MM	2415+84.57	0.00	610.29
NN	2415+90.57	0.00	610.30
OO	2416+17.25	64.93 R	608.81
PP	2416+17.25	70.93 R	608.72
QQ	2415+85.41	68.89 R	609.48



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS




 PROPOSED SIDEWALK

 DETECTABLE WARNINGS

 SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

	STATION	OFFSET	ELEVATION
A	2416+52.05	73.80 R	(609.79)
B	2416+49.79	73.80 R	(609.81)
C	2416+49.79	76.92 R	(609.78)
D	2416+49.79	70.92 R	609.74
E	2416+49.79	65.92 R	609.69
F	2416+44.79	65.92 R	609.64
G	2416+44.79	70.92 R	609.69
H	2416+32.89	77.89 R	(608.72)
I	2416+32.90	75.31 R	609.06
J	2416+29.25	71.37 R	608.69
K	2416+29.25	70.92 R	608.67
L	2416+30.83	70.92 R	608.69
M	2416+29.25	65.92 R	608.62
N	2416+29.25	65.36 R	608.60
O	2416+30.83	65.92 R	608.64
P	2416+30.96	61.92 R	608.83
Q	2416+44.79	48.69 R	609.99
R	2416+49.79	48.69 R	610.04
S	2416+44.79	43.69 R	610.04
T	2416+49.79	43.69 R	610.09
U	2416+52.05	43.09 R	(610.19)
V	2416+57.40	43.09 R	(610.15)
W	2416+49.79	38.69 R	609.92
X	2416+57.40	32.16 R	(609.97)
Y	2416+53.52	34.62 R	610.21
Z	2416+49.79	35.96 R	609.90
AA	2416+50.36	34.02 R	609.90
BB	2416+49.79	34.25 R	609.88
CC	2416+44.79	36.80 R	609.85
DD	2416+44.24	37.15 R	609.83
EE	2416+44.79	38.69 R	609.87
FF	2416+42.63	40.27 R	609.95
GG	2416+45.54	0.00	610.38
HH	2416+51.54	0.00	610.41
II	2416+17.25	64.93 R	608.81
JJ	2416+17.25	70.93 R	608.72



FILE NAME =
95212_Cermak-sht-Lombard02.dgn

```
USER NAME = j1robinson
```

DESIGNED - KB

REVISÉ -

REVISÉ -

REVISED	-
---------	---

PLOT SCALE = 10.0000' / in.

CHECKED	-	JIM
---------	---	-----

REVISED	-
---------	---

Default

SMART CORRIDOR

CERMAK ROAD / 22ND STREET & LOMBARD AVENUE

SCALE: 1" = 5'

SHEET

OF

SHEETS

STA.

TO :

F.A.U. RTE.	1453
----------------	------

SECTION


COUNTY

TOTAL SHEETS	SHEET NO.
-----------------	--------------

SHEETS	NO.
54	220

CONTRACT NO. 62F74

ILLINOIS		FED. AID PROJECT
----------	--	------------------



LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE

PROPOSED SIDEWALK

PROPOSED SIDE CURB

SC

TOP OF PROPOSED SIDE CURB

CLASS D PATCH

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 609.845
BENCHMARK : SOUTH EAST BOLT ON FIRE HYDRANT
LOCATION : ON NORTH WEST CORNER OF CERMAK RD. AND 61ST AVE.


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN

CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	22R
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				



LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE

PROPOSED SIDEWALK

PROPOSED SIDE CURB

SC

TOP OF PROPOSED SIDE CURB

CLASS D PATCH

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 609.845

BENCHMARK : SOUTH EAST BOLT ON FIRE HYDRANT


LOCATION : ON NORTH WEST CORNER OF CERMAK RD. AND 61ST AVE.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN

CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE: SHEET OF SHEETS STA. TO STA.



LEGEND

xx.xx'

()

EXISTING LENGTH

EXISTING ELEVATION/SLOPE

PROPOSED SIDEWALK

PROPOSED SIDE CURB

SC

TOP OF PROPOSED SIDE CURB

CLASS D PATCH

DETECTABLE WARNINGS

SIDEWALK REMOVAL REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 610.623

BENCHMARK : SE BOLT ON FIRE HYDRANT

LOCATION : NORTH WEST CORNER OF CERMAK AVE AND 60TH CT

FILE NAME :	USER NAME : lacymr	DESIGNED -	REVISED - ML 4/27/18
pw:\11084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\1083218\1083218-gh\1083218-gh.dgn		CHECKED -	REVISED -
Default	PLOT DATE : 4/30/2018	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN

CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)


SCALE:

SHEET OF SHEETS

STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	22T
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

ADA DETAILS FOR PHASE 1 PROJECTS



AUSTIN BOULEVARD

CERMAK ROAD



	STATION	OFFSET	ELEVATION
A	2429+17.18	79.98 L	(608.99)
B	2429+17.18	73.98 L	608.96
C	2429+12.68	74.84 L	(609.07)
D	2429+17.18	74.84 L	(608.95)
E	2429+17.18	68.98 L	609.01
F	2429+22.18	73.98 L	608.91
G	2429+22.18	68.98 L	608.96
H	2429+29.10	76.98 L	608.61
I	2429+30.68	79.98 L	(608.36)
J	2429+29.10	73.98 L	608.42
K	2429+30.68	74.43 L	608.39
L	2429+30.68	73.98 L	608.40
M	2429+29.10	68.98 L	608.47
N	2429+30.68	68.98 L	608.45
O	2429+30.68	68.42 L	608.46
P	2429+29.10	65.65 L	608.71
Q	2429+22.18	56.01 L	609.06
R	2429+17.18	56.01 L	609.13
S	2429+17.18	51.01 L	609.11
T	2429+22.18	51.01 L	609.04
U	2429+24.68	50.78 L	608.99
V	2429+23.97	47.81 L	608.81
W	2429+22.18	48.37 L	608.86
X	2429+22.18	46.39 L	608.84
Y	2429+17.18	48.37 L	608.93
Z	2429+17.18	45.52 L	608.92
AA	2429+17.18	43.84 L	608.90
BB	2429+16.18	43.52 L	608.91
CC	2429+13.68	44.58 L	609.15
DD	2429+02.18	42.75 L	(608.90)
EE	2429+12.68	51.01 L	(609.15)
FF	2429+18.40	0.00	609.59
GG	2429+26.41	0.00	609.57
HH	2429+57.18	73.58 L	609.04
II	2429+57.18	67.58 L	609.07

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS


	STATION	OFFSET	ELEVATION
A	2429+97.18	75.00 L	(608.86)
B	2429+97.18	72.21 L	608.85
C	2429+97.18	67.21 L	608.82
D	2429+92.18	67.21 L	608.79
E	2429+92.18	72.21 L	608.82
F	2429+84.26	72.21 L	608.49
G	2429+84.26	75.39 L	608.69
H	2429+82.68	80.21 L	(608.42)
I	2429+82.68	72.76 L	608.46
J	2429+82.68	72.21 L	608.47
K	2429+84.26	67.21 L	608.52
L	2429+82.68	67.21 L	608.50
M	2429+82.68	66.76 L	608.51
N	2429+84.40	63.21 L	608.79
O	2429+92.18	54.65 L	609.04
P	2429+97.18	54.65 L	609.09
Q	2429+97.18	49.65 L	609.14
R	2429+97.18	44.65 L	609.10
S	2429+92.18	49.65 L	609.09
T	2429+90.18	47.27 L	609.13
U	2429+90.31	44.43 L	608.99
V	2429+92.18	44.65 L	609.05
W	2429+92.18	42.28 L	609.03
X	2429+97.18	39.86 L	609.08
Y	2429+97.18	37.88 L	609.06
Z	2429+97.81	37.44 L	609.08
AA	2430+08.58	32.45 L	(609.26)
BB	2430+01.99	36.74 L	609.40
CC	2429+94.97	0.00	609.73
DD	2429+86.94	0.00	609.68
EE	2429+57.18	67.58 L	609.07
FF	2429+57.18	67.58 L	609.07

AUSTIN BOULEVARD

CERMAK ROAD




ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2429+16.18	74.44 R	(608.87)
B	2429+25.60	74.44 R	(608.46)
C	2429+25.60	71.79 R	608.43
D	2429+25.60	66.79 R	608.48
E	2429+30.60	66.79 R	608.43
F	2429+30.60	71.79 R	608.38
G	2429+35.60	74.79 R	608.30
H	2429+25.60	76.79 R	(608.56)
I	2429+37.18	76.79 R	(608.03)
J	2429+35.60	71.79 R	608.11
K	2429+37.18	72.26 R	608.08
L	2429+37.18	71.79 R	608.09
M	2429+37.18	66.79 R	608.11
N	2429+37.18	66.26 R	608.13
O	2429+35.60	66.79 R	608.13
P	2429+35.55	62.91 R	608.40
Q	2429+26.18	51.50 R	609.00
R	2429+21.18	51.50 R	609.07
S	2429+21.18	46.50 R	609.04
T	2429+26.18	46.50 R	608.97
U	2429+21.18	41.50 R	609.01
V	2429+28.18	43.76 R	608.98
W	2429+26.18	41.50 R	608.94
X	2429+28.55	41.73 R	608.79
Y	2429+26.18	39.27 R	608.92
Z	2429+21.18	37.26 R	608.99
AA	2429+21.18	35.36 R	608.97
BB	2429+20.18	34.73 R	609.00
CC	2429+17.98	35.30 R	609.28
DD	2429+02.69	29.75 R	(608.88)
EE	2429+18.40	0.00	609.59
FF	2429+26.41	0.00	609.57
GG	2429+57.18	65.93 R	608.96
HH	2429+57.18	71.93 R	608.92

	STATION	OFFSET	ELEVATION
A	2429+90.03	79.63 R	(608.77)
B	2429+90.03	74.08 R	(608.61)
C	2429+97.46	74.08 R	(608.76)
D	2429+90.00	71.07 R	608.55
E	2429+90.00	66.07 R	608.58
F	2429+85.00	66.07 R	608.51
G	2429+85.00	71.07 R	608.48
H	2429+77.18	79.63 R	607.87
I	2429+78.76	74.07 R	608.21
J	2429+78.76	71.07 R	608.04
K	2429+77.18	71.60 R	608.01
L	2429+77.18	71.07 R	608.02
M	2429+77.18	71.07 R	608.02
N	2429+77.18	65.60 R	608.07
O	2429+78.76	66.07 R	608.07
P	2429+78.76	61.72 R	608.39
Q	2429+85.00	57.43 R	608.78
R	2429+90.00	57.43 R	608.85
S	2429+90.00	52.43 R	608.82
T	2429+85.00	52.43 R	608.75
U	2429+90.00	47.43 R	608.74
V	2429+93.41	43.22 R	609.00
W	2430+07.96	41.25 R	(608.74)
X	2429+91.78	41.99 R	608.73
Y	2429+90.00	42.58 R	608.70
Z	2429+90.00	44.29 R	608.72
AA	2429+85.00	45.38 R	608.65
BB	2429+85.00	47.43 R	608.67
CC	2429+83.40	46.76 R	608.62
DD	2429+83.35	49.08 R	608.75
EE	2429+94.97	0.00	609.73
FF	2429+86.94	0.00	609.68
GG	2429+57.18	65.93 R	608.96
HH	2429+57.18	71.93 R	608.92



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



PROPOSED SIDEWALK



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & AUSTIN BOULEVARD

SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.
----------------	-------	----	--------	------	---------

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	22W
		CONTRACT NO. 62F74		
ILLINOIS		FED. AID PROJECT		

FILE NAME =
95212_Cermak-sht-Austin02.dgn

USER NAME	=	j1robinson
-----------	---	------------

DESIGNED - KBH

REVISÉ -


PLOT SCALE = 10.0000 ' /

CHECKED	-	JIR
---------	---	-----

REVISÉ -

Default

		CONTRACT NO. 02F74	
ILLINOIS	FED. AID PROJECT		



LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE



PROPOSED SIDEWALK



PROPOSED SIDE CURB

SC

TOP OF PROPOSED
SIDE CURB



CLASS D PATCH



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 610.54

BENCHMARK : NORTH WEST BOLT ON FIRE HYDRANT

LOCATION : ON NORTH WEST CORNER OF CERMAK RD. AND
59TH AVE.


FILE NAME =	USER NAME = Bilgramiso	DESIGNED -	REVIS
pw\11084EBIDINTEG\Illinois.gov\PI\DOT\Documents\DOT Offices\District 1\Projects\DI03218\Bilgramiso\Design\DI03218-sh\Default2.dgn		DATE	REVIS
		CHECKED -	REVIS
Default		DATE	REVIS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


SIDEWALK DETAIL PLAN
CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	222
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				



LEGEND xx.xx' EXISTING LENGTH () EXISTING ELEVATION/SLOPE



CERMAK RD

58th CT

58TH CT. NORTH LEG

LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE



PROPOSED SIDEWALK



PROPOSED SIDE CURB

SC

TOP OF PROPOSED
SIDE CURB



CLASS D PATCH



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 609.37

BENCHMARK : NW BOLT FIRE HYDRANT

LOCATION : NORTH WEST CORNER OF CERMAK AVE AND 58TH CT

FILE NAME =	USER NAME = lacymr	DESIGNED -	REVISD -
pw\11084EBID\TEG\Illinois.gov\PIDOT\Documents\IDOT Offices\District 1\Projects\DI03218\BROWN\Design\QIP3218-sh\Default3.dgn		DATE -	REVISD -
Default		DATE -	REVISD -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN
CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE: SHEET OF SHEETS STA. TO STA.


F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	23A
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2442+57.60	75.00 L	(607.74)
B	2442+60.73	75.00 L	(607.70)
C	2442+60.73	78.12 L	(607.73)
D	2442+60.71	71.62 L	607.74
E	2442+60.71	66.62 L	607.79
F	2442+65.71	66.62 L	607.74
G	2442+65.71	71.62 L	607.69
H	2442+76.67	78.12 L	(607.03)
I	2442+75.08	76.31 L	607.45
J	2442+75.08	71.62 L	607.35
K	2442+76.67	72.09 L	607.31
L	2442+76.67	71.62 L	607.33
M	2442+76.51	66.62 L	607.40
N	2442+76.46	66.10 L	607.42
O	2442+74.92	66.62 L	607.42
P	2442+74.55	63.04 L	607.70
Q	2442+92.92	71.82 L	608.01
R	2442+92.92	65.82 L	608.03
S	2442+62.48	55.48 L	607.86
T	2442+67.48	55.48 L	607.84
U	2442+62.48	50.48 L	607.91
V	2442+67.48	50.48 L	607.89
W	2442+57.60	43.00 L	(607.77)
X	2442+59.48	44.58 L	608.05
Y	2442+62.48	45.48 L	607.83
Z	2442+62.48	44.58 L	607.82
AA	2442+61.96	43.00 L	607.83
BB	2442+62.48	43.00 L	607.81
CC	2442+67.48	43.77 L	607.85
DD	2442+67.97	43.97 L	607.86
EE	2442+67.48	45.48 L	607.87
FF	2442+70.50	47.51 L	608.07
GG	2442+61.24	0.00	608.68
HH	2442+67.24	0.00	608.67

	STATION	OFFSET	ELEVATION
A	2443+32.92	75.00 L	(608.07)
B	2443+25.92	75.00 L	(607.93)
C	2443+25.92	66.00 L	607.86
D	2443+25.92	71.00 L	607.81
E	2443+20.92	66.00 L	607.81
F	2443+20.92	71.00 L	607.76
G	2443+12.50	74.33 L	607.24
H	2443+10.92	75.00 L	(606.97)
I	2443+12.50	71.00 L	607.18
J	2443+10.92	71.53 L	607.13
K	2443+10.92	71.00 L	607.16
L	2443+11.26	66.00 L	607.22
M	2443+11.30	65.52 L	607.24
N	2443+12.85	66.00 L	607.24
O	2442+92.92	65.82 L	608.03
P	2442+92.92	71.82 L	608.01
Q	2443+13.23	61.30 L	607.62
R	2443+25.92	52.07 L	608.26
S	2443+20.92	52.07 L	608.21
T	2443+25.92	47.07 L	608.21
U	2443+20.92	47.07 L	608.16
V	2443+25.92	42.07 L	608.11
W	2443+19.11	44.17 L	608.22
X	2443+20.92	42.07 L	608.04
Y	2443+20.42	40.33 L	608.00
Z	2443+20.92	39.85 L	608.02
AA	2443+25.92	37.94 L	608.09
BB	2443+25.92	36.08 L	608.07
CC	2443+26.42	35.79 L	608.09
DD	2443+29.09	36.19 L	608.38
EE	2443+32.47	33.21 L	(608.17)
FF	2443+20.44	0.00	608.72
GG	2443+26.44	0.00	608.73
HH	2443+12.85	71.00 L	607.19



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE


■ PROPOSED SIDEWALK

■ DETECTABLE WARNINGS


■ SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS


ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2442+53.75	75.00 R	(607.97)
B	2442+61.14	75.00 R	(607.90)
C	2442+61.14	81.94 R	(607.89)
D	2442+61.14	68.38 R	607.89
E	2442+61.14	73.38 R	607.84
F	2442+66.14	68.38 R	607.84
G	2442+66.14	73.38 R	607.79
H	2442+76.92	81.94 R	(606.85)
I	2442+75.33	76.38 R	607.50
J	2442+75.33	73.38 R	607.38
K	2442+76.92	73.98 R	607.33
L	2442+76.92	73.38 R	607.36
M	2442+76.92	68.38 R	607.43
N	2442+76.92	67.97 R	607.45
O	2442+75.33	68.38 R	607.45
P	2442+75.33	62.90 R	607.80
Q	2442+92.92	68.93 R	607.93
R	2442+92.92	74.94 R	607.82
S	2442+61.14	49.64 R	608.05
T	2442+66.14	49.64 R	608.00
U	2442+61.14	44.64 R	608.10
V	2442+66.14	44.64 R	608.05
W	2442+61.14	39.64 R	608.06
X	2442+69.14	42.95 R	608.10
Y	2442+66.14	39.64 R	608.01
Z	2442+66.61	37.92 R	607.97
AA	2442+66.14	37.51 R	607.99
BB	2442+61.14	35.83 R	608.05
CC	2442+61.14	34.00 R	608.03
DD	2442+60.68	33.74 R	608.04
EE	2442+57.67	34.03 R	608.30
FF	2442+53.75	31.01 R	(608.15)
GG	2442+61.24	0.00	608.68
HH	2442+67.24	0.00	608.67



	STATION	OFFSET	ELEVATION
A	2443+32.43	75.00 R	(606.64)
B	2443+25.92	75.61 R	(607.69)
C	2443+25.92	81.03 R	(607.11)
D	2443+25.92	70.61 R	607.74
E	2443+20.97	70.61 R	607.69
F	2443+20.97	75.61 R	607.64
G	2443+12.25	73.61 R	607.27
H	2443+10.67	81.03 R	(607.06)
I	2443+12.25	75.61 R	607.16
J	2443+10.67	76.01 R	607.12
K	2443+10.67	75.61 R	607.14
L	2443+12.25	70.61 R	607.23
M	2443+10.67	70.61 R	607.21
N	2443+10.67	70.00 R	607.23
O	2443+12.25	65.61 R	607.60
P	2442+92.92	68.93 R	607.93
Q	2442+92.92	74.94 R	607.82
R	2443+20.97	54.26 R	607.80
S	2443+25.97	54.26 R	607.84
T	2443+20.97	49.26 R	607.85
U	2443+25.97	49.26 R	607.89
V	2443+32.43	41.50 R	(607.84)
W	2443+29.36	43.08 R	608.07
X	2443+25.97	44.26 R	607.86
Y	2443+25.97	43.10 R	607.84
Z	2443+26.47	41.50 R	607.83
AA	2443+25.97	41.52 R	607.82
BB	2443+20.97	44.26 R	607.82
CC	2443+20.97	42.55 R	607.78
DD	2443+20.47	42.75 R	607.77
EE	2443+17.94	46.03 R	607.97
FF	2443+20.44	0.00	608.72
GG	2443+26.44	0.00	608.73
HH	*N/A	*N/A ***	0.00



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB


(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK


DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD



				LEGEND xx.xx' EXISTING LENGTH () EXISTING ELEVATION/SLOPE PROPOSED SIDEWALK PROPOSED SIDE CURB SC TOP OF PROPOSED SIDE CURB CLASS D PATCH DETECTABLE WARNINGS SIDEWALK REMOVAL REPLACE W/TOPSOIL & SOD				REFERENCE BENCHMARK ELEV 608.80 BENCHMARK : ARROW POINTS TO NORTH WESTERNLY LOWER FLANGE BOLT OF HYDRANT LOCATION : ON NORTH WEST CORNER OF CERMAK RD. AND 57TH CT.											
FILE NAME = pw:\IL04EBID\INTEG\Illinois.gov\FWIDOT\Documents\DOT Offices\District 1\Projects\0103218-gh\Design\0103218-gh\Default		USER NAME = Bilgremisa		DESIGNED - --- --/--/----		REVISED -		REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION SIDEWALK DETAIL PLAN CERMAK RD. – IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.) SCALE: SHEET OF SHEETS STA. TO STA.				F.A.U. RTE. 1453	SECTION (78-1&78-3)RS-2		COUNTY COOK	TOTAL SHEETS 54	SHEET NO. 23F
Default		PLOT SCALE = 10.0000 ' / in.		CHECKED -		REVISED -		CONTRACT NO. 62TF4											
		PLOT DATE = 4/30/2018		DATE		REVISED -													

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2449+19.35	43.00 L	(607.54)
B	2449+29.35	43.03 L	607.52
C	2449+29.85	43.07 L	607.52
D	2449+34.85	44.29 L	607.50
E	2449+35.33	44.50 L	607.49
F	2449+26.35	44.58 L	607.74
G	2449+29.85	44.66 L	607.53
H	2449+29.85	46.02 L	607.55
I	2449+34.85	46.02 L	607.50
J	2449+37.85	47.86 L	607.56
K	2449+29.85	50.02 L	607.57
L	2449+34.85	50.02 L	607.52
M	2449+29.85	55.02 L	607.59
N	2449+34.85	55.02 L	607.54
O	2449+45.35	69.25 L	606.66
P	2449+45.35	69.75 L	606.66
Q	2449+45.35	74.75 L	606.64
R	2449+45.35	75.25 L	606.64
S	2449+39.78	83.73 L	(606.41)
T	2449+42.56	78.25 L	606.82
U	2449+43.77	74.75 L	606.64
V	2449+43.77	69.75 L	606.66
W	2449+43.77	66.25 L	606.89
X	2449+34.85	69.75 L	607.11
Y	2449+34.85	74.75 L	607.13
Z	2449+29.85	74.75 L	(607.20)
AA	2449+29.85	69.75 L	607.18
BB	2449+19.35	74.75 L	(607.53)
CC	2449+29.85	82.68 L	(607.36)
DD	2449+62.85	75.41 L	607.18
EE	2449+62.85	69.41 L	607.19
FF	2449+30.04	0.00	(608.15)
GG	2449+36.04	0.00	(608.17)


LEGEND

- (XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE


- PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

	STATION	OFFSET	ELEVATION
A	2449+83.53	82.80 L	(606.38)
B	2449+78.35	75.54 L	606.60
C	2449+78.35	75.30 L	606.60
D	2449+78.35	70.30 L	606.65
E	2449+78.35	69.54 L	606.66
F	2449+82.62	78.80 L	606.69
G	2449+80.12	75.30 L	606.60
H	2449+80.12	70.30 L	606.65
I	2449+79.93	66.80 L	606.90
J	2449+89.47	75.30 L	607.15
K	2449+89.47	70.30 L	607.10
L	2449+94.47	75.30 L	(607.20)
M	2449+94.47	70.30 L	607.15
N	2449+94.47	81.88 L	(607.30)
O	2449+97.21	75.00 L	607.24
P	2449+88.64	38.14 L	607.51
Q	2449+89.21	37.65 L	607.52
R	2449+94.21	34.29 L	607.57
S	2449+94.71	34.03 L	607.57
T	2449+86.21	42.94 L	607.70
U	2449+89.21	39.75 L	607.52
V	2449+94.21	39.75 L	607.59
W	2449+94.21	36.10 L	607.57
X	2449+97.71	34.40 L	607.83
Y	2449+89.21	43.75 L	607.56
Z	2449+89.21	48.75 L	607.58
AA	2449+94.21	43.75 L	607.63
BB	2449+94.21	48.75 L	607.65
CC	2449+97.21	46.78 L	607.64
DD	2450+08.35	46.78 L	(607.56)
EE	2450+08.35	30.75 L	(607.67)
FF	2449+62.85	69.41 L	607.19
GG	2449+62.85	75.41 L	607.18
HH	2449+89.30	0.00	608.20
II	2449+95.30	0.00	608.16




ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2449+26.51	31.61 R	(607.57)
B	2449+30.57	33.13 R	607.53
C	2449+31.07	33.37 R	607.52
D	2449+36.07	36.53 R	607.47
E	2449+36.64	36.98 R	607.45
F	2449+27.57	33.61 R	607.76
G	2449+31.07	35.15 R	607.52
H	2449+31.07	38.58 R	607.54
I	2449+36.07	38.58 R	607.47
J	2449+39.57	42.29 R	607.56
K	2449+31.07	44.58 R	607.44
L	2449+36.07	44.58 R	607.39
M	2449+31.07	49.58 R	607.39
N	2449+36.07	49.58 R	607.34
O	2449+47.94	68.13 R	606.74
P	2449+47.99	68.63 R	606.74
Q	2449+48.33	73.63 R	606.71
R	2449+47.95	74.13 R	606.69
S	2449+43.32	80.14 R	(606.51)
T	2449+46.02	65.13 R	606.97
U	2449+46.34	68.63 R	606.74
V	2449+46.34	73.63 R	606.71
W	2449+43.64	77.13 R	606.78
X	2449+35.07	73.63 R	607.40
Y	2449+30.07	73.63 R	(607.45)
Z	2449+35.07	68.63 R	607.35
AA	2449+30.07	68.63 R	607.40
BB	2449+30.10	74.25 R	(607.45)
CC	2449+27.07	74.25 R	(607.41)
DD	2449+30.10	79.18 R	(607.35)
EE	2449+62.85	73.98 R	607.16
FF	2449+62.85	67.98 R	607.23
GG	2449+30.04	0.00	(608.15)
HH	2449+36.04	0.00	(608.17)

	STATION	OFFSET	ELEVATION
A	2449+84.92	82.70 R	(606.54)
B	2449+74.26	73.87 R	606.76
C	2449+74.38	72.37 R	606.77
D	2449+74.70	68.37 R	606.80
E	2449+74.74	67.87 R	606.80
F	2449+76.57	64.87 R	607.03
G	2449+76.29	68.37 R	606.80
H	2449+76.29	72.37 R	606.77
I	2449+75.97	72.37 R	606.77
J	2449+77.82	76.11 R	607.05
K	2449+80.29	72.37 R	607.03
L	2449+80.29	68.37 R	606.99
M	2449+95.52	72.37 R	(607.08)
N	2449+95.52	68.37 R	607.02
O	2449+95.52	74.37 R	(607.09)
P	2449+90.02	41.72 R	607.18
Q	2449+90.52	41.68 R	607.20
R	2449+95.52	41.73 R	607.18
S	2449+96.02	41.74 R	607.18
T	2450+12.27	42.13 R	(607.15)
U	2449+99.02	43.40 R	607.37
V	2449+95.52	43.31 R	607.18
W	2449+90.52	43.31 R	607.20
X	2449+87.02	43.98 R	607.32
Y	2449+90.52	47.31 R	607.24
Z	2449+90.52	52.31 R	607.26
AA	2449+95.52	47.31 R	607.22
BB	2449+95.52	52.31 R	607.24
CC	2449+97.73	50.04 R	(607.16)
DD	2449+62.85	73.98 R	607.16
EE	2449+62.85	67.98 R	607.23
FF	2449+89.30	0.00	608.20
GG	2449+95.30	0.00	608.16
HH	2449+95.52	81.38 R	(607.21)
II	2450+12.23	47.81 R	(607.20)
JJ	2449+90.52	68.37 R	607.01



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE


** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

ADA DETAILS FOR PHASE 1 PROJECTS




	STATION	OFFSET	ELEVATION
A	2455+78.41	75.07 L	(606.91)
B	2455+87.94	45.23 L	607.11
C	2455+92.94	45.23 L	607.14
D	2455+87.94	40.23 L	607.16
E	2455+92.94	40.23 L	607.19
F	2455+87.94	35.23 L	607.14
G	2455+78.41	31.25 L	(607.07)
H	2455+84.94	33.04 L	607.32
I	2455+87.94	33.57 L	607.12
J	2455+87.44	31.84 L	607.09
K	2455+87.94	31.95 L	607.10
L	2455+92.94	35.23 L	607.17
M	2455+92.94	33.51 L	607.15
N	2455+93.44	33.72 L	607.17
O	2455+96.35	37.02 L	607.46
P	2455+87.38	0.00	607.68
Q	2455+93.38	0.00	607.67
R	2455+98.96	70.67 L	606.97
S	2455+98.94	65.67 L	606.92
T	2456+03.94	65.65 L	606.87
U	2456+03.96	70.65 L	606.92
V	2456+11.56	74.96 L	(606.46)
W	2456+09.97	74.13 L	606.80
X	2456+11.54	71.13 L	606.48
Y	2456+11.54	70.63 L	606.49
Z	2456+09.96	70.63 L	606.51
AA	2456+11.53	65.63 L	606.54
BB	2456+11.52	65.13 L	606.56
CC	2456+09.94	65.63 L	606.56
DD	2456+09.93	61.31 L	606.90
EE	2456+32.03	71.07 L	607.02
FF	2456+32.01	65.07 L	607.09
GG	2455+99.06	75.00 L	(607.04)

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



	STATION	OFFSET	ELEVATION
A	2456+70.56	73.47 L	(606.74)
B	2456+59.56	57.41 L	606.81
C	2456+64.56	57.41 L	606.86
D	2456+59.56	52.41 L	606.86
E	2456+64.56	52.41 L	606.91
F	2456+64.56	47.41 L	606.80
G	2456+70.56	43.75 L	(606.74)
H	2456+67.56	45.33 L	606.99
I	2456+64.61	43.90 L	606.76
J	2456+64.56	43.91 L	606.76
K	2456+65.96	0.00	607.61
L	2456+59.96	0.00	607.59
M	2456+64.56	45.51 L	606.78
N	2456+59.56	45.58 L	606.71
O	2456+58.53	46.19 L	606.67
P	2456+59.56	47.41 L	606.73
Q	2456+56.56	50.01 L	606.89
R	2456+64.56	70.48 L	606.67
S	2456+64.56	65.48 L	606.62
T	2456+59.56	65.50 L	606.57
U	2456+59.58	70.50 L	606.62
V	2456+53.33	61.41 L	606.65
W	2456+53.35	65.52 L	606.35
X	2456+51.76	65.02 L	606.34
Y	2456+51.76	65.52 L	606.33
Z	2456+51.78	70.52 L	606.28
AA	2456+51.78	71.02 L	606.26
BB	2456+53.36	70.52 L	606.30
CC	2456+51.80	77.52 L	(606.20)
DD	2456+53.37	73.52 L	606.49
EE	2456+32.03	71.07 L	607.02
FF	2456+32.01	65.07 L	607.09

FILE NAME = 95212_Cermak-sh1-Central01.dgn
Default

USER NAME = jrobinson
PLOT SCALE = 10.0000" / 1in.
PLOT DATE = 3/26/2018

DESIGNED - KBH
DRAWN - KBH
CHECKED - JIR
DATE - 1/24/2018

REVISED -
REVISED -
REVISED -
REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & CENTRAL AVENUE

SCALE: 1" = 5' SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	23K
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

ADA DETAILS FOR PHASE 1 PROJECTS




	STATION	OFFSET	ELEVATION
A	2455+83.24	74.46 R	(606.83)
B	2455+87.81	53.48 R	606.89
C	2455+92.81	53.48 R	606.84
D	2455+87.81	48.48 R	606.84
E	2455+92.81	48.48 R	606.79
F	2455+84.81	43.33 R	607.01
G	2455+83.24	41.75 R	(606.78)
H	2455+87.81	43.33 R	606.77
I	2455+87.31	41.75 R	606.76
J	2455+87.81	41.75 R	606.75
K	2455+92.81	41.89 R	606.73
L	2455+93.31	41.95 R	606.72
M	2455+92.81	43.48 R	606.75
N	2455+95.81	44.08 R	606.97
O	2455+87.38	0.00	607.68
P	2455+93.38	0.00	607.67
Q	2455+98.81	66.37 R	606.73
R	2455+98.81	71.37 R	606.68
S	2456+03.81	71.39 R	606.63
T	2456+03.81	66.39 R	606.68
U	2456+10.75	62.96 R	606.73
V	2456+10.76	66.41 R	606.45
W	2456+12.34	65.89 R	606.45
X	2456+12.34	66.41 R	606.43
Y	2456+10.74	71.41 R	606.39
Z	2456+12.32	71.41 R	606.37
AA	2456+12.32	71.89 R	606.36
BB	2456+12.31	74.56 R	606.34
CC	2456+10.73	74.41 R	606.59
DD	2456+31.59	65.67 R	607.01
EE	2456+31.57	71.67 R	606.95

CENTRAL AVENUE

LEGEND


- (XX.XX) EXISTING LENGTH/ELEVATION
- == PROPOSED SIDE CURB
- (%) EXISTING SLOPE
- PROPOSED SIDEWALK
- DETECTABLE WARNINGS
- SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD
- ** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



CENTRAL AVENUE

	STATION	OFFSET	ELEVATION
A	2456+64.56	79.83 R	(606.94)
B	2456+64.56	73.83 R	(606.81)
C	2456+74.37	73.86 R	(606.95)
D	2456+66.89	49.35 R	607.03
E	2456+61.89	49.35 R	606.98
F	2456+66.89	45.35 R	607.01
G	2456+61.89	45.35 R	606.96
H	2456+66.89	42.48 R	606.94
I	2456+66.89	37.90 R	606.93
J	2456+70.39	35.71 R	607.18
K	2456+74.37	32.24 R	(607.06)
L	2456+67.06	35.85 R	606.91
M	2456+66.89	35.97 R	606.91
N	2456+65.96	0.00	607.61
O	2456+59.96	0.00	607.59
P	2456+61.89	40.14 R	606.87
Q	2456+61.21	40.86 R	606.86
R	2456+61.89	42.48 R	606.89
S	2456+59.89	45.02 R	607.06
T	2456+31.57	71.67 R	606.95
U	2456+65.28	65.93 R	606.68
V	2456+65.28	70.93 R	606.73
W	2456+60.28	65.93 R	606.63
X	2456+60.28	70.91 R	606.68
Y	2456+54.33	74.75 R	606.57
Z	2456+54.37	62.90 R	606.40
AA	2456+54.36	65.90 R	606.22
BB	2456+52.77	65.41 R	606.18
CC	2456+52.77	65.89 R	606.20
DD	2456+52.76	70.89 R	606.26
EE	2456+52.76	71.42 R	606.28
FF	2456+54.34	70.90 R	606.28
GG	2456+52.73	79.79 R	606.27
HH	2456+31.59	65.67 R	607.01





LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE

PROPOSED SIDEWALK

PROPOSED SIDE CURB

TOP OF PROPOSED SIDE CURB

CLASS D PATCH

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 609.050
BENCHMARK : NE BOLT FIRE HYDRANT
LOCATION : NORTH WEST CORNER OF CERMAK AVE AND 55TH AVE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN


CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE: SHEET OF SHEETS STA. TO STA.

FILE NAME :	USER NAME : Bilgramiso	DESIGNED : --- --/--/----	REVISED : --- --/--/----
pw:\11084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI03218\BROWN\Design\Q103218-sh\1\default3.dgn			REVISED : --- --/--/----
Default	PLOT SCALE = 10.0000' / in.	CHECKED : --- --/--/----	REVISED : --- --/--/----
	PLOT DATE = 4/30/2018	DATE : --- --/--/----	REVISED : --- --/--/----


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	23M
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2469+26.91	54.94 L	(606.06)
B	2469+36.91	49.94 L	606.20
C	2469+36.91	44.94 L	606.25
D	2469+41.91	44.94 L	606.20
E	2469+41.91	49.94 L	606.15
F	2469+51.75	54.54 L	605.11
G	2469+49.63	52.94 L	606.02
H	2469+50.94	51.88 L	605.81
I	2469+48.45	49.94 L	605.87
J	2469+50.18	49.94 L	605.85
K	2469+47.52	44.94 L	605.92
L	2469+45.61	44.94 L	605.94
M	2469+46.54	43.50 L	605.95
N	2469+70.57	53.42 L	606.01
O	2469+70.57	45.40 L	606.17
P	2469+42.76	41.41 L	606.36
Q	2469+41.91	40.53 L	606.27
R	2469+42.37	38.78 L	606.22
S	2469+41.91	38.36 L	606.25
T	2469+36.91	40.53 L	606.32
U	2469+36.91	36.52 L	606.30
V	2469+36.91	34.65 L	606.28
W	2469+36.45	34.37 L	606.30
X	2469+33.91	34.80 L	606.57
Y	2469+26.91	32.53 L	(606.31)
Z	2469+37.09	0.00	607.21
AA	2469+43.09	0.00	607.17
BB	2469+45.61	49.94 L	605.89

	STATION	OFFSET	ELEVATION
A	2470+14.52	59.80 L	(605.98)
B	2470+04.52	53.80 L	606.19
C	2470+04.52	48.80 L	606.24
D	2469+99.52	48.80 L	606.19
E	2469+99.52	53.80 L	606.14
F	2469+94.65	53.80 L	605.79
G	2469+89.06	59.53 L	(605.45)
H	2469+91.28	56.80 L	605.84
I	2469+90.17	54.97 L	605.69
J	2469+90.57	53.80 L	605.75
K	2469+92.25	53.80 L	605.77
L	2469+94.65	48.80 L	605.84
M	2469+92.83	48.80 L	605.82
N	2469+93.76	47.23 L	605.86
O	2469+70.57	53.42 L	606.01
P	2469+70.57	45.40 L	606.17
Q	2469+97.38	44.87 L	606.22
R	2469+99.52	42.49 L	606.16
S	2469+99.07	40.71 L	606.12
T	2469+99.52	40.29 L	606.14
U	2470+04.52	42.49 L	606.21
V	2470+04.52	38.35 L	606.19
W	2470+04.52	35.47 L	606.17
X	2470+04.97	36.19 L	606.19
Y	2470+08.45	36.10 L	606.48
Z	2470+14.12	32.34 L	(606.37)
AA	2469+98.17	0.00	606.83
BB	2470+04.17	0.00	606.82



LEGEND


(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



ADA DETAILS FOR PHASE 1 PROJECTS




	STATION	OFFSET	ELEVATION
A	2469+32.24	67.99 R	(606.52)
B	2469+43.24	53.99 R	606.63
C	2469+43.24	58.99 R	606.58
D	2469+43.24	58.99 R	606.58
E	2469+43.24	53.99 R	606.63
F	2469+51.25	53.99 R	606.06
G	2469+51.25	58.99 R	606.03
H	2469+60.01	67.99 R	(606.93)
I	2469+58.35	62.99 R	606.22
J	2469+56.25	58.99 R	605.98
K	2469+59.46	59.49 R	605.94
L	2469+59.36	58.99 R	605.95
M	2469+57.94	53.99 R	605.97
N	2469+57.76	53.50 R	605.98
O	2469+70.57	59.42 R	606.15
P	2469+70.57	53.42 R	606.22
Q	2469+56.25	53.99 R	605.99
R	2469+54.92	50.99 R	606.20
S	2469+38.24	47.97 R	606.78
T	2469+43.24	47.97 R	606.73
U	2469+38.24	42.97 R	606.73
V	2469+43.24	42.97 R	606.68
W	2469+46.24	40.16 R	606.75
X	2469+43.24	37.97 R	606.58
Y	2469+43.77	36.42 R	606.54
Z	2469+43.24	36.10 R	606.56
AA	2469+38.24	37.97 R	606.62
BB	2469+38.24	35.30 R	606.60
CC	2469+38.24	33.58 R	606.58
DD	2469+37.71	33.37 R	606.60
EE	2469+32.58	31.82 R	(606.64)
FF	2469+34.87	34.06 R	606.89
GG	2469+37.09	0.00	607.21
HH	2469+43.09	0.00	607.17
II	2469+57.74	58.99 R	605.97

LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE


PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS




	STATION	OFFSET	ELEVATION
A	2470+07.78	66.87 R	(606.21)
B	2470+02.78	58.80 R	606.05
C	2470+02.78	53.80 R	606.10
D	2469+97.78	53.80 R	606.05
E	2469+97.78	58.80 R	606.00
F	2469+88.07	66.87 R	(605.71)
G	2469+89.97	61.80 R	605.97
H	2469+92.16	58.80 R	605.83
I	2469+90.53	58.80 R	605.81
J	2469+88.80	59.31 R	605.76
K	2469+88.91	58.80 R	605.79
L	2469+70.57	53.42 R	606.22
M	2469+70.57	59.42 R	606.15
N	2469+90.45	53.80 R	605.84
O	2469+90.65	53.30 R	605.86
P	2469+92.16	53.80 R	605.86
Q	2469+93.57	50.85 R	606.03
R	2470+02.78	44.84 R	606.54
S	2469+97.78	44.84 R	606.49
T	2469+97.21	43.10 R	606.44
U	2469+97.78	42.51 R	606.47
V	2470+02.78	40.25 R	606.51
W	2470+02.78	38.30 R	606.49
X	2470+03.33	37.93 R	606.52
Y	2470+07.08	35.78 R	(606.54)
Z	2470+06.35	37.95 R	606.76
AA	2470+04.17	0.00	606.82
BB	2469+98.17	0.00	606.83






				LEGEND xx.xx' EXISTING LENGTH () EXISTING ELEVATION/SLOPE PROPOSED SIDEWALK PROPOSED SIDE CURB SC TOP OF PROPOSED SIDE CURB CLASS D PATCH DETECTABLE WARNINGS SIDEWALK REMOVAL REPLACE W/TOPSOIL & SOD			REFERENCE BENCHMARK ELEV 608.384 BENCHMARK : ARROW POINTS TO SOUTH EASTERNLY LOWER FLANGE BOLT OF HYDRANT LOCATION : ON SOUTH WEST CORNER OF CERMAK RD. AND 53RD AVE.							
FILE NAME =		USER NAME = Bilgramiso	DESIGNED - --- --/--/----	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION SIDEWALK DETAIL PLAN CERMAK RD. – IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)				F.A.U. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
pw:\IL\084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI03218\Bilgramiso\Design\0103218-sh\Default.dgn				REVISED -					1453	(78-1&78-3)RS-2		COOK	54	230
		PLOT SCALE = 10.0000' / in.	CHECKED -	REVISED -					CONTRACT NO. 62F74					
Default		PLOT DATE = 4/30/2018	DATE -	REVISED -					ILLINOIS FED. AID PROJECT					
					SCALE:		SHEET OF SHEETS		STA. TO STA.					

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2482+64.86	65.54 L	(604.53)
B	2482+70.86	55.54 L	605.19
C	2482+70.86	50.54 L	605.14
D	2482+75.86	55.54 L	605.14
E	2482+75.86	50.54 L	605.09
F	2482+81.68	55.54 L	604.73
G	2482+83.86	55.54 L	604.71
H	2482+81.68	50.54 L	604.68
I	2482+83.20	50.02 L	604.63
J	2482+83.47	50.54 L	604.66
K	2482+85.53	55.54 L	604.69
L	2482+85.67	56.00 L	604.71
M	2482+84.89	59.38 L	604.98
N	2482+87.09	65.54 L	(604.76)
O	2483+09.59	55.75 L	605.69
P	2483+09.59	49.75 L	605.71
Q	2482+70.86	42.93 L	605.39
R	2482+65.41	34.57 L	(605.52)
S	2482+66.86	36.87 L	605.70
T	2482+70.86	39.01 L	605.37
U	2482+70.34	36.85 L	605.38
V	2482+70.86	37.15 L	605.35
W	2482+75.86	40.78 L	605.30
X	2482+75.86	42.93 L	605.32
Y	2482+76.86	43.93 L	605.36
Z	2482+80.92	46.35 L	604.74
AA	2482+68.16	0.00	606.43
BB	2482+78.18	0.00	606.31

	STATION	OFFSET	ELEVATION
A	2483+54.59	63.98 L	(605.72)
B	2483+49.59	54.98 L	605.73
C	2483+49.59	49.98 L	605.68
D	2483+44.59	49.98 L	605.63
E	2483+44.59	54.98 L	605.68
F	2483+35.15	54.98 L	605.29
G	2483+35.15	49.98 L	605.28
H	2483+33.61	49.50 L	605.26
I	2483+33.35	49.98 L	605.26
J	2483+32.88	54.98 L	605.26
K	2483+31.20	54.98 L	605.24
L	2483+31.02	55.53 L	605.24
M	2483+31.72	58.98 L	605.58
N	2483+29.41	63.98 L	(605.21)
O	2483+09.59	55.75 L	605.69
P	2483+09.59	49.75 L	605.71
Q	2483+39.29	44.13 L	605.52
R	2483+44.59	39.29 L	605.35
S	2483+44.15	37.66 L	605.31
T	2483+44.59	37.35 L	605.33
U	2483+49.59	36.26 L	605.38
V	2483+50.00	34.32 L	605.38
W	2483+49.59	34.51 L	605.36
X	2483+49.59	39.29 L	605.40
Y	2483+52.59	34.97 L	605.62
Z	2483+54.13	32.77 L	(605.40)
AA	2483+48.37	0.00	605.89
BB	2483+42.36	0.00	605.91



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS



PROPOSED SIDEWALK



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

SCALE: 1" = 5'

	SHE
--	-----

SMART CORRIDOR

CERMAK ROAD / 22ND STREET & LARAMIE AVENUE

	SHE
--	-----

OF	SHEETS	STA.
----	--------	------

TO STA.

F.A.U. RTE.	1453
----------------	------

SECTION


COUNTY

TOTAL SHEETS	SHEET NO.
54	235



CONTRACT NO.	62F74
--------------	-------

ILLINOIS	FED. AID PROJECT
----------	------------------

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2482+56.80	60.52 R	(605.45)
B	2482+67.13	60.52 R	(605.48)
C	2482+67.13	62.84 R	(605.48)
D	2482+68.80	69.00 R	(605.51)
E	2482+68.80	75.00 R	(605.52)
F	2482+37.29	74.91 R	(605.06)
G	2482+74.28	69.00 R	605.50
H	2482+71.13	62.84 R	605.43
I	2482+71.13	57.84 R	605.47
J	2482+67.13	57.84 R	605.51
K	2482+71.13	52.84 R	605.78
L	2482+67.13	52.84 R	605.84
M	2482+78.63	54.03 R	605.59
N	2482+77.51	52.84 R	605.70
O	2482+75.23	52.84 R	605.72
P	2482+75.47	45.85 R	605.68
Q	2482+67.13	47.42 R	605.82
R	2482+67.13	45.68 R	605.80
S	2482+65.50	45.00 R	605.84
T	2482+56.97	42.94 R	(605.95)
U	2482+68.16	0.00	606.43
V	2482+78.18	0.00	606.31
W	2483+09.59	47.70 R	605.65
X	2483+09.59	55.71 R	605.61



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

PROPOSED SIDEWALK

DETECTABLE WARNINGS

 SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SMART CORRIDOR
CERMAK ROAD / 22ND STREET & LARAMIE AVENUE

SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.
----------------	-------	----	--------	------	---------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	23T
		CONTRACT NO. 62F74		
		ILLINOIS FED. AID PROJECT		

FILE NAME =
95212_Cermak-sht-Laramie02.dgn

```
USER NAME = j1robinson
```

DESIGNED	-	KBH
----------	---	-----

DRAWN	-	KBH
-------	---	-----


PLOT SCALE = 10.0000' / in.

CHECKED	-	JIR
---------	---	-----

REVISED	-
---------	---

REVISÉ -

REVISÉ -



LEGEND

xx.xx'

EXISTING LENGTH

()

EXISTING ELEVATION/SLOPE



PROPOSED SIDEWALK



PROPOSED SIDE CURB

SC

TOP OF PROPOSED
SIDE CURB



CLASS D PATCH



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

REFERENCE BENCHMARK ELEV 607.935

BENCHMARK : SOUTH WEST BOLT ON FIRE HYDRANT

LOCATION : ON NORTH EAST CORNER OF CERMAK RD. AND
51ST AVE.

FILE NAME =	USER NAME = Bilgrami	DESIGNED -	REVIS
pw\11084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI03218\Design\DI03218-sh\Default.dgn		DESIGNED -	REVIS
Default		CHECKED -	REVIS
		DATE -	REVIS


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN
CERMAK RD. - IL 43 (HARLEM AVE.) TO IL 50 (CICERO AVE.)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	23U
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

ADA DETAILS FOR PHASE 1 PROJECTS




	STATION	OFFSET	ELEVATION
A	2496+03.26	61.31 L	(604.79)
B	2496+26.34	61.02 L	(603.99)
C	2496+12.97	55.31 L	604.95
D	2496+12.97	51.31 L	604.90
E	2496+16.97	55.31 L	604.90
F	2496+16.97	51.31 L	604.85
G	2496+21.41	51.31 L	604.61
H	2496+22.44	49.84 L	604.61
I	2496+23.17	51.31 L	604.59
J	2496+21.41	55.31 L	604.59
K	2496+23.13	55.31 L	604.57
L	2496+24.81	55.31 L	604.54
M	2496+24.96	55.73 L	604.51
N	2496+24.09	58.31 L	604.68
O	2496+47.53	54.75 L	604.91
P	2496+47.53	48.74 L	605.00
Q	2496+01.99	50.01 L	(604.45)
R	2496+08.81	43.90 L	605.17
S	2496+12.97	44.38 L	604.86
T	2496+12.97	42.60 L	604.84
U	2496+12.97	41.02 L	604.82
V	2496+16.97	42.07 L	604.80
W	2496+16.97	44.38 L	604.82
X	2496+18.96	44.36 L	604.72
Y	2496+18.75	46.78 L	604.90
Z	2496+13.28	0.00	605.78
AA	2496+19.28	0.00	605.77

LEGEND

- (XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE


- PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS




	STATION	OFFSET	ELEVATION
A	2496+87.83	60.20 L	(604.67)
B	2496+68.02	59.94 L	(604.03)
C	2496+82.83	53.20 L	604.70
D	2496+82.83	48.20 L	604.75
E	2496+77.83	48.20 L	604.70
F	2496+77.83	53.20 L	604.65
G	2496+74.09	53.20 L	604.46
H	2496+74.09	48.20 L	604.51
I	2496+72.57	47.65 L	604.52
J	2496+72.25	48.20 L	604.49
K	2496+71.56	53.20 L	604.44
L	2496+69.86	53.20 L	604.42
M	2496+69.64	53.79 L	604.40
N	2496+69.98	58.20 L	604.50
O	2496+47.53	54.75 L	604.91
P	2496+47.53	48.74 L	605.00
Q	2496+76.66	44.60 L	604.90
R	2496+77.83	43.25 L	604.87
S	2496+82.83	43.25 L	604.94
T	2496+77.32	41.47 L	604.83
U	2496+77.83	40.96 L	604.85
V	2496+82.83	38.76 L	604.93
W	2496+82.83	36.82 L	604.91
X	2496+83.30	36.50 L	604.94
Y	2496+86.16	36.62 L	605.27
Z	2496+87.13	34.32 L	(605.11)
AA	2496+77.17	0.00	605.66
BB	2496+83.17	0.00	605.68

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2496+08.90	31.99 R	(605.11)
B	2496+08.53	60.00 R	(605.03)
C	2496+13.53	45.67 R	605.35
D	2496+18.53	45.67 R	605.30
E	2496+13.53	41.67 R	605.30
F	2496+18.53	41.67 R	605.25
G	2496+13.53	37.67 R	605.12
H	2496+21.53	39.73 R	605.35
I	2496+19.54	36.43 R	605.01
J	2496+18.53	37.67 R	605.05
K	2496+18.53	35.82 R	605.03
L	2496+13.53	35.13 R	605.10
M	2496+13.53	33.43 R	605.08
N	2496+09.07	33.66 R	605.49
O	2496+13.28	0.00	605.78
P	2496+19.28	0.00	605.77
Q	2496+18.53	49.00 R	605.21
R	2496+18.53	54.00 R	605.16
S	2496+23.53	54.00 R	605.11
T	2496+23.53	49.00 R	605.16
U	2496+29.87	54.00 R	604.81
V	2496+33.62	57.54 R	605.01
W	2496+35.78	59.68 R	(604.79)
X	2496+32.40	54.00 R	604.79
Y	2496+34.10	54.00 R	604.77
Z	2496+31.71	49.00 R	604.84
AA	2496+31.40	48.48 R	604.85
BB	2496+29.87	49.00 R	604.86
CC	2496+27.80	46.00 R	605.16
DD	2496+47.53	54.85 R	604.94
EE	2496+47.53	48.85 R	605.01
FF	2496+34.31	54.55 R	604.77




FILE NAME =	USER NAME = jirobinson	DESIGNED - KBH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SMART CORRIDOR CERMAK ROAD /22ND STREET & 50TH AVENUE				F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9512_Cermak-sht-50th02.dgn		DRAWN - KBH	REVISED -		1453	(78-1&78-3)RS-2		COOK	54	23X			
Default	PLOT SCALE = 10.0000' / in.	CHECKED - JIR	REVISED -		CONTRACT NO. 62F74								
	PLOT DATE = 3/26/2018	DATE - 1/24/2018	REVISED -		SCALE: 1" = 5'	SHEET	OF	SHEETS	STA.	TO STA.			

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2502+78.87	60.79 L	(604.24)
B	2502+84.87	55.79 L	604.35
C	2502+84.87	50.79 L	604.37
D	2502+89.87	55.79 L	604.28
E	2502+89.87	50.79 L	604.30
F	2502+94.69	50.79 L	603.96
G	2502+94.69	55.79 L	603.94
H	2502+96.83	55.79 L	603.92
I	2502+97.47	57.93 L	604.00
J	2502+98.62	56.18 L	603.88
K	2502+98.50	55.79 L	603.90
L	2502+96.47	50.79 L	603.94
M	2502+96.23	50.31 L	603.96
N	2503+16.89	55.08 L	604.09
O	2503+16.89	49.07 L	604.20
P	2502+84.87	43.93 L	604.35
Q	2502+92.02	46.55 L	604.36
R	2502+89.87	43.93 L	604.28
S	2502+90.37	42.14 L	604.25
T	2502+89.87	41.64 L	604.26
U	2502+84.87	37.50 L	604.32
V	2502+84.37	37.17 L	604.34
W	2502+81.87	37.48 L	604.58
X	2502+78.87	34.22 L	(604.51)
Y	2502+84.40	0.00	605.01
Z	2502+90.40	0.00	604.93
AA	2502+99.65	60.52 L	(603.65)
BB	2502+84.87	39.46 L	604.34

	STATION	OFFSET	ELEVATION
A	2503+54.92	59.43 L	(604.01)
B	2503+32.62	59.12 L	(603.75)
C	2503+48.92	53.43 L	604.38
D	2503+48.92	48.43 L	604.43
E	2503+43.92	53.43 L	604.33
F	2503+43.92	48.43 L	604.38
G	2503+38.53	53.43 L	603.95
H	2503+35.99	53.43 L	603.93
I	2503+34.93	56.43 L	604.08
J	2503+34.06	54.05 L	603.89
K	2503+34.29	53.43 L	603.91
L	2503+38.53	48.43 L	604.00
M	2503+37.03	47.86 L	604.00
N	2503+36.69	48.43 L	603.98
O	2503+16.89	55.08 L	604.09
P	2503+16.89	49.07 L	604.20
Q	2503+42.10	43.65 L	604.40
R	2503+48.92	41.77 L	604.37
S	2503+51.92	36.07 L	604.59
T	2503+54.92	33.02 L	(604.41)
U	2503+48.92	37.81 L	604.36
V	2503+49.36	35.67 L	604.36
W	2503+48.92	35.94 L	604.34
X	2503+43.92	39.62 L	604.30
Y	2503+43.47	40.02 L	604.28
Z	2503+43.92	41.77 L	604.32
AA	2503+42.44	0.00	605.01
BB	2503+48.44	0.00	605.06




LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD


** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2502+80.93	73.11 R	(604.39)
B	2502+84.93	58.11 R	604.22
C	2502+84.93	53.11 R	604.27
D	2502+89.93	53.11 R	604.22
E	2502+89.93	58.11 R	604.17
F	2502+95.01	58.11 R	603.84
G	2502+95.01	53.11 R	603.87
H	2502+99.39	73.11 R	(603.22)
I	2502+97.45	61.60 R	604.10
J	2502+96.74	58.11 R	603.82
K	2502+98.47	58.52 R	603.78
L	2502+98.37	58.11 R	603.80
M	2502+96.73	53.11 R	603.85
N	2502+96.50	52.57 R	603.87
O	2503+16.89	52.05 R	604.22
P	2503+16.89	58.05 R	604.15
Q	2502+92.93	49.11 R	604.20
R	2502+89.93	46.95 R	604.16
S	2502+84.93	45.44 R	604.22
T	2502+84.93	46.95 R	604.23
U	2502+82.47	43.29 R	604.27
V	2502+74.96	39.05 R	604.93
W	2502+70.16	37.65 R	(605.00)
X	2502+70.95	33.73 R	(604.91)
Y	2502+71.26	32.18 R	(604.51)
Z	2502+76.40	35.31 R	604.90
AA	2502+84.43	37.80 R	604.22
BB	2502+84.93	38.16 R	604.20
CC	2502+84.93	40.14 R	604.22
DD	2502+89.93	42.56 R	604.13
EE	2502+90.43	43.11 R	604.11
FF	2502+89.93	44.95 R	604.15
GG	2502+84.40	0.00	605.01
HH	2502+90.40	0.00	604.93

	STATION	OFFSET	ELEVATION
A	2503+51.89	63.00 R	(604.06)
B	2503+46.89	57.00 R	604.01
C	2503+46.89	52.00 R	604.06
D	2503+41.89	52.00 R	604.01
E	2503+41.89	57.00 R	603.96
F	2503+38.17	57.00 R	603.82
G	2503+36.36	57.00 R	603.80
H	2503+38.17	52.00 R	603.82
I	2503+36.64	51.54 R	603.81
J	2503+36.44	52.00 R	603.80
K	2503+34.72	57.00 R	603.78
L	2503+34.58	57.59 R	603.76
M	2503+35.70	60.00 R	603.92
N	2503+33.75	62.88 R	(603.65)
O	2503+16.89	52.05 R	604.22
P	2503+16.89	58.05 R	604.15
Q	2503+46.89	47.81 R	604.28
R	2503+40.29	48.10 R	604.23
S	2503+41.89	47.81 R	604.23
T	2503+41.89	45.81 R	604.20
U	2503+41.30	44.00 R	604.16
V	2503+41.89	43.30 R	604.18
W	2503+46.89	40.59 R	604.23
X	2503+49.89	38.37 R	604.48
Y	2503+51.13	35.78 R	(604.30)
Z	2503+47.46	38.14 R	604.23
AA	2503+46.89	38.57 R	604.21
BB	2503+42.44	0.00	605.01
CC	2503+48.44	0.00	605.06




LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD


** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

ADA DETAILS FOR PHASE 1 PROJECTS



	STATION	OFFSET	ELEVATION
A	2509+45.26	86.13 L	604.24
B	2509+54.57	86.17 L	(603.38)
C	2509+45.26	81.13 L	604.00
D	2509+52.99	81.16 L	603.88
E	2509+52.99	78.18 L	603.85
F	2509+52.99	74.16 L	603.53
G	2509+49.26	74.15 L	603.79
H	2509+45.26	74.13 L	603.83
I	2509+34.76	74.09 L	604.44
J	2509+29.76	74.58 L	(604.41)
K	2509+29.76	69.08 L	(604.40)
L	2509+34.76	69.09 L	604.42
M	2509+45.26	69.13 L	603.78
N	2509+49.26	69.15 L	603.74
O	2509+52.99	65.16 L	603.87
P	2509+52.99	69.16 L	603.55
Q	2509+54.57	74.68 L	603.49
R	2509+54.57	74.17 L	603.51
S	2509+54.57	69.17 L	603.53
T	2509+54.57	68.68 L	603.54
U	2509+85.28	75.05 L	604.02
V	2509+85.31	69.05 L	604.03
W	2509+39.76	57.16 L	604.18
X	2509+44.76	57.16 L	604.13
Y	2509+44.76	52.16 L	604.08
Z	2509+39.76	52.16 L	604.13
AA	2509+48.76	50.76 L	604.05
BB	2509+39.76	47.16 L	603.78
CC	2509+44.76	47.16 L	603.73
DD	2509+45.21	45.57 L	603.69
EE	2509+44.76	45.29 L	603.71
FF	2509+39.76	44.83 L	603.77
GG	2509+39.76	43.18 L	603.75
HH	2509+39.14	43.03 L	603.77
II	2509+33.76	42.50 L	(603.84)
JJ	2509+35.76	44.12 L	604.09
KK	2509+37.92	0.00	604.33
LL	2509+43.92	0.00	604.28

	STATION	OFFSET	ELEVATION
A	2510+30.18	75.03 L	(603.90)
B	2510+25.18	80.00 L	(603.94)
C	2510+25.18	69.97 L	603.87
D	2510+20.18	69.97 L	603.82
E	2510+20.18	74.97 L	603.77
F	2510+14.25	77.94 L	603.73
G	2510+12.66	79.94 L	(603.52)
H	2510+12.68	75.42 L	603.50
I	2510+12.69	74.94 L	603.50
J	2510+14.27	74.94 L	603.52
K	2510+12.71	69.94 L	603.53
L	2510+12.71	69.42 L	603.55
M	2510+14.29	69.94 L	603.55
N	2509+85.28	75.05 L	604.02
O	2509+85.31	69.05 L	604.03
P	2510+25.18	45.62 L	603.65
Q	2510+20.18	57.73 L	603.88
R	2510+25.18	57.73 L	603.83
S	2510+25.18	52.73 L	603.78
T	2510+20.18	52.73 L	603.83
U	2510+18.18	50.83 L	603.85
V	2510+25.18	48.73 L	603.67
W	2510+19.65	47.10 L	603.59
X	2510+20.19	46.68 L	603.61
Y	2510+25.19	43.92 L	603.63
Z	2510+25.58	43.78 L	603.61
AA	2510+28.18	44.70 L	603.88
BB	2510+30.18	42.81 L	603.56
CC	2510+18.68	0.00	604.09
DD	2510+24.68	0.00	604.06
EE	2510+25.18	75.00 L	(603.82)
FF	2510+20.18	48.73 L	603.63
GG	2510+14.31	65.94 L	603.87
HH	2510+25.19	43.92 L	603.63



LEGEND

(XX.XX) EXISTING LENGTH/ELEVATION

== PROPOSED SIDE CURB

(%) EXISTING SLOPE

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

11

PROPOSED SIDEWALK

DETECTABLE WARNINGS

SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

SMART CORRIDOR

CERMAK ROAD / 22ND STREET & CICERO AVENUE (IL-50)

SCALE: 1" = 5'

	SHE
--	-----

OF

SHEET

STA.

TO STA

	F.A.U. RTE.
--	----------------

SECTION

COUNTY



TOTAL SHEETS	SHEET NO.
-----------------	--------------

54	24
NO. 63E74	

CONTRACT NO. 62F74

ILLINOIS	FED. AID PROJECT
----------	------------------

ADA DETAILS FOR PHASE 1 PROJECTS



LEGEND


(XX.XX) EXISTING LENGTH/ELEVATION
== PROPOSED SIDE CURB
(%) EXISTING SLOPE

PROPOSED SIDEWALK
DETECTABLE WARNINGS
SIDEWALK REMOVAL
REPLACE W/ TOPSOIL & SOD

** ALL CROSSWALKS SHALL BE HIGH VISIBILITY CROSSWALKS

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	799	FOOT

MODEL: Default
FILE: N:\151\Design\151\Detector Loop\6374 - Cermak Rd. from IL-43 (Harlem Ave.) to IL-50 (Cicero Ave.)\CADD\151280 - Cermak Rd. at Harlem Ave. 0222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / in.	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 12/04/2017	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT IL RTE 43 (HARLEM AVE)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3) RS-2	COOK	54	25
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations)".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	689	FOOT

MODEL: Default
FILE NAME: SWPDesign\B5\Detector Loop\6374 - Cermak Rd. from IL-50 (Cicero Ave.)\CADD\5795 - CERMAK RD AT WENONAH AVE 022203.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT WENONAH AVE / CERMAK PLAZA ENTRANCE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	26
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations)".
2. This plan is for the sole purpose of detector loop replacement.



CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	336	FOOT

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT HOME AVE


SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
--------	-------	----	--------	------	---------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3) RS-2	COOK	54	27
		CONTRACT NO. 62F74		
		ILLINOIS	FED. AID PROJECT	

MODEL: Default
FILE NAME: SWP(Design)BSDetector Loops62F74 - Cernak Rd. from IL-43 (Harlem Ave.) to IL 50 (Cicero Ave.)CADT54810 - CERNAK RD AT HOME AVE 02222018.dgn

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	1042	FOOT

MODEL: Default
FILE: Note13.rvt
Design: 850
Detector: Loop163774 - Cermak Rd. from IL-43 (Harlem Ave.) to IL-50 (Cicero Ave.)
CADD: 154830 - Cermak Rd. at Oak Park Ave. 02/22/2018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
DRAWN - BS	REVISED -	
PLOT SCALE = 40.0000' / 1" =	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT OAK PARK AVE

SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
--------	-------	----	--------	------	---------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	28
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	376	FOOT

MODEL: Default
FILE NAME: S:\WPDesign\BS\Detector Loops\6374 - CermaK Rd. from IL-50 (Harlem Ave.) to IL-50 (Clermont Ave.)\CADD\54840 - CERMAK RD AT WESLEY AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT WESLEY AVE			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	29
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	235	FOOT

MODEL: Default
FILE: N:\M\15\150\Design\150\Detector Loop\150\15074 - Cermak Rd. from IL-43 (Harlem Ave.) to IL-50 (Cicero Ave.)\CADD\15074 - Cermak Rd. AT EAST AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1" =	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT EAST AVE			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	30
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	511	FOOT

MODEL: Default
FILE NAME: S:\WPDesign\85\Detector Loops\6374 - Cermak Rd. from IL-50 (Cicero Ave.)\CADD\54835 - Cermak Rd. AT RIDGELAND AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1" =	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT RIDGELAND AVE			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3) RS-2	COOK	54	31
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	344	FOOT

MODEL: Default
FILE NAME: SWPDesign\B5\Detector_Loops\6374 - Cermak Rd. from IL-50 (Cicero Ave.)\CADD\54815 - Cermak Rd. AT LOMBARD AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1" =	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT LOMBARD AVE			
SCALE:	SHEET	OF	SHEETS
	STA.		TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	32
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	411	FOOT

MODEL: Default
FILE: Note13.rvt
PROJECT: 62F74 - Cermak Rd. from IL-50 (Cicero Ave.) to IL-53 (Hawthorne Ave.)
SHEET: 54 of 54
DATE: 02/22/2018

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/22/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT AUSTIN AVE			
SCALE:	SHEET	OF	SHEETS
	STA.		TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	33
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations)".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	323	FOOT

MODEL: Default
FILE: Note: SWPDesign\B5Detector Loops\6374 - Cermak Rd. from IL-50 (Cicero Ave.)\CADD\5780 - Cermak Rd. at 58th Ave. 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT 58TH AVE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3) RS-2	COOK	54	34
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	322	FOOT

MODEL: Default
FILE: Note: SWPDesign\85\Detector Loops\6374 - Cermak Rd. from IL-43 (Helen Ave.) to IL-50 (Cicero Ave.)\CAD\154775 - Cermak Rd. AT 57TH AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT 57TH AVE			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	35
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations)".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	522	FOOT

MODEL: Default
FILE NAME: SWPDesign\BS\Detector Loops\6374 - Cermak Rd. from IL-50 (Cicero Ave.)\CADD\57790 - Cermak Rd. AT CENTRAL AVE 0222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1" =	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT CENTRAL AVE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	36
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision,
"Detector Loop Replacement and/or Installation (Roadway Grinding,
Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	357	FOOT

MODEL: Default
FILE: N:\MTE 3\WPDesign\85\Detector Loop\6374 - Cermak Rd. from IL-50 (Cicero Ave.)\CADD\1512790 - CERMAK RD AT 54TH AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT 54TH AVE			
SCALE:	SHEET	OF	SHEETS
	STA.		TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	37
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision,
"Detector Loop Replacement and/or Installation (Roadway Grinding,
Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	145	FOOT

MODEL: Default
FILE NAME: S:\WPDesign\85\Detector Loop\6374 - CermaK Rd. from IL-3 (Harlem Ave.) to IL-50 (Clermont Ave.)\CADD\1512785 - CermaK Rd AT LARAMIE AVE 0222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / in.	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT LARAMIE AVE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	38
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision,
"Detector Loop Replacement and/or Installation (Roadway Grinding,
Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	390	FOOT

MODEL: Default
FILE NAME: SWPDesign\85\Detector Loop\6374 - Cermak Rd. from IL-3 (Harlem Ave.) to IL-50 (Cicero Ave.)\CADD\1512780 - Cermak Rd. AT 50TH AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT 50TH AVE			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	39
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision, "Detector Loop Replacement and/or Installation (Roadway Grinding, Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	350	FOOT

MODEL: Default
FILE NAME: SWPDesign\85\Detector Loop\6374 - Cermak Rd. from IL-3 (Harlem Ave.) to IL-50 (Cicero Ave.)\CADD\151275 - CERMAK RD AT 49TH AVE 02222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



DETECTOR LOOP REPLACEMENT PLAN
CERMAK RD AT 49TH AVE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1678-3) RS-2	COOK	54	40
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				

NOTES:

1. Work shall meet the requirements of the special provision,
"Detector Loop Replacement and/or Installation (Roadway Grinding,
Resurfacing & Patching Operations".
2. This plan is for the sole purpose of detector loop replacement.



REPLACE ALL DETECTOR LOOPS AS SHOWN
(WITHIN THE RESURFACING LIMITS)

CODE	ITEM	QUANTITY	UNIT
88600600	DETECTOR LOOP REPLACEMENT	307	FOOT


MODEL: Default
FILE NAME: 31012Design05Detector_Loop063174 - Cermak Rd. from IL-43 (Harlem Ave.) to IL-50 (Cicero Ave.)\CADD\1512770 - CERMak RD AT CICERO AVE 03222018.dgn

USER NAME = snowba	DESIGNED - BS	REVISED -
	DRAWN - BS	REVISED -
PLOT SCALE = 40.0000' / 1"	CHECKED - LP	REVISED -
PLOT DATE = 2/23/2018	DATE - 02/22/2018	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETECTOR LOOP REPLACEMENT PLAN CERMAK RD AT CICERO AVE			
SCALE:	SHEET	OF	SHEETS
	STA.		TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3) RS-2	COOK	54	41
CONTRACT NO. 62F74				
ILLINOIS FED. AID PROJECT				



NOTES:

EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.

IF THE EXISTING LIDS ARE OPEN, THE FRAME WILL BE ADJUSTED TO THE ELEVATION OF THE MILLED PAVEMENT SURFACE PRIOR TO THE MILLING OPERATION. THE FRAME WILL NOT BE REMOVED AND COVERED BY THE METAL PLATE.

CITY OF CHICAGO CASTINGS ARE THE PROPERTY OF THE CITY AND THE CONTRACTOR SHALL NOTIFY THE CITY FOR REMOVAL AND DISPOSITION OF THE CASTINGS.

THE METAL PLATE USED TO COVER THE STRUCTURE SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.

WHEN STRUCTURES ARE TO BE ADJUSTED OR RECONSTRUCTED, THE LOWERING AND RAISING OF THE FRAMES AND LIDS WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF THE CORRESPONDING PAY ITEM.

CONSTRUCTION PROCEDURES

STAGE 1 (BEFORE PAVEMENT MILLING)

- A) REMOVE A MINIMUM OF 12 (300) OF THE PAVEMENT FROM AROUND THE STRUCTURE.
B) REMOVE THE EXISTING FRAME AND LID FROM THE STRUCTURE.
C) COVER THE STRUCTURE OPENING WITH A 36 (900) DIAMETER METAL PLATE.
D) BACKFILL WITH CRUSHED STONE AND A MINIMUM 1½ (40) THICK HMA SURFACE MIX APPROVED BY THE ENGINEER.

STAGE 2 (AFTER PAVEMENT MILLING)

- A) REMOVE THE HMA SURFACE MIX AND CRUSHED STONE.
B) INSTALL THE FRAME AND LID; ADJUST THE FRAME TO ITS FINAL SURFACE ELEVATION.
C) THE SURROUNDING SPACE SHALL BE FILLED WITH CLASS PP-1* CONCRETE TO THE ELEVATION OF THE SURFACE OF THE EXISTING BASE COURSE OR THE BINDER COURSE.

*UNLESS OTHERWISE SPECIFIED IN THE PLANS.

THE PROCEDURE EXPLAINED ABOVE SHALL CONFORM TO THE APPLICABLE PORTIONS OF SECTIONS 353, 406, 602, AND 603 OF THE STANDARD SPECIFICATIONS EXCEPT THAT "THE CONTRACTOR SHALL ADJUST THE STRUCTURES TO THE FINISHED PAVEMENT ELEVATION NO MORE THAN 5 CALENDAR DAYS PRIOR TO PLACEMENT OF THE FINAL LIFT OF SURFACE UNLESS APPROVED BY THE ENGINEER."

LEGEND

- ① SUB-BASE GRANULAR MATERIAL
② EXISTING PAVEMENT
③ 36 (900) DIAMETER METAL PLATE
④ PROPOSED CRUSHED STONE AND HMA SURFACE MIX
⑤ EXISTING STRUCTURE
⑥ FRAME AND LID (SEE NOTES)
⑦ CLASS PP-1* CONCRETE
⑧ PROPOSED HMA SURFACE COURSE
⑨ PROPOSED HMA BINDER COURSE

LOCATION OF STRUCTURES:

THE CONTRACTOR WILL BE REQUIRED TO KEEP A RECORD OF THE LOCATIONS OF THE BURIED STRUCTURES ACCORDING TO THE STATION AND DISTANCE LEFT OR RIGHT OF THE CENTERLINE OF PAVEMENT. UPON COMPLETION OF THE WORK, THE CONTRACTOR WILL DELIVER THE RECORD TO THE ENGINEER.

BASIS OF PAYMENT:

REMOVING FRAMES AND LIDS ON DRAINAGE AND UTILITY STRUCTURES IN THE PAVEMENT PRIOR TO MILLING, AND ADJUSTING TO FINAL GRADE PRIOR TO PLACING THE SURFACE COURSE, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR "FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)."

THIS WORK WILL NOT BE PAID FOR WHEN DRAINAGE AND UTILITY STRUCTURES ARE SPECIFIED FOR PAYMENT AS STRUCTURE RECONSTRUCTION.

NEW FRAMES AND LIDS, WHEN SPECIFIED, WILL BE PAID FOR SEPARATELY.

DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN


FILE NAME =	USER NAME = Bilgramiso	DESIGNED - R. SHAH	REVISED - R. WIEDEMAN 05-14-04
p:\1\1084EBIDINTEG\illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI032018\1084EBIDINTEG\Design\DistStd.dgn			REVISED - R. BORO 01-01-07
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - R. BORO 03-09-11
	PLOT DATE = 3/23/2018	DATE - 10-25-94	REVISED - R. BORO 12-06-11

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETAILS FOR
FRAMES AND LIDS ADJUSTMENT WITH MILLING

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	\$TOPG\$	\$CUPG\$
BD600-03 (BD-8)		CONTRACT NO. 62F74		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)


1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

1. MILL HMA FIRST IF THERE IS AT LEAST 4 1/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = Bilgrami	DESIGNED - R. SHAH	REVISED - A. ABBAS 04-27-98	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\11\084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI032\Bilgrami\Design\DistStd.dgn			REVISED - R. BORO 01-01-07					1453	(78-1&78-3)R5-2	COOK	54	43
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - R. BORO 09-04-07					BD400-04 (BD-22)		CONTRACT NO. 62F74		
	PLOT DATE = 3/23/2018	DATE - 10-25-94	REVISED - K. ENG 10-27-08		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		




- * 3" (75) MINIMUM FROM TOP AND BOTTOM OF THE CONCRETE PAVEMENT OR BASE COURSE.
- * * IF THE FINAL SURFACE OF THE PAVEMENT IS CONCRETE, THE GUTTER IS TO BE FLUSH WITH THE PAVEMENT.
- NOTE: ① SIDEWALK, DRIVEWAY PAVEMENT OR MEDIAN SURFACE SHALL BE SIMILAR TO THE MATERIAL BEING REMOVED AND WILL BE PAID FOR SEPARATELY.
- SODDING, SALT TOLERANT AND TOP SOIL, FURNISH AND PLACE 4" WILL BE PAID FOR SEPARATELY.
- ② FERTILIZER FOR THE PLACEMENT OF THE SOD IS NOT REQUIRED
- ③ CURB OR CURB AND GUTTER REPLACEMENT SHALL MATCH THE SHAPE OF THE EXISTING CURB OR CURB AND GUTTER UNLESS OTHERWISE SPECIFIED.
- ④ FOR CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT ADJACENT TO FLEXIBLE PAVEMENT DELETE EPOXY COATED TIE BARS.
- ⑤ LONGITUDINAL BARS, IF ENCOUNTERED IN THE EXISTING CURB OR CURB AND GUTTER, ARE NOT TO BE REPLACED. CUTTING AND REMOVING LONGITUDINAL BARS SHALL BE INCLUDED IN THE COST OF CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT.
- ⑥ THE COST OF HMA SURFACE REMOVAL IN THE EXISTING GUTTER FLAG SHALL BE INCLUDED IN THE COST OF THE CURB AND GUTTER REMOVAL AND REPLACEMENT.
- ⑦ THE REMOVAL AND REPLACEMENT OF THE EXISTING CURB OR CURB AND GUTTER SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF SECTION 440 AND 606 OF THE STANDARD SPECIFICATIONS.
- ⑧ THE LOCATIONS OF REMOVAL AND REPLACEMENT OF EXISTING CURB OR CURB AND GUTTER SHALL BE DETERMINED BY THE RESIDENT ENGINEER AT THE TIME OF CONSTRUCTION.

BASIS OF PAYMENT:
THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT (METER) FOR "CURB REMOVAL AND REPLACEMENT" OR "COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT".


CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = p:\1\1084EBID\INTEG\Illinois.gov\PWIDOT\Documents\DOT Offices\District 1\Projects\DI032018\1084EBID\Design\DistStd.dgn	USER NAME = Bilgramiso	DESIGNED - A. HOUSEH	REVISED - R. SHAH 10-03-96	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			REVISED - A. ABBAS 03-21-97					1453	(78-1&78-3)RS-2	COOK	54	44
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - M. GOMEZ 01-22-01					BD600-06 (BD-24)		CONTRACT NO. 62F74		
	PLOT DATE = 3/23/2018	DATE - 03-11-94	REVISED - R. BORO 12-15-09					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
							SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		




OPTION 1





OPTION 2

TYPICAL TEMPORARY RAMP



TYPICAL BUTT JOINT AND HMA TAPER
FOR MILLING AND RESURFACING



TYPICAL BUTT JOINT AND HMA TAPER
FOR RESURFACING ONLY

*** PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT.

NOTES

- A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS.
- B: MINOR SIDE ROADS.
- C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E: TAPER THE TEMP. RAMP AT A RATE OF 3'-0" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- F: INSTALLATION AND REMOVAL OF THE 4'-6" (1.35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL - BUTT JOINT

G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".

*** SEE TYPICAL SECTIONS FOR MILLING THICKNESS.


*** 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A")
10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

BASIS OF PAYMENT:

THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD (SQUARE METER) FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT".

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = Bilgramiso	DESIGNED - M. DE YONG	REVISED - R. SHAH 10-25-94	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BUTT JOINT AND HMA TAPER DETAILS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\1\1084EBID\INTEG\Illinois.gov\PI\DOT\Documents\IDOT Offices\District 1\Projects\DI032\BROWN\Design\DistStd.dgn			REVISED - A. ABBAS 03-21-97			1453	(78-1&78-3)RS-2	COOK	54	45
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - M. GOMEZ 04-06-01			BD400-05 BD32		CONTRACT NO. 62F74		
	PLOT DATE = 3/23/2018	DATE - 06-13-90	REVISED - R. BORO 01-01-07			SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT



NOTES:


1. SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:

a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
2. SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:

a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN ROUTE.
b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
3. CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
4. WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).
5. WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARD(S). THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
6. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.
7. THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.


All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME =	USER NAME = Bilgramiso	DESIGNED - L.H.A.	REVISED - A. HOUSEH 10-15-96	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS					F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\11\084EBID\INTEG\Illinois.gov\PI\DOT\Documents\IDOT Offices\District 1\Projects\DI032\BROWN\Note\Design\DistStd.dgn			REVISED -T. RAMMACHER 01-06-00		1453	(78-1&78-3)RS-2	COOK	54	46					
PLOT SCALE = 100.0000' / in.	CHECKED -		REVISED - A. SCHUETZE 07-01-13		TC-10		CONTRACT NO. 62F74							
Default	PLOT DATE = 3/23/2018	DATE - 06-89	REVISED - A. SCHUETZE 09-15-16		SCALE: NONE		SHEET 1	OF 1	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		




*** REDUCE TO 40' (12 m) O.C. ON CURVES WITH POSTED OR ADVISORY SPEED 45 M.P.H. (70 km/h) OR LESS.

TWO-LANE/TWO-WAY




LANE REDUCTION TRANSITION




SEE NOTE A

TWO-WAY LEFT TURN



SEE NOTE A

MULTI-LANE/UNDIVIDED



SEE NOTE A

MULTI-LANE/DIVIDED

GENERAL NOTES

1. MARKERS USED WITH DASHED LINES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS.
2. MARKERS USED ADJACENT TO SOLID LINES SHALL BE OFFSET 2 TO 3 (50 TO 75) TOWARD TRAFFIC AS SHOWN.
3. MARKERS THROUGH TANGENTS LESS THAN 500' (150 m) IN LENGTH BETWEEN CURVES SHALL BE INSTALLED AT THE LESSER OF THE TWO CURVE SPACINGS.

LANE MARKER NOTES


- A. USE DOUBLE LANE LINE MARKERS SPACED AS SHOWN.
- B. REDUCE TO 40' (12 m) O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 M.P.H (20 km/h) LOWER THAN POSTED SPEEDS.

SYMBOLS

- YELLOW STRIPE
- WHITE STRIPE
- ◀ ONE-WAY AMBER MARKER
- ◀ ONE-WAY CRYSTAL MARKER (W/O)
- ◆ TWO-WAY AMBER MARKER

DESIGN NOTES

1. DOUBLE LANE LINE MARKERS SHALL BE USED UNLESS SPECIFIED OTHERWISE.
2. EXCEPT AS SHOWN ON THE LANE REDUCTION TRANSITION AND FREEWAY EXIT RAMP DETAIL, MARKERS ARE NOT TO BE SPECIFIED ON RIGHT EDGE LINES.
3. THE EXACT MARKER LIMITS, SPACING, AND COLOR SHALL BE INCLUDED IN THE PLANS WHEN STANDARD SPECIFICATIONS ARE NOT BEING USED.
4. MARKERS SHOULD NOT BE USED ALONGSIDE CURBS EXCEPT FOR EXTREMELY SHORT SECTIONS OF CURBS WHERE NOT MORE THAN TWO MARKERS WOULD BE INVOLVED.



* SEE TWO-LANE/TWO-WAY WHERE MARKERS CONTINUE
** WHERE THE MEDIAN WIDTH IS 6' (2 m) OR LESS
USE TWO-WAY MARKERS.

LEFT TURN

All dimensions are in inches (millimeters)
unless otherwise shown.

FILE NAME =	USER NAME = Bilgrami	DESIGNED -	REVISED - T. RAMMACHER 09-19-94
p:\1\1084EBID\INTEG\illinois.gov\PI\DOT\Documents\DOT Offices\District 1\Projects\DI032\Bilgrami\Design\DistStd.dgn			REVISED - T. RAMMACHER 03-12-99
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - T. RAMMACHER 01-06-00
	PLOT DATE = 3/23/2018	DATE -	REVISED - C. JUCIUS 09-09-09

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TYPICAL APPLICATIONS				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)				1453	(78-1&78-3)RS-2	COOK	54	47
				TC-11		CONTRACT NO. 62F74		
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

2-LANE ROADWAY

MULTI-LANE UNDIVIDED

TYPICAL LANE AND EDGE LINE MARKING

DETAIL "A"

DETAIL "B"

TYPICAL CROSSWALK MARKING

* MARKINGS SHALL BE INSTALLED PARALLEL TO THE CENTERLINE OF THE ROAD WHICH IT CROSSES

4' (1.2 m) WIDE MEDIANS ONLY

DIAGONAL LINE SPACING: 50' (15 m) C-C (LESS THAN 30MPH (50 km/h))
75' (25 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h))
150' (45 m) C-C (MORE THAN 45MPH (70 km/h))

MEDIANS OVER 4' (1.2 m) WIDE

MEDIAN WITH TWO-WAY LEFT TURN LANE

TYPICAL PAINTED MEDIAN MARKING

FULL SIZE LETTERS 8' (2.4 m) AND ARROWS SHALL BE USED.

* TURN LANES IN EXCESS OF 400' (120 m) IN LENGTH MAY HAVE AN ADDITIONAL SET OF ARROW - "ONLY" INSTALLED MIDWAY BETWEEN THE OTHER TWO SETS OF ARROW - "ONLY".

TYPICAL LEFT (OR RIGHT) TURN LANE

TYPICAL TURN LANE MARKING

ISLAND OFFSET FROM PAVEMENT EDGE

ISLAND AT PAVEMENT EDGE

TYPICAL ISLAND MARKING

COMBINATION LEFT AND U-TURN

U-TURN

D(FT)	SPEED LIMIT
345	30
425	35
500	40
580	45
665	50
750	55

LANE REDUCTION TRANSITION

* LANE REDUCTION ARROWS REQUIRED AT SPEEDS OF 45 MPH OR GREATER OR WHEN SPECIFIED IN PLANS.

TYPE OF MARKING	WIDTH OF LINE	PATTERN	COLOR	SPACING /REMARKS
CENTERLINE ON 2 LANE PAVEMENT	4 (100)	SKIP-DASH	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE
CENTERLINE ON MULTI-LANE UNDIVIDED PAVEMENT	2 @ 4 (100)	SOLID	YELLOW	11 (280) C-C
NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS	4 (100) 2 @ 4 (100)	SOLID SOLID	YELLOW YELLOW	5½ (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN
LANE LINES	4 (100) 5 (125) ON FREEWAYS	SKIP-DASH SKIP-DASH	WHITE WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE
DOTTED LINES (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS)	SAME AS LINE BEING EXTENDED	SKIP-DASH	SAME AS LINE BEING EXTENDED	2' (600) LINE WITH 6' (1.8 m) SPACE
EDGE LINES	4 (100)	SOLID	YELLOW-LEFT WHITE-RIGHT	OUTLINE MEDIANS IN YELLOW
TURN LANE MARKINGS	6 (150) LINE; FULL SIZE LETTERS & SYMBOLS (8" (2.4m))	SOLID	WHITE	SEE TYPICAL TURN LANE MARKING DETAIL
TWO WAY LEFT TURN MARKING	2 @ 4 (100) EACH DIRECTION 8' (2.4m) LEFT ARROW	SKIP-DASH AND SOLID IN PAIRS	YELLOW WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE FOR SKIP-DASH; 5½ (140) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE SEE TYPICAL TWO-WAY LEFT TURN MARKING DETAIL
CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL)	2 @ 6 (150) 12 (300) @ 45° 12 (300) @ 90°	SOLID SOLID SOLID	WHITE WHITE WHITE	NOT LESS THAN 6' (1.8 m) APART 2' (600) APART 2' (600) APART SEE TYPICAL CROSSWALK MARKING DETAILS.
STOP LINES	24 (600)	SOLID	WHITE	PLACE 4' (1.2 m) IN ADVANCE OF AND PARALLEL TO CROSSWALK, IF PRESENT, OTHERWISE, PLACE AT DESIRED STOPPING POINT, PARALLEL TO CROSSROAD CENTERLINE, WHERE POSSIBLE
PAINTED MEDIANS	2 @ 4 (100) WITH 12 (300) DIAGONALS @ 45° NO DIAGONALS USED FOR 4' (1.2 m) WIDE MEDIANS	SOLID	YELLOW; TWO WAY TRAFFIC WHITE; ONE WAY TRAFFIC	11 (280) C-C FOR THE DOUBLE LINE. SEE TYPICAL PAINTED MEDIAN MARKING.
CORE MARKING AND CHANNELIZING LINES	8 (200) WITH 12 (300) DIAGONALS @ 45°	SOLID	WHITE	DIAGONALS; 15' (4.5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h)) 30' (9 m) C-C (OVER 45MPH (70 km/h))
RAILROAD CROSSING	24 (600) TRANSVERSE LINES; "RR" 15 6" (1.8 m) LETTERS; 16 (400) LINE FOR "X"	SOLID	WHITE	SEE STATE STANDARD 780001 AREA OF: "R"=3.6 SQ. FT. (0.33 m²) EACH "X"=54.0 SQ. FT. (5.0 m²)
SHOULDER DIAGONALS (REQUIRED FOR SHOULDERS ≥ 8')	12 (300) @ 45°	SOLID	WHITE - RIGHT YELLOW - LEFT	50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) TO 45MPH (70 km/h)) 150' (45 m) C-C (OVER 45MPH (70 km/h))
U TURN ARROW	SEE DETAIL	SOLID	WHITE	16.3 SF
2 ARROW COMBINATION LEFT AND U TURN	SEE DETAIL	SOLID	WHITE	30.4 SF

FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO
STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE
CONSTRUCTION AND STATE STANDARD 780001.

All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME =	USER NAME = Bilgremisa	DESIGNED - EVERS	REVISED - C. JUCIUS 09-09-09
pw:\VL04EBID\INTEG\Illinois.gov\FWIDOT Documents\DOT Offices\District 1\Projects\01832\BWM\Notes\Design\DistStd.dgn		DATE = 03-19-90	REVISED - C. JUCIUS 07-01-13
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED - C. JUCIUS 12-21-15
Default	PLOT DATE = 3/23/2018	DATE = 03-19-90	REVISED - C. JUCIUS 04-12-16

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DISTRICT ONE TYPICAL PAVEMENT MARKINGS					F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
					1453	(78-1&78-3)RS-2	COOK	54	48
					TC-13		CONTRACT NO. 62F74		
SCALE: NONE	SHEET 1	OF 1	SHEETS	STA.	TO STA.				
					ILLINOIS FED. AID PROJECT				

TURN BAY ENTRANCE AT START
OF LANE CLOSURE TAPER





FIGURE 1

LEGEND



NOTES:

1. A) WHEN "L" IS $\leq$ THE STORAGE LENGTH OF THE TURN LANE (AS SHOWN IN FIG. 1), USE FIGURE 1.
B) WHEN "L" IS $>$ THE STORAGE LENGTH OF THE TURN LANE OR THE TURN LANE IS WITHIN THE LANE CLOSURE, USE FIGURE 2.
2. CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
3. LIGHTS WILL NOT BE REQUIRED ON BARRICADES OR DRUMS FOR DAY OPERATIONS. ALL LIGHTS SHALL BE MONODIRECTIONAL.
4. REFLECTIVE TEMPORARY PAVEMENT MARKINGS SHALL BE PLACED THROUGHOUT THE BARRICADED AREAS OF EACH TURN BAY AS SHOWN WHERE THE CLOSURE TIME IS GREATER THAN FOURTEEN (14) DAYS.
5. THIS APPLICATION ALSO APPLIES WHEN WORK IS BEING PERFORMED IN THE RIGHT LANE(S) AND THE RIGHT TURN BAY IS TO REMAIN OPEN. UNDER THIS CONDITION, "RIGHT TURN LANE" R3-1100R 24 x 24 (600 x 600) AND M6-2R 21 x 15 (530 x 380) SHALL BE USED.
6. THESE CONTROLS SHALL SUPPLEMENT MAINLINE TRAFFIC CONTROL FOR LANE CLOSURES.
7. THE SIGNS SHALL BE MOUNTED ABOVE THE BARRICADES/DRUMS ON SEPARATE SIGN SUPPORTS THAT MEET NCHRP 350 OR MASH PREQUIREMENTS.
8. TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

TURN BAY ENTRANCE
WITHIN A LANE CLOSURE






FIGURE 2



DETAIL A



All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME =	USER NAME = Bilgrami	REVISED - T. RAMMACHER 09-08-94	REVISED - R. BORO 09-14-09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)				F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\1\11084EBIDINTEG\Illinois.gov\PI\DOT\Documents\DOT Offices\District 1\Projects\DI032\REVISED\Design\HOUSEH 11-07-95		REVISED - A. HOUSEH 11-07-95	REVISED - A. SCHUETZE 07-01-13						1453	(78-1&78-3)R5-2	COOK	54	49
Default	PLOT SCALE = 100.0000' / in.	REVISED - A. HOUSEH 10-12-96	REVISED - A. SCHUETZE 09-15-16						TC-14		CONTRACT NO. 62F74		
	PLOT DATE = 3/23/2018	REVISED - T. RAMMACHER 01-06-00	REVISED -		SCALE: NONE	SHEET 1	OF 1	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		




QUANTITY

4 (100) LINE = 45.5 ft. (13.9 m)
15.2 sq. ft. (1.41 sq. m)



QUANTITY

4 (100) LINE = 64.1 ft. (19.5 m)
21.4 sq. ft. (1.99 sq. m)




QUANTITY

4 (100) LINE = 82.5 ft. (25.1 m)
27.5 sq. ft. (2.53 sq. m)

NOTE:

ALL QUANTITIES OF PLACEMENT ARE REPRESENTED IN LINEAR FEET OF 4" LINES TO MATCH THE 4" TEMPORARY TAPE PAY ITEM AND REPRESENTS THE TOTAL QUANTITY OF 4" TAPE REQUIRED.




QUANTITY

4 (100) LINE = 225.9 ft. (68.9 m)
75.3 sq. ft. (6.99 sq. m)

All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME = p:\1\1084EBID\INTEG\Illinois.gov\PI\DOT\Documents\DOT Offices\District 1\Projects\DI032\BROWNS\Browns\Design\DistStd.dgn	USER NAME = Bilgromisa	DESIGNED -	REVISED - T. RAMMACHER 03-02-98	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHORT TERM PAVEMENT MARKING LETTERS AND SYMBOLS				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0010 ' / in.	CHECKED -	REVISED - E. GOMEZ 08-28-00						1453	(78-1&78-3)RS-2	COOK	54	50
	PLOT DATE = 3/23/2018	DATE - 09-18-94	REVISED - A. SCHUETZE 09-15-16		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.				TC-16 CONTRACT NO. 62F74				
									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				




NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = Bilgramiso	DESIGNED -	REVISED - R. MIRS 09-15-97	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ARTERIAL ROAD INFORMATION SIGN			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\11\084EBIDINTEG\Illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI032018\Bilgramiso\Design\DistStd.dgn			REVISED - R. MIRS 12-11-97					1453	(78-1&78-3)RS-2	COOK	54	51
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED - T. RAMMACHER 02-02-99					TC-22		CONTRACT NO. 62F74		
	PLOT DATE = 3/23/2018	DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		



3.0" RADIUS, 0.5" BORDER, WHITE ON GREEN; REFLECTORIZED
"DRIVEWAY" D; "ENTRANCE" D; STANDARD ARROW CUSTOM 12.0" x 5.0"

NOTES:

1. HALF OF THE SIGNS WILL REQUIRE A LEFT HAND FACING ARROW.
2. TWO SIGNS SHALL BE USED AT EACH COMMERCIAL ENTRANCE
PLACED BACK-TO-BACK; ONE WITH A RIGHT HAND ARROW (SHOWN)
SHALL BE PLACED ON THE NEAR RIGHT SIDE THE DRIVEWAY
AND ONE WITH A LEFT HAND ARROW SHALL BE PLACED ON THE
FAR LEFT SIDE OF THE DRIVEWAY.
3. SIGNS TO BE PAID FOR AS ITEM "TEMPORARY INFORMATION SIGNING".

FILE NAME =	USER NAME = Bilgramiso	DESIGNED -	REVISED - C. JUCIUS 02-15-07
p:\1\1084EBIDINTEG\illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI032\BROWN\Design\DistStd.dgn		CHECKED -	REVISED -
	PLOT SCALE = 100.0000' / in.	DATE -	REVISED -
	PLOT DATE = 3/23/2018		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DRIVEWAY ENTRANCE SIGNING


SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1453	(78-1&78-3)RS-2	COOK	54	52
TC-26		CONTRACT NO. 62F74		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		


LOOP DETECTOR NOTES

1. EACH PAIR OF LOOP WIRES SHALL BE PLACED IN A SEPARATE EMPTY COILABLE NONMETALLIC CONDUIT FROM THE EDGE OF PAVEMENT TO THE HANDHOLE. SPACING BETWEEN THE HOLES DRILLED IN THE PAVEMENT SHALL NOT BE LESS THAN 6" (150 mm). EMPTY COILABLE NONMETALLIC CONDUIT SHALL BE INCLUDED IN THE COST OF THE LOOP WIRE.
2. THE NUMBER OF LOOP TURNS SHALL BE AS RECOMMENDED BY THE AMPLIFIER MANUFACTURER. ALL ADJACENT SIDES OF THE LOOPS SHALL BE INSTALLED IN SUCH A WAY THAT THE CURRENT FLOW IS IN THE SAME DIRECTION TO REINFORCE ITS MAGNETIC FIELDS FOR SMALL VEHICLE DETECTION.
3. EACH LOOP LEAD-IN SHALL BE IDENTIFIED AND PERMANENTLY TAGGED IN THE HANDHOLE. EACH LEAD-IN CABLE TAG SHALL INDICATE THE LOCATION OF THE LOOP, LOOP ROTATION (CLOCKWISE/COUNTERCLOCKWISE), LOOP LEAD-IN DIRECTION (IN OR OUT), LOOP CABLE NUMBER AND LOCATION IN CABINET, AND NUMBER OF TURNS IN THE DETECTOR LOOPS IN WATER PROOF INK AS INDICATED ON THE DISTRICT 1 STANDARD TRAFFIC SIGNAL DESIGN DETAIL. THE CONTRACTOR SHALL MARK LOOP LOCATIONS ON RECORD DRAWINGS AND PRESENT TO THE ENGINEER AFTER FINAL INSPECTION. LOOPS SHALL BE MARKED BY LANE AND LOOP NUMBER. SEE DETAIL BELOW.
4. ALL LOOP CABLE SHALL BE FASTENED WITH PLASTIC TIE WRAP TO THE HANDHOLE HOOKS.
5. IN ASPHALT PAVEMENT, LOOPS SHOULD BE PLACED IN THE BINDER AND DIVEHOLES MARKED AT THE CURB WITH A SAW-CUT. THE SAW-CUT SHALL BE CUT IN ACCORDANCE WITH LOCAL AND E.P.A. DUST CONTROL REQUIREMENTS. DETECTOR LOOP(S) SHALL NOT BE INSTALLED IN WET CONDITIONS AND THE SAW-CUTS MUST BE FREE OF DEBRIS AND RESIDUE SUCH AS DUST AND WATER WHICH IS TO BE ACHIEVED BY THE USE OF COMPRESSED AIR, WIRE BRUSHING AND HEAT DRYING ACCORDING TO SEALANT MANUFACTURER REQUIREMENTS. THE DETECTOR WIRE SHALL BE HELD IN PLACE BY THE USE OF FORM WEDGES. WEDGES SHALL BE SPACED NO MORE THAN 18" (450 mm) APART.
6. LOOP SPLICES SHALL BE SOLDERED USING A SOLDERING IRON. BLOW TORCHES OR OTHER DEVICES WHICH OXIDIZE COPPER CABLE SHALL NOT BE ALLOWED FOR SOLDERING OPERATIONS. SEE DETAIL BELOW RIGHT.
7. PREFORMED DETECTOR LOOPS SHALL BE USED, AS SHOWN ON THE PLANS, WHERE NEW CONCRETE PAVEMENT IS PROPOSED. THE INSTALLATION OF PREFORMED LOOPS SHALL BE IN ACCORDANCE WITH THE DISTRICT 1 SPECIFICATIONS OR AS DIRECTED BY THE ENGINEER.

LOOP LEAD-IN CABLE TAG




- A. LANE 1 IS THE LANE CLOSEST TO THE CENTERLINE OF THE ROADWAY
- B. LOOP #1 IS THE LOOP IN THE LANE CLOSEST TO THE INTERSECTION.
- C. LABEL LOOP CABLE "IN" OR LOOP CABLE "OUT".
- D. LABEL LOOP CABLE CLOCKWISE OR LOOP CABLE COUNTERCLOCKWISE.




DETECTOR LOOP WIRING SCHEMATIC

- LOOPS SHALL BE SPLICED IN SERIES.
- SAW-CUTS SHALL BE A MINIMUM WIDTH OF 5/16" (8 mm).
- SAW-CUT DEPTHS SHALL BE 3" (75 mm). IF IN CONCRETE, THE SAW-CUT DEPTH SHALL BE TO THE TOP OF THE REINFORCEMENT.
- LOOP CORNERS SHALL BE DRILLED WITH A 2" (50 mm) DIAMETER CORE.




DETAIL "A"
LOOP-TO-LOOP SPLICE




DETAIL "B"
LOOP-TO-CONTROLLER SPLICE

TYPE I LOOP



DETAIL "A"
LOOP-TO-LOOP SPLICE



DETAIL "B"
LOOP-TO-CONTROLLER SPLICE


PRE-FORMED LOOP

LOOP DETECTOR SPLICE

- WESTERN UNION SPLICE SOLDERED WITH ROSIN CORE FLUX. ALL EXPOSED SURFACES OF THE SOLDER SHALL BE SMOOTH. THE WESTERN UNION SPLICES SHALL BE STAGGERED.
- WCSMW 30/100 HEAT SHRINK TUBE, MINIMUM LENGTH 3" (75 mm), UNDERWATER GRADE.
- WCS 200/750 HEAT SHRINK TUBE, MINIMUM LENGHT 6" (150 mm), UNDERWATER GRADE.
- NO. 14 2/C TWISTED, SHIELDED CABLE.
- LOOP CONDUCTOR WITH FLEXIBLE PLASTIC TUBE.
- PREFORMED LOOP
- XL POLYOLEFIN 2 CONDUCTOR BREAKOUT SEALS. TYCO CBR-2 OR APPROVED EQUAL

LOOPS NEXT TO SHOULDERS

PROVIDE A PAVEMENT REPLACEMENT
NOTE WHICH SHOULD EQUAL
3' (900 mm) X WIDTH OF
PAVED SHOULDER.




* = (600 mm)

** UNIT DUCT IS TO BE SHOWN ON PLAN SHEETS
BUT SHALL NOT BE INCLUDED IN THE PAY ITEMS.

LEFT TURN LANES WITH MEDIANS
VOLUME DENSITY ("FAR OUT" DETECTION)
ON SAME APPROACH

(PROTECTED / PERMITTED LEFT TURN PHASING)

HANDHOLE LOCATION MAY
VARY DEPENDING ON GEOMETRICS
AND DESIGN OF TRAFFIC SIGNALS.
HEAVY-DUTY HANDHOLES TO BE
USED WHEN THE MEDIAN IS
MOUNTABLE. REFER TO STANDARD
814001 TO ENSURE THAT HANDHOLE
FITS IN MEDIAN.




** UNIT DUCT IS TO BE SHOWN ON PLAN SHEETS
BUT SHALL NOT BE INCLUDED IN THE PAY ITEMS.

NOTE: DUAL LEFT TURNS NOT SHOWN REFER TO
PLAN SHEET FOR DETECTOR LOOP REPLACEMENT


LEFT TURN LANES WITHOUT MEDIANS
VOLUME DENSITY ("FAR OUT" DETECTION)
ON SAME APPROACH

(PROTECTED / PERMITTED LEFT TURN PHASING)




NOTE: DUAL LEFT TURNS NOT SHOWN REFER TO
PLAN SHEET FOR DETECTOR LOOP REPLACEMENT

ARTERIAL-VOLUME DENSITY ("FAR OUT" DETECTION)
CROSS STREET-VOLUME DENSITY ("FAR OUT" DETECTION)



DETAIL 1
N.T.S.

ARTERIAL-VOLUME DENSITY ("FAR OUT" DETECTION)
CROSS STREET-NON VOLUME DENSITY ("UPTIGHT" PRESENCE DETECTION)



DETAIL 2
N.T.S.

NOTES:

VEHICLES LOOP DETECTORS

- * ALL LEAD IN CABLE SHALL BE TWO CONDUCTOR NO. 14 TWISTED, SHIELDED.
- * EACH DETECTOR LOOP SHALL HAVE ITS OWN SAW CUT FROM THE LOOP TO THE EDGE OF PAVEMENT OR TO A HANDHOLE IN THE PAVEMENT.
- * EACH DETECTOR LOOP SHALL HAVE ITS OWN ONE INCH (25 mm) UNIT DUCT BETWEEN THE EDGE OF PAVEMENT AND THE FIRST HANDHOLE OR JUNCTION BOX. EACH UNIT DUCT RUN SHALL BE SHOWN ON THE PLANS BY THE DESIGNER, BUT SHALL NOT BE PAID FOR SEPARATLY. THIS ITEM IS INCIDENTAL TO THE PAY ITEM FOR DETECTOR LOOPS.
- * ONE DIMENSION OF ALL DETECTOR LOOPS SHALL BE SIX FEET (1.8 m)
- * EACH LANE OF NON-LOCKING, PRESENCE DETECTION AND EACH LANE OF A DOUBLE LEFT TURN LANE REQUIRES A SEPARATE INDUCTIVE LOOP DETECTOR AND LEAD IN CABLE.
- * WHEN NON-LOCKING, PRESENCE DETECTION IS USED, MORE THAN ONE LOOP PER LANE IS REQUIRED BEHIND THE STOP BAR (i.e. 1-1/2, 1-3/4, 2).
- * WHEN SYSTEM LOOPS ARE REQUIRED ON AN APPROACH OF AN INTERSECTION, THE LOOPS USED FOR VOLUME DENSITY AND INTERSECTION TIMING SHALL ALSO BE USED AS SYSTEM DETECTORS. EACH ONE OF THESE TYPE OF LOOPS REQUIRES A SEPARATE TWO CONDUCTOR NO. 14 TWISTED SHIELDED CABLE AND A SEPARATE INDUCTIVE LOOP DETECTOR WHEN NEW CONTROLLERS ARE UTILIZED. THE DESIGNER SHALL LABEL THESE TYPES OF LOOPS AS "INTERSECTION AND SAMPLING (SYSTEM) DETECTORS" ON THE SIGNAL LAYOUT, THE INTERCONNECT PLAN AND THE SYSTEM CABLE PLAN. WHEN AN EXISTING CONTROLLER IS UTILIZED FOR THIS TYPE OF DETECTION, THE PAY ITEM "INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT" SHOULD BE USED.

PLACEMENT OF DETECTORS

THE FOLLOWING FIGURES REPRESENT THE MOST COMMON DETECTOR LOOP LOCATIONS AND SIZES. ADJUSTMENTS WILL BE NECESSARY FOR SPECIFIC GEOMETRIC CONSIDERATIONS.

LOCATIONS AND DEMENSIONS OF DETECTOR LOOPS ARE REQUIRED ON ALL SIGNAL LAYOUT PLAN SHEETS.

"FAR OUT" DETECTION REFERS TO LOCKING, PRESENCE TYPE DETECTION LOCATED IN THRU LANES, RIGHT TURN LANES, AND RIGHT TURN LANE TAPER AREAS (IF APPLICABLE), USUALLY 250' (75 m) IN ADVANCE OF STOP BARS. "UPTIGHT" DETECTION REFERS TO NON-LOCKING PRESENCE TYPE DETECTION LOCATED IN ALL LANES AND 10'-15' (3.0 m-4.5 m) BEHIND THE CROSSING STREET'S EDGE OF PAVEMENT EXTENDED.

NOTE:

ALL DETAILS AND NOTES SHOWN ARE FROM THE I.D.O.T. DISTRICT 1 TRAFFIC SIGNAL DESIGN GUIDELINES DATED JANUARY 1995

THIS DRAWING HAS BEEN PREPARED TO ASSIST THE RESIDENT ENGINEER FOR ALL ROADWAY RESURFACING OR S.M.A.R.T. PROJECTS WHERE THE DIMENSIONS ARE NOT SHOWN ON THE PLANS AND THE FINAL LOCATIONS FOR CROSSWALKS OR STOP BARS ARE NOT DETERMINED.

FILE NAME =	USER NAME = Bilgrami	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT 1 – DETECTOR LOOP INSTALLATION				F.A.U.	SECTION	COUNTY	TOTAL	SHEET
p:\11\084EBID\INTEG\Illinois.gov\PI\DOT\Documents\DOT Offices\District 1\Projects\DI032\Bilgrami\Design\DistStd.dgn		CHECKED -	REVISED -		DETAILS FOR ROADWAY RESURFACING				RTE.			SHEETS	NO.
		CHECKED - R.K.F.	REVISED -		1453	(78-1&78-3)RS-2		COOK	54	54			
PLOT SCALE = 100.0000' / in.		DATE -	REVISED -		TS-07				CONTRACT NO. 62F74				
PLOT DATE = 3/23/2018					SCALE: NONE		SHEET NO. 1 OF 1 SHEETS	STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			