

SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
						80% FEDERAL 20% STATE		100% LOCAL
						ROADWAY 0004 URBAN	SIGNALS 0021 URBAN	ROADWAY 0004 URBAN
		20101000	TEMPORARY FENCE	FOOT	115			
		20200100	EARTH EXCAVATION	CU YD	239	239		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	38	38		
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	226	226		
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,895	1,895		
*		25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5		
*		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36		
*		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36		
*		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36		
*		25100630	EROSION CONTROL BLANKET	SQ YD	2,085	2,085		
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40	40		
*		28000400	PERIMETER EROSION BARRIER	FOOT	1,137	1,137		
		28000510	INLET FILTERS	EACH	7	7		
	S	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	38	38		
	S	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	902	902		
		31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	101	101		
		35501322	HOT-MIX ASPHALT BASE COURSE, 9 1/2"	SQ YD	349	349		
		35600714	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/2"	SQ YD	308	308		
		40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	3,351	297		3,054
		40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3		
		40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	283	28		255
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	487			487
		40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	659	65		594
	S	X4060004	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, N80	TON	659	65		594
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	9	9		
		40800025	BITUMINOUS MATERIALS (PRIME COAT)	POUND	218	218		
		40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	44	44		
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	745	745		
		42400800	DETECTABLE WARNINGS	SQ FT	77	77		
		44000100	PAVEMENT REMOVAL	SQ YD	202	202		
		44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	6,007			6,007
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	973	973		
		44000600	SIDEWALK REMOVAL	SQ FT	205	205		

FILE NAME: \\s11\projects\2017\102518 - Kirk at Pine\Bids\KAP\Drawings\20170604-SQS.dwg

WBK engineering
 WBK ENGINEERING, LLC
 116 WEST MAIN STREET, SUITE 201
 ST. CHARLES, ILLINOIS 60134
 (630) 448-7755

USER NAME = bpoctorrif	DESIGNED - RMS	REVISED - 5/15/2018
PLOT SCALE = 1:2	DRAWN - RMS	REVISED
PLOT DATE = 5/15/2018	CHECKED - MNB	E E
	DATE - 3/14/2018	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**KIRK AT PINE INTERSECTION IMPROVEMENTS
SUMMARY OF QUANTITIES**

SCALE: SHEET 1 OF 4 SHEETS STA. TO STA.

FAP RTE. 360	SECTION 15-00342-01-CH	COUNTY KANE	TOTAL SHEETS 42	SHEET NO. 3
ILLINOIS FED. AID PROJECT X			CONTRACT NO. 61E75	