

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL	90% FED 10% STATE	
				SAFETY	
				0021	RURAL
20400800	FURNISHED EXCAVATION	CU YD	189		189
48101200	AGGREGATE SHOULDERS, TYPE B	TON	280.9		280.9
50104000	BRIDGE RAIL REMOVAL	FOOT	726		726
50900200	STEEL RAILING, TYPE 2399	FOOT	500		500
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	400		400
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	5725.5		5725.5
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	4750.5		4750.5
63000052	WEAK POST GUARDRAIL ATTACHED TO CULVERT CASE III	FOOT	271.9		271.9
63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	37.5		37.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4		4
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2		2
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	29		29
63200310	GUARDRAIL REMOVAL	FOOT	11943		11943

• SPECIALTY ITEM

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL	90% FED 10% STATE	
				SAFETY	
				0021	RURAL
67100100	MOBILIZATION	L SUM	1		1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1		1
70100350	TRAFFIC CONTROL AND PROTECTION, STANDARD 701101	EACH	3		3
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	29		29
78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	160		160
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	400		400
Ø Z0076600	TRAINEES	HOUR	500		500
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500		500

• SPECIALTY ITEM

Ø 0042

1 REV. 6-8-2018

MODEL: Default
FILE NAME: p:\p\p\01_norveg\p\lin.com\HISDOT\Documents\1710403\p\182013\W03\CAD_Summary\076L05-sh1-500.dgn

USER NAME = jepetitbone	DESIGNED -	REVISED -
PLOT SCALE = 300.0000" / in.	DRAWN -	REVISED -
PLOT DATE = 5/3/2018	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. - RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	DIST 8 GUARDRAIL 2018-3	***	14	3
			CONTRACT NO. 76L05	
ILLINOIS FED. AID PROJECT			*** CALHOUN JERSEY MADISON	

* VARIOUS
** VARIOUS
*** CALHOUN JERSEY MADISON

GUARDRAIL SCHEDULE

LOCATION NUMBER	COUNTY	ROUTE	LOCATION	LATITUDE	LONGITUDE	BRIDGE RAIL REMOVAL	GUARDRAIL REMOVAL	SPBGR, TYPE A, 6' POSTS	SPBGR, TYPE A, 9' POSTS	WEAK POST GUARDRAIL ATTACHED TO CULVERT CASE III	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 6A	FURNISHED EXCAVATION	AGGREGATE SHOULDER S, TYPE B	GUARDRAIL REFLECTORS, TYPE A	TERMINAL MARKER - DIRECT APPLIED	
						FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	CU YD	TON	EACH	EACH	
1	CALHOUN	IL -96	N side of IL-96, 725' W of IL Bridge 007-0028	39.294343	-90.72120818		200	200.0				2				21.0	15.2	4	2	
2	CALHOUN	IL -96	Culvert 007-2427	39.29338136	-90.69014379		175	138.0			37.5	2				21.0	12.1	4	2	
3	CALHOUN	IL -96	N side of IL-96, Culvert 007-2417	39.29675609	-90.62794022		88	50.0				2				21.0	4.5	4	2	
4	JERSEY	IL 16	E side of IL-16, 60' N of IL Bridge 042-0005	39.12105951	-90.56305479	70	100	50.0		81.25		1				10.5	5.1	4	1	
			W side of IL-16, 220' N of IL Bridge 042-0005	39.12146327	-90.56318622	70	239	225.0		81.25		1					10.5	13.9	5	1
5	JERSEY	IL 100	E side of IL-100, 125' N of IL Bridge 042-0010	39.10583512	-90.56071526	42	150	100.0		53.13		1				10.5	7.6	4	1	
6	JERSEY	IL 100	E side of IL-100, IL Bridge 042-0012	39.07603828	-90.55589048	250	95		25.0			1			2	10.5	3.5	4	1	
			W side of IL-100, 185' N of IL Bridge 042-0012	39.07632419	-90.55599212	250	225		138.0				1			1	10.5	5.7	4	1
			W side of IL-100, 80' S of IL Bridge 042-0012	39.07489209	-90.55613723		205			50.0				2			1	10.5	3.5	4
7	MADISON	I-55	250' S of New Douglas Rd	38.96612253	-89.75184318		2189	2125.0				2					112.5	28	2	
8	MADISON	IL 143	S side of IL-143, 25' W of Kiowa St	38.81324793	-89.93877618	44	76	100.0		56.25		2				10.5	7.6	4	2	
9	MADISON	IL 3	20' N of Amoco Cutoff	38.85277231	-90.10356989		100	37.5				1	1					4	1	
10	MADISON	IL 3	150' N of Buckmaster Ln	38.9191476	-90.16744599		319		262.5			1	1			10.5	32.8	5	1	
11	MADISON	IL 3	10' N of Curvey St	38.92378407	-90.18628186		588		537.5			1	1				7.6	8	1	
12	MADISON	IL 3	Grovelin St	38.92409406	-90.18838582		875	212.5	500.0			3	1			10.5	11.1	11	3	
13	MADISON	US 67	1000' N of 9th St	38.89899357	-90.18527406		960		862.5			1		1		10.5	24.0	12	1	
14	MADISON	US 67	10' S of College Ave	38.90546476	-90.17668056		2569		2375.0			1		1				31	1	
15	MADISON	US 67	1500' S of Godfrey Rd	38.92937717	-90.18800179		1250	1150.0				2				10.5	7.0	16	2	
			800' S of Godfrey Rd	38.92941766	-90.18830004		1540	1337.5					2				10.5	7.2	4	2
TOTAL						726	11943	5725.5	4750.5	271.88	37.5	29	4	2	4	189	280.9	160	29	



TRAFFIC CONTROL SCHEDULE

LOCATION NUMBER	TRAFFIC CONTROL STANDARD						
	701101	701201	701421	401456	701501	701601	701701
1		X					
2		X					
3		X					
4		X					
5		X					
6		X					
7				X			
8					X		
9						X	X
10	X		X				
11	X		X				X
12	X		X				X
13		X					
14				X			
15		X					

CONCRETE MEDIAN SCHEDULE

LOCATION NUMBER	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN SURFACE REMOVAL
	SQ FT	SQ FT
9	400	400
TOTAL	400	400

STEEL RAILING

LOCATION NUMBER	STEEL RAILING, TYPE 2399
	FOOT
6	500
TOTAL	500

REV. 6-8-2018

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	DIST 8 GUARDRAIL 2018-3	***	14	4
CONTRACT NO. 76L05				

* VARIOUS
** VARIOUS
*** CALHOUN JERSEY MADISON

MODEL: Default
FILE: Model - 201809101 - harrish@illinois.gov
Documents: 1710403-2182015W03CAD_Sheets030976L05-shc-schedule.dgn