

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		COOK	17	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 44917

CODE NO.	ITEM	UNIT	TOTAL
XX004486	ASCLEPIAS TUBEROSA, 1-GALLON	EACH	41
XX004490	ECHINACEA PURPUREA 'MAGNUS', 1-GALLON	EACH	25
K0030397	PERENNIAL PLANTS, EUPATORIUM PURPUREUM, (PURPLE JOE PYE WEED), 1-GALLON	EACH	70
K0030399	PERENNIAL PLANTS, PANICUM VIRGATUM "SHENANDOAH", (SHENANDOAH SWITCH GRASS), 1-GALLON	EACH	190
K1004466	PERENNIAL PLANTS, RUDBECKIA SUBTOMENTOSA (SWEET BLACK EYED SUSAN), 1-GALLON	EACH	76
K0030428	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS, (PRAIRIE DROPSEED), 1-GALLON	EACH	23
K1005481	SHREDDED BARK MULCH 3"	SQ YD	1810
X0323185	DUCTILE IRON WATER MAIN TEE, 6" x 6"	EACH	1
X4066412	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N30	TON	70
X4066760	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N30	TON	35
XX003544	DUCTILE IRON WATER MAIN FITTINGS, 6", 90 DEGREE BEND	EACH	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
X0325417	GATE, SPECIAL 14'	EACH	1
X0325418	GATE, SPECIAL 28'	EACH	1
XX002982	GATE VALVES 6"	EACH	1
X0325419	BALL VALVES 2"	EACH	1
X0325420	INSTALL FURNISHED SIGNS	EACH	4
X0325421	STONE SURFACE SPECIAL	SQ YD	4800
X0325422	DUCTILE IRON WATER MAIN FITTINGS, 6", 11/4 DEGREE BEND	EACH	1
X0325423	DUCTILE IRON WATER MAIN 6" (SPECIAL)	FOOT	10
X0325424	INLET SPECIAL WITH SPECIAL GRATE	EACH	1
X0325425	REMOVE AND RESET POWER POLE	EACH	1

* SPECIAL PROVISION

TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
LOCATION	UNIT
NORTH OF ADMINISTRATION BUILDING AT FENCE	20
TOTAL	20

TREE REMOVAL ACRES	
LOCATION	ACRE
NORTH FENCE LINE	0.17
EAST FENCE LINE	0.21
WEST FENCE LINE	0.04
NORTHEAST CORNER ADMINISTRATION BUILDING	0.03
TOTAL	0.45

PERIMETER EROSION BARRIER	
LOCATION	FOOT
SOUTHEAST CORNER OF PROPERTY	342
SOUTH SIDE PROPERTY LINE	308
WEST SIDE PROPERTY LINE	886
NORTH SIDE PROPERTY LINE	64
TOTAL	1,600

INLET AND PIPE PROTECTION	
LOCATION	EACH
WEST SIDE ADMINISTRATION BUILDING	5
EAST SIDE REAR ERECTING SHOPS (EXIST. SS MH)	1
EAST SIDE REAR ERECTING SHOPS (TRANSFER PIT)	1
TOTAL	7

AGGREGATE BASE COURSE, TYPE A	
LOCATION	TON
WALKWAY AREA	860
TOTAL	860

DRIVEWAY PAVEMENT REMOVAL	
LOCATION	SQ YD
SOUTH COTTAGE GROVE (80' SOUTH MAIN ENTRANCE)	32
SOUTH COTTAGE GROVE (MAINTENANCE TO ADMIN. BLDG.)	43
TOTAL	75

SIDEWALK REMOVAL	
LOCATION	SQ FT
SOUTH COTTAGE GROVE AT MAIN ENTRANCE	1,795
WATERMAIN LINE AT COTTAGE GROVE	82
NORTH FACTORY BUILDING	93
TOTAL	1,970

GATE, SPECIAL 14'	
LOCATION	EACH
SERVICE DRIVE - NORTHEAST CORNER ADMINISTRATION BUILDING	1
TOTAL	1

GATE, SPECIAL 28'	
LOCATION	EACH
SERVICE DRIVE AT SOUTH SIDE REAR ERECTING SHOPS	1
TOTAL	1

STONE SURFACE SPECIAL	
LOCATION	SQ YD
WEST OF REAR ERECTING SHOPS	396
EAST OF ADMINISTRATION BUILDING	185
SOUTHEAST REAR ERECTING SHOPS	340
WEST PROPERTY LINE	280
MAIN PATHWAY (EXCAVATED AREA)	3,599
TOTAL	4,800

EARTH WORK TABLE			
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION (SPECIAL)	TOPSOIL FURNISH & PLACE, 4"
	CU YD	CU YD	SQ YD
PATHWAY OTHER THAN CONCRETE	755		
TRANSFER PIT		50	
SOUTHEAST PROPERTY CORNER			980
NORTH OF NORTH FACTORY BUILDING	150		470
WEST OF NORTH FACTORY BUILDING	90		1,090
NEW WATERMAIN			30
TOTAL	995	50	2,570

TRENCH BACKFILL	
LOCATION	SQ YD
TAP IN STREET	30
SIDEWALK AT STREET	16
SIDEWALK AT BUILDING	16
NEW 10' STONE SURFACE	22
INSIDE BUILDING	11
PATHWAY BEHIND RES BUILDING	5
TOTAL	100

PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	
LOCATION	SQ FT
6" WATERMAIN AT COTTAGE GROVE	80
6" WATERMAIN AT NORTH FACTORY	95
TOTAL	175

SEEDING TABLE							
LOCATION	SEEDING CLASS 1 (SPECIAL)	SEEDING CLASS 4 (SPECIAL)	SEEDING CLASS 5 (SPECIAL)	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 1
SOUTHWEST CORNER OF SITE; NORTH, EAST AND WEST SIDE ADMINISTRATION BUILDING	1.7						
NORTH, SOUTH, EAST AND WEST PROPERTY LINES		0.9					
WEST PROPERTY LINE			0.4				
SEEDING, CLASS 1 (SPECIAL) AREA				153	153	153	3.4
SEEDING, CLASS 4 (SPECIAL) AREA				81	81	81	1.8
SEEDING, CLASS 5 (SPECIAL) AREA				36	36	36	0.8
TOTAL	1.7	0.9	0.4	270	270	270	6.0

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY AND SCHEDULE OF QUANTITIES IDOT / IHPA PULLMAN STATE HISTORIC SITE
NAME	DATE	

SCALE: VERT. _____
HORIZ. _____
DATE: 11/08/05

DRAWN BY: DJM
CHECKED BY: PJM