



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 8, 2006

SUBJECT: FAP Route 351  
Project F-0351 (015)  
Section 3277B  
Cook County  
Contract No. 62206  
Item No. 135, June 16, 2006 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page iii of the Table of Contents to the Special Provisions.
2. Revised page 142 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine  
Engineer of Design  
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; Estimates; Design & Environment File

TBW:MS:jc

REINFORCEMENT BARS (BDE) ..... 122  
SEEDING AND SODDING (BDE)..... 124  
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)..... 126  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 131  
TEMPORARY CONCRETE BARRIER (BDE) ..... 132  
TEMPORARY EROSION CONTROL (BDE) ..... 134  
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) ..... 135  
TRAINING SPECIAL PROVISIONS ..... 136  
WEIGHT CONTROL DEFICIENCY DEDUCTION..... 138  
WORK ZONE TRAFFIC CONTROL (BDE) ..... 139  
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) ..... 140  
STEEL COST ADJUSTMENT (BDE) (RETURN WITH BID)..... 142

Revised 06/08/2006

Delete the fourth paragraph of Article 702.05(a) of the Standard Specifications.

Revise the sixth paragraph of Article 702.05(a) of the Standard Specifications to read:

“When the work operations exceed four days, all signs shall be post mounted unless the signs are located on the pavement or define a moving or intermittent operation. When approved by the Engineer, a temporary sign stand may be used to support a sign at 1.2 m (5 ft) minimum where posts are impractical. Longitudinal dimensions shown on the plans for the placement of signs may be increased up to 30 m (100 ft) to avoid obstacles, hazards or to improve sight distance, when approved by the Engineer. “ROAD CONSTRUCTION AHEAD” signs will also be required on side roads located within the limits of the mainline “ROAD CONSTRUCTION AHEAD” signs.”

Delete all references to “Type 1A barricades” and “wing barricades” throughout Section 702 of the Standard Specifications.

### **STEEL COST ADJUSTMENT (BDE) (RETURN WITH BID)**

Effective: April 2, 2004

Revised: July 1, 2004

Description. At the bidder’s option, a steel cost adjustment will be made to provide additional compensation to the Contractor or a credit to the Department for fluctuations in steel prices. The bidder must indicate on the attached form whether or not steel cost adjustments will be part of this contract. This attached form shall be submitted with the bid. Failure to submit the form shall make this contract exempt of steel cost adjustments.

Types of Steel Products. An adjustment will be made for fluctuations in the cost of steel used in the manufacture of the following items:

- Metal Piling (excluding temporary sheet piling)
- Structural Steel
- Reinforcing Steel

Other steel materials such as dowel bars, tie bars, mesh reinforcement, guardrail, steel traffic signal and light poles, towers and mast arms, metal railings (excluding wire fence), frames and grates, and other miscellaneous items will be subject to a steel cost adjustment when the pay item they are used in has a contract value of \$10,000 or greater.

Documentation. Sufficient documentation shall be furnished to the Engineer to verify the following:

Revised 06/08/2006