

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
20200100	EARTH EXCAVATION	CU YD	250	250					
20800150	TRENCH BACKFILL	CU YD	50	50					
28100105	STONE RIPRAP, CLASS A3	SQ YD	20	20					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14					
40600300	AGGREGATE (PRIME COAT)	TON	70	70					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	360	360					
42001300	PROTECTIVE COAT	SQ YD	920	920					
44000111	BITUMINOUS REMOVAL OVER PATCHES 2 3/4"	SQ YD	2280	2280					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2750	2750					
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	115	115					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	100	100					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	510	510					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	615	615					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1205	1205					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	60	60					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1					
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1					
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1					
55039700	STORM SEWERS TO BE CLEANED	FOOT	2000	2000					
10323381	STORM SEWERS (WATER MAIN REQUIREMENTS)	FOOT	205	205					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	530	530					
55101200	STORM SEWER REMOVAL 24"	FOOT	6	6					
55101600	STORM SEWER REMOVAL 36"	FOOT	6	6					

SUMMARY OF QUANTITIES			100% STATE URBAN TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
60201330	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 23 FRAME AND GRATE	EACH	5	5					
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	7	7					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	12	12					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	26	26					
60500040	REMOVING MANHOLES	EACH	3	3					
60500050	REMOVING CATCH BASINS	EACH	6	6					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6010	6010					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17200	17200					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	485	485					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	316	316					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6460	6460					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17200	17200					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	685	685					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	316	316					

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 FAP 112 - IL 53  
 CATON FARM RD. TO IL 7 (THEODORE ST.)  
 PLOT DATE: 3/29/2006

3/29/2006