

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3578	1327B	COOK	108	3
STA. 1503+19.73		TO STA. 1528+17.76		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES		UNIT	URBAN TOTAL QTY.	CONSTRUCTION TYPE CODE								
				80% FED 20% STATE			100% VILLAGE OF ORLAND PARK		35% FED 9% STATE 56% VILLAGE			
				ROADWAY 1000-2A	BRIDGE AT US RTE 45 X271-2A	RET. WALL Y007	BRIDGE AT US RTE 45 X271-2A	ROADWAY 1000-2A	RET. WALL Y007	BRIDGE AT US RTE 45 X231-2A		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24	24								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	24								
20101000	TEMPORARY FENCE	FOOT	1750	1750								
20200100	EARTH EXCAVATION	CU YD	5953	5287				666				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3186	1384	1802							
20400800	FURNISHED EXCAVATION	CU YD	25279	18718				6561				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	151		151							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	2713		2632		81					
20800150	TRENCH BACKFILL	CU YD	627.4	229.0				398.4				
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	16500	16500								
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	7920	7920								
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	150	150								
* 25000210	SEEDING CLASS 2A	ACRE	1.5	1.5								
* 25000310	SEEDING CLASS 4	ACRE	1.7	1.7								
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	155	155								
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	155	155								
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	155	155								
* 25100630	EROSION CONTROL BLANKET	SQ YD	32125	32125								
* 25200110	SODDING, SALT TOLERANT	SQ YD	1575	1575								
* 25200200	SUPPLEMENTAL WATERING	UNIT	35	35								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	330	330								

SUMMARY OF QUANTITIES		UNIT	URBAN TOTAL QTY.	CONSTRUCTION TYPE CODE								
				80% FED 20% STATE			100% VILLAGE OF ORLAND PARK		35% FED 9% STATE 56% VILLAGE			
				ROADWAY 1000-2A	BRIDGE AT US RTE 45 X271-2A	RET. WALL Y007	BRIDGE AT US RTE 45 X271-2A	ROADWAY 1000-2A	RET. WALL Y007	BRIDGE AT US RTE 45 X231-2A		
28000300	TEMPORARY DITCH CHECKS	EACH	21	21								
28000400	PERIMETER EROSION BARRIER	FOOT	4950	4950								
28000510	INLET FILTERS	EACH	33	30				3				
28100105	STONE RIPRAP, CLASS A3	SQ YD	211	211								
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	650	650								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.5	2.9				0.6				
40600300	AGGREGATE (PRIME COAT)	TON	16.0	13.0				3.0				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1								
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	58	58								
42001300	PROTECTIVE COAT	SQ YD	2092	2092								
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	260	260								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	255	255								
44000100	PAVEMENT REMOVAL	SQ YD	2025	2025								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	380	380								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	190	190								
44000700	APPROACH SLAB REMOVAL	SQ YD	180	180								
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	560	560								
44100100	PAVEMENT REPLACEMENT	SQ YD	200	200								
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3464	2231				1233				
48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	135	135								
48202400	BITUMINOUS SHOULDER SUPERPAVE 6"	SQ YD	381	381								

PLOT DATE = 03/09/06  
 FILE NAME = MAIL 7\Proposed\Plans\Cover\SD04.dgn  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.U. ROUTE 3576 (IL. ROUTE 7)

IL. ROUTE 7  
 SUMMARY OF QUANTITIES

SCALE: VERT.      DRAWN BY BCD  
 HORIZ.              CHECKED BY SLR  
 DATE: MAR. 10, 2006