

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2004-025 RS	LAKE	116	5
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
* PARK ROADS		IDNR File No. 2-03-025	D91-191-04	

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

STATION	OFFSET (FT.)	SIDE	UNIT	TYPE
NORTH POINT DR. 28+73.95	178.95	RT	12	RED PINE
29+10.45	31.01	LT	15	TREMBLING ASPEN
30+79.60	33.34	LT	6x2	TREMBLING ASPEN
35+65.99	30.55	LT	7	TREMBLING ASPEN
36+78.14	32.3	LT	8x3	TREMBLING ASPEN
37+39.16	29.55	LT	7	TREMBLING ASPEN
45+25.19	31.42	LT	12	TREMBLING ASPEN
45+65.41	27.37	LT	15	COTTONWOOD
CHARTER BASIN/ YACHT CLUB 21+86.70	26.93	RT	6	SEE NOTE BELOW
21+97.30	33.69	RT	6	SEE NOTE BELOW
21+99.47	44.73	RT	12	SEE NOTE BELOW
BOAT LAUNCH RD. 1+00.58	21.09	RT	6	BUCKTHORN
TOTAL =				134 UNITS

X2010300 TREE REMOVAL (UNDER 6 UNITS DIAMETER)

STATION	OFFSET (FT.)	SIDE	UNIT	TYPE
7TH ST. 38+10	0.1	LT	2	SHADBLOW SERVICEBERRY
CHARTER BASIN/ YACHT CLUB 0+14.52	19.71	LT	2x3	QUAKING ASPEN
21+65.80	28.89	RT	3	MULBERRY
21+80.81	29.18	RT	5	SEE NOTE BELOW
21+83.52	33.06	RT	2	UNKNOWN
21+85.91	38.83	RT	4	SEE NOTE BELOW
21+86.24	32.09	RT	4	SEE NOTE BELOW
21+90.18	35.30	RT	4	SEE NOTE BELOW
21+93.27	44.67	RT	2	UNKNOWN
21+93.97	28.11	RT	5	SEE NOTE BELOW
21+94.99	39.36	RT	5	SEE NOTE BELOW
NORTH POINT DR. 3+58	41	LT	4	TREMBLING ASPEN
7+46	137	RT	2	FLOWERING CRABAPPLE
16+13.52	197.44	RT	2	SHADBLOW SERVICEBERRY
18+20	61	RT	1.5	HACKBERRY
18+27.54	252.47	RT	2	FLOWERING CRABAPPLE
26+10.46	70.81	LT	2	RED CHOKEBERRY
26+19.10	78.17	LT	2	JUNE BERRY
26+22.69	82.13	LT	2	JUNE BERRY
31+31.12	33.05	LT	4x3	TREMBLING ASPEN
34+21.50	63.45	LT	2x2	HACKBERRY
34+47.32	74.16	LT	2x6	BOXELDER
26+21	120	LT	2	BLACK ALDER
34+90	35	LT	5	HACKBERRY
38+25	30	RT	1x3	MULBERRY
42+72.29	33.02	LT	2	ASH
42+73.42	30.12	LT	1	ASH
TOTAL =				100.5 UNITS

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU. YDS.)	UNSUITABLE MATERIAL (CU. YDS.)	EARTH EXCAVATION MINUS UNSUITABLE & ADJUSTED (SHRINKAGE 5%) (CU. YDS.)	EMBANKMENT (CU. YDS.)	EARTH WORK BALANCE SURPLUS (+) OR SHORTAGE (-) (CU. YDS.)
NEW PARKING LOT	2420.0	854.2	1487.5	1107.0	+380.5
BOAT LAUNCH ROAD RECONSTRUCTION	2390.0	24.7	2247.0	107.0	+2140.0
YACHT CLUB/CHARTER BASIN ROAD RECONSTRUCTION	2327.0	13.7	2197.6	163.0	+2034.6
JUNCTION CHAMBER	0.0	5.0	0.0	0.0	+5.0
RECONSTRUCTION OF BOAT DOCKING PADS	293.0	0.0	278.4	7.0	+271.4
WIDENING AND RESURFACING (W/ AGG. SHOULDER REM.)	948.0	246.2	666.7	4.0	+662.7
TOTAL	8378.0	1143.8	6877.2	1388.0	+5489.2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PARK ROADS
 ILLINOIS BEACH STATE PARK
 NORTH POINT MARINA
 SCHEDULE OF QUANTITIES

SCALE: _____
 DATE _____

DRAWN BY: CDT
 CHECKED BY: _____

PLOT DATE = 1/2/2006
 FILE NAME = c:\p\j\m\p\34482\design\32
 REFERENCE = BR54