

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1576	2121 RS-2	COOK	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT 62846

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN	PARKING		
				100% STATE	100% CITY		
				1000-2A	Y025		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.5	14.5	5		
40800030	AGGREGATE (PRIME COAT)	TON	98	69.9	28.1		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	13.5	1.5		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1000	1000			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	20	20			
44000119	BITUMINOUS REMOVAL OVER PATCHES 4 3/4"	SQ YD	600	600			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	900	900			
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	730	730			
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	730	730			
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	973	973			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	102	102			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6000	6000			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	550	550			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	22000	22000			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1000	1000			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	300	300			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	550	550			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22000	22000			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	300	300			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	4138	3112	1026		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN	PARKING		
				100% STATE	100% CITY		
				1000-2A	Y025		
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	2075	1562	513		
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	48668	36568	12100		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 3/31/2006

3/31/2006 2:42:38 PM User: jay...