

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000	BRIDGE SFTY-2A			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7				
40600300	AGGREGATE (PRIME COAT)	TON	35	35				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	150	150				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	270	270				
42001300	PROTECTIVE COAT	SQ YD	2405	540	1865			
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	4500	4500				
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	1580	1580				
44000900	BITUMINOUS CONCRETE REMOVAL	SQ YD	585		585			
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	1865		1865			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250				
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	700	700				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	550	550				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	175	175				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	400	400				
50300260	BRIDGE DECK GROOVING	SQ YD	1860	1860				
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	24		24			
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	970		970			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6990		6990			
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	24		24			
55039700	STORM SEWERS TO BE CLEANED	FOOT	456	456				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2				
60260100	INLETS TO BE ADJUSTED	EACH	6	6				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	7	7				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3				

* SPECIALITY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000	BRIDGE SFTY-2A			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3700	3700				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	175	175				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8000	8000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1230	1230				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	70	70				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	170	170				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	250	250				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5410	5410				
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	715		715			
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	715		715			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140	140				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7200	7200				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1120	1120				
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	70	70				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. 3520: CROSS POINT ROAD
SUMMARY OF QUANTITIES
PLOT DATE: 3/23/2006

Rev. 6-5-06

3/23/2006