

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000	BRIDGE SFTY-2A			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	250	250				
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	800	800				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	288	288				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	55	55				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	683	683				
X0320887	POLYMER CONCRETE	CU FT	20		20			
X0321744	SILICONE JOINT SEALER, 2"	FOOT	281		281			
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	234		234			
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1865		1865			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154.2	154.2				
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	10	10				
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	1200	1150	50			
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	470	470				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	775	750	25			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	13000	13000				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1			
X7030125	TEMPORARY PAVEMENT MARKING, LINE 4", TYPE 3, SPECIAL	FOOT	6300	6300				
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	32		32			
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	2450		2450			
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	2		2			
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	63		63			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	19	19				
⊙ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1			
⊙ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1			

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000	BRIDGE SFTY-2A			
Z0037620	PAVEMENT RELIEF JOINT, REMOVE AND REPLACE	SQ FT	416		416			
Z0047300	PROTECTIVE SHIELD	SQ YD	1015		1015			

* SPECIALITY ITEM
⊙ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. 3520: GROSS POINT ROAD
SUMMARY OF QUANTITIES

Rev. 6-5-06

PLOT DATE: 3/24/2006