

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
880	12 RS-9	LAKE	14	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62922

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SE 120 O. SK. HWY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	7	7					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1					
40600300	AGGREGATE (PRIME COAT)	TON	6	6					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	55	55					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	20	20					
42001300	PROTECTIVE COAT	SQ YD	12	12					
44000116	BITUMINOUS REMOVAL OVER PATCHES 4"	SQ YD	85	85					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	45	45					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	35	35					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	25	25					
55039700	STORM SEWERS TO BE CLEANED	FOOT	50	50					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	670	670					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1935	1935					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1010	1010					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1735	1735					
*78002110	PREFORMED PLASTIC PAVEMENT MARKING TYPE A - LINE 4"	FOOT	260	260					
*78002180	PREFORMED PLASTIC PAVEMENT MARKING TYPE A - LINE 24"	FOOT	70	70					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SE 120 O. SK. HWY 1000					
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	220	220					
X4066765	LEVELING BINDER (MACHINE METHOD) SUPERPAVE, N50	TON	110	110					
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	2615	2615					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1					

\* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
S.E. IL. 120 OLD SKOKIE HIGHWAY  
SOUTH CHESTNUT AVE TO KNIGHT AVE  
SUMMARY OF QUANTITIES

PLOT DATE: 4/3/2006

4/3/2006 10:00 AM