

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FEDERAL								
				20 % STATE		15% STATE / 5% CITY	25%STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD		
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY		
				I000	J000	Y031-1F	Y046	SFTY-1B	Y031-3D	Y060		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	926	926								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	35	35								
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	2								
50300225	CONCRETE STRUCTURES	CU YD	48		48							
50800105	REINFORCEMENT BARS	POUND	<b>9,090</b>		<b>9,090</b>							
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	150		150							
51000305	PIPE HANDRAIL, SPECIAL	FOOT	70	70								
54002020	EXPANSION BOLTS 3/4 INCH	EACH	22		22							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		1							
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	83	83								
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	192	192								
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	472	472								
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	90	90								
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	446	446								
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	166	166								
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	47	47								
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	97	97								
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	80	80								
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	161	161								
550A2620	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 48"	FOOT	116	116								

- SPECIALITY ITEM
- + NON PARTICIPATING ITEM

PLOT DATE = Mon Apr 03 11:49:07 2006  
 FILE NAME = C:\projects\20050802\885802.dwg  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = jrdemhd