

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
142	40-M	WINNEBAGO	165	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FEDERAL								
				20% STATE		15% STATE / 5% CITY	25% STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD		
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY		
				I000	J000	Y031-1F	Y046	SFTY-1B	Y031-3D	Y060		
60500060	REMOVING INLETS	EACH	18	18								
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6.0		6.0							
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,835		1,835							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,551		4,551							
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	286		286							
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	202		202							
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8,055		8,055							
60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SQ FT	4,379		4,379							
60624600	CORRUGATED MEDIAN	SQ FT	833		833							
* 63200310	GUARDRAIL REMOVAL	FOOT	254	254								
* 66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	80	80								
* 66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2								
* 66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	2	2								
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,442	2,442								
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1								
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2								
* 66901000	BACKFILL PLUGS	CU.YD.	75	75								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15								
67100100	MOBILIZATION	L SUM	1	1								

* SPECIALITY ITEM
 + NON PARTICIPATING ITEM

PLOT DATE = Mon Apr 03 13:26:32 2006
 FILE NAME = C:\projects\200602\urban02.dgn
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = jordanid