

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	9
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FEDERAL													
				20% STATE		15% STATE / 5% CITY	25% STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD							
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY							
				I000	J000	Y031-1F	Y046	SFTY-1B	Y031-3D	Y060							
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4			4											
• 82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1			1											
• 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1											
• 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,275			1,275											
• 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,311			1,311											
• 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,399			2,399											
• 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	913			913											
• 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	107			107											
• 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2			2											
• 87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1			1											
• 87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1			1											
• 87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1			1											
• 87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1			1											
• 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6			6											
• 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3			3											
• 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	28			28											
• 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	29.5			29.5											
• 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10			10											
• A2001814	TREE, ACER SACCHARUM GREEN MOUNTAIN (GREEN MOUNTAIN SUGAR MAPLE), 1-3/4" CALIPER BALLED AND BURLAPPED	EACH	5	5													
• A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5													

- SPECIALITY ITEM
- + NON PARTICIPATING ITEM

PLT DATE = Mon Apr 03 11:49:08 2006
 FILE NAME = C:\Programs\AutoCAD\2006\14800200.dgn
 PLOT SCALE = 0.000000 / IN.
 USER NAME = jordannd