

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
T42	40-M	WINNEBAGO	165	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL							
				20 % STATE		15% STATE / 5% CITY	25%STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD	
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY	
				I000	J000	Y031-1F	Y046	SFTY-1B	Y031-3D	Y060	
• X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2					
• X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8			8					
• X8801395	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2			2					
• X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2			2					
• X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2			2					
• X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	2			2					
• X8880010	ADA PEDESTRIAN PUSH-BUTTON	EACH	6			6					
XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	119	119							
XX002943	CONCRETE FOUNDATION SPECIAL	EACH	8	8							
• XX003162	EMERGENCY VEHICLE PRIORITY SYSTEM DETECTOR UNIT	EACH	1							1	
• XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1			1					
• XX003167	STREET NAME SIGN MAST ARM MOUNTED (INSTALL ONLY)	EACH	4			4					
XX004900	TURF REINFORCEMENT MAT	SQ YD	506	506							
• XX006241	GATE VALVE AND BOX 8"	EACH	1	1							
XX146400	STORM SEWER REMOVAL	FOOT	1,978	1,978							
+ Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	60	60							
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1							
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1							
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1							
Z0007604	BUILDING REMOVAL NO. 4	L SUM	1	1							

• SPECIALITY ITEM
+ NON PARTICIPATING ITEM

PLOT DATE = Mon Apr 03 11:45:00 2006
FILE NAME = C:\projects\228002\050002\cur.dgn
PLOT SCALE = 50.0000' / IN.
USER NAME = jordanhd