

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FEDERAL								
				20 % STATE		15% STATE / 5% CITY	25%STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD		
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY		
				I000	J000	Y031-1F	Y046	SFTY-1B	Y031-3D	Y060		
Z0007605	BUILDING REMOVAL NO. 5	L SUM	1	1								
Z0007606	BUILDING REMOVAL NO. 6	L SUM	1	1								
Z0007607	BUILDING REMOVAL NO. 7	L SUM	1	1								
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
• Z0024476	FLEXIBLE DELINEATOR MAINTENANCE	EACH	50	50								
• Z0024478	FLEXIBLE DELINEATORS	EACH	100	100								
Z0028415	GEOTECHNICAL REINFORCEMENT	SO YD	17,044	17,044								
Z0041700	PLUG EXISTING STORM SEWERS	EACH	2	2								
• X0325339	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	1,295			1,295						
• B2002412	TREE, MAGNOLIA LILIFLORA (JANE MAGNOLIA), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5								
• X0325340	FIRE HYDRANT WITH 6" VALVE AND VALVE BOX	EACH	4	4								
• X0325341	BUTTERFLY VALVE AND BOX 16"	EACH	2	2								
• X0325342	CONNECT TO EXISTING WATERMAIN 16"	EACH	2	2								
• X0325343	COPPER SERVICE PUSHED 1"	EACH	3	3								
• X0325344	COPPER SERVICE 2"	EACH	1	1								

- SPECIALITY ITEM
- + NON PARTICIPATING ITEM

PLOT DATE = Mon Apr 03 11:49:00 2006
 FILE NAME = C:\p0\proj\12090602\ad00002a.rvt.dgn
 PLOT SCALE = 3/8"=1'-0"
 USER NAME = jordan